




DANKS

CATALOGUE

JOHN DANKS & SON Pty. Ltd., 324-330 Pitt Street, Sydney TELEPHONE
M 6505 (18 lines)
AND AT 391-403 BOURKE STREET, MELBOURNE

Special Notice

Owing to conditions brought about by the war, prices quoted in the enclosed list must not be regarded as firm but are a true indication of values existing when this list was printed and must be treated as approximately only.

Under these circumstances our customers are requested to select their requirements carefully and on receipt of enquiries we will be pleased to submit a firm quotation for current stock at lowest prices.

Catalogue Issue No.1, May, 1941



(INCORPORATED IN VICTORIA)

Established in 1859

324-330 PITT STREET, SYDNEY

Telephone: M 6505 (18 lines)

and at

391-403 BOURKE STREET, MELBOURNE, C.1

Telephone: M 2381 (12 lines)

Manufacturers of:—

**"DASPYL" ENGINEERS' AND PLUMBERS'
BRASSWARE**

Consisting of

COCKS — VALVES — BRASS — GUNMETAL — IRON — LEAD — AND SPECIAL
ALLOY FITTINGS FOR STEAM — WATER — GAS — AIR — OIL AND
SEWERAGE SERVICES — WINDMILLS, PUMPS, ETC.

Distributors of:—

BUILDERS' HARDWARE
ELECTRICAL ACCESSORIES, APPLIANCES AND FITTINGS
DOMESTIC HARDWARE
ENGINEERS' AND PLUMBERS' BRASSWARE
GALVANISED IRON AND PRODUCTS
HEATING AND HOT WATER BOILERS AND RADIATORS
MOTOR ACCESSORIES
PAINTS, COLOURS AND OILS
SANITARY WARE AND FITTINGS
SEWERAGE FITTINGS
TOOLS —
CARPENTERS, ENGINEERS, GARDENERS AND PLUMBERS, ETC.
WALLPAPERS

SECTIONAL INDEX

	Pages		Pages
Bathroom Fittings and Sanitary Ware	47-57	Heating Boilers and Radiators	80-84
Builders' Hardware	109-125	Motor Accessories	126-133
Domestic Hardware—Stoves, Grates, etc.	85-94	Paints and Painters' Requirements	97-105
Electrical Accessories, Fittings, etc.	58-79	Pumps, Windmills, etc.	35-46
Engineers' and Plumbers' Supplies	1-34	Roofing, Floor Coverings, etc.	107-108
		Tools, General	134-193
		Wallpapers	95-96



WHILST this General Catalogue aims to be as complete a guide as possible to the goods stocked and sold by John Danks & Son Pty. Ltd., it obviously cannot deal fully with our many activities or show more than a small selection of our most popular products.

It does, however, give you some idea of how completely we are equipped to satisfy your every need in the many sections of our business listed on the following pages.

Perhaps even more important to you than the large selection of goods we stock, is the surety we give you of their undoubted value.

Since 1859 the House of Danks has enjoyed an enviable reputation for highest quality and keen values, and this reputation is upheld by every article we make or sell.

HOW TO ORDER

When ordering from this Catalogue, it is sufficient to quote the NUMBERS ONLY of the items wanted. DO NOT CUT out the illustration to send to us. This is quite unnecessary and only mutilates your copy of the Catalogue and detracts from its value to you.

ALWAYS KEEP THE CATALOGUE HANDY. You will find it of great help in ensuring the goods you require are of the highest quality and keenest value.

ALL QUOTATIONS ARE SUBJECT TO FLUCTUATION WITHOUT NOTICE.

Business Terms.—Terms to regular customers are—payment in the month following that in which the goods are invoiced. Orders from persons with whom we have no previous dealings should be accompanied by cash, bank draft, postal note or money order. If it is desired to open an account in our books, at least two approved business references should be supplied. Kind attention to the foregoing will obviate delay and inconvenience.

STAMPED PARCELS PREPAID RATES

A consignment note must be tendered for each parcel handed to the Commissioner for despatch by rail. Each parcel will be charged for separately.

The following are the rates for the conveyance of Parcels by Passenger Trains on the New South Wales Government Railways:—

Not exceeding Miles—	NOT EXCEEDING																				Each addi- tional 28 lb. or part thereof
	1 lb.	2 lb.	3 lb.	4 lb.	5 lb.	6 lb.	7 lb.	8 lb.	9 lb.	10 lb.	11 lb.	12 lb.	13 lb.	14 lb.	28 lb.	42 lb.	56 lb.	84 lb.	112 lb.		
	d.	d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.		
25	5	5	0 5	0 6	0 6	0 6	0 6	0 6	0 6	0 6	0 6	0 6	0 6	0 6	1 0	1 3	1 8	2 2	2 6	0 8	
50	6	6	0 6	0 6	0 6	0 6	0 6	0 8	0 8	0 8	0 8	0 8	0 8	0 8	1 3	1 9	2 4	3 1	4 0	1 1	
75	6	6	0 6	0 8	0 8	0 8	0 8	1 1	1 1	1 1	1 1	1 1	1 1	1 1	1 8	2 4	3 0	4 3	5 4	1 3	
100	6	7	0 8	1 0	1 0	1 2	1 2	1 3	1 3	1 3	1 3	1 3	1 3	1 3	2 2	2 11	3 8	5 4	6 7	1 8	
125	6	8	0 10	1 0	1 2	1 3	1 4	1 7	1 7	1 7	1 7	1 7	1 7	1 7	2 6	3 6	4 6	6 5	8 0	1 10	
150	6	9	1 0	1 0	1 3	1 4	1 5	1 9	1 9	1 9	1 9	1 9	1 9	1 9	2 11	4 0	5 2	7 2	9 2	2 3	
175	6	9	1 0	1 0	1 3	1 6	1 9	2 0	2 3	2 3	2 3	2 3	2 3	2 3	3 4	4 7	5 9	8 3	10 5	2 6	
200	6	9	1 0	1 0	1 3	1 6	1 9	2 0	2 3	2 6	2 9	2 9	2 9	2 9	3 8	5 2	6 6	9 2	11 7	2 11	
250	6	9	1 0	1 0	1 3	1 6	1 9	2 0	2 3	2 6	2 9	2 11	2 11	2 11	4 7	6 4	8 0	10 8	13 7	3 4	
300	6	9	1 0	1 0	1 3	1 6	1 9	2 0	2 3	2 6	2 9	3 4	3 4	3 4	5 4	7 0	8 8	12 1	15 4	3 6	
350	6	9	1 0	1 0	1 3	1 6	1 9	2 0	2 3	2 6	2 9	3 8	3 8	3 8	5 9	8 0	9 6	12 10	16 3	3 8	
400	6	9	1 0	1 0	1 3	1 6	1 9	2 0	2 3	2 6	2 9	3 10	3 10	3 10	6 4	8 8	10 5	13 7	16 11	4 1	
500	6	9	1 0	1 0	1 3	1 6	1 9	2 0	2 3	2 6	2 9	3 11	3 11	3 11	7 0	9 11	12 1	15 3	18 8	4 7	
600	6	9	1 0	1 0	1 3	1 6	1 9	2 0	2 3	2 6	2 9	4 1	4 1	4 1	8 0	10 8	13 7	16 11	20 4	5 1	
700	6	9	1 0	1 0	1 3	1 6	1 9	2 0	2 3	2 6	2 9	4 7	4 7	4 7	8 3	11 7	15 0	18 8	22 0	5 4	
850	6	9	1 0	1 0	1 3	1 6	1 9	2 0	2 3	2 6	2 9	5 9	5 9	5 9	9 2	13 4	16 6	21 1	23 11	5 9	
Over 850	6	9	1 0	1 0	1 3	1 6	1 9	2 0	2 3	2 6	2 9	7 5	7 5	7 5	10 5	15 8	19 1	23 11	27 4	6 7	

Any package exceeding 336 lb. in weight or 36 cubic feet in measurement will not be accepted for conveyance by passenger train except by special arrangement.

When freight is not prepaid, 25 per cent. additional (not to exceed 1/-) will be charged. The minimum charge for a parcel when freight is not prepaid will be 7d.

To compute the through rate from Sydney to a Victorian station, the rate from Sydney to Victorian Border (Albury or Tocumwal, as the case may be) must be added to the rate in Victoria.

PARCEL RATES FROM SYDNEY TO VICTORIAN BORDER

Sydney to Victorian Border:

WEIGHT IN LBS.

Every additional 28 lbs. or part thereof

Via ALBURY—

1	2	3	4	5	6	7	8	9	10	11	12	13	14	21	28	35	42	49	56	84	112
s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.
0 9	1 0	1 3	1 3	1 6	1 9	2 0	2 6	2 9	3 0	3 3	4 4	4 4	4 4	6 11	6 11	9 4	9 4	11 1	11 1	14 5	17 10

Via TOCUMWAL—

0 6	0 9	1 0	1 0	1 3	1 6	1 9	2 0	2 3	2 6	2 9	3 11	3 11	3 11	7 0	7 0	9 11	9 11	12 1	12 1	15 3	18 8	4 7
-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	------	------	------	-----	-----	------	------	------	------	------	------	-----

PARCELS BY PASSENGER TRAINS

The following are the rates for the conveyance of Parcels by Passenger Trains on the Victorian Government Railways:—

STAMPED PARCELS (PREPAID) RATES

Mile not exceeding

LBS. WEIGHT NOT EXCEEDING—

Every additional 28 lbs. or part thereof

1	2	3	4	5	6	7	8	9	10	11	12	13	14	21	28	35	42	49	56	84	112
s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.
25	0 6	0 8	0 8	0 8	0 8	0 8	0 8	0 9	0 9	0 9	0 10	0 10	0 10	0 11	0 11	0 11	1 2	1 4	1 6	1 8	2 2
50	0 6	0 8	0 8	0 9	0 9	0 10	0 10	0 11	1 0	1 1	1 1	1 2	1 2	1 2	1 4	1 5	1 10	2 2	2 7	3 0	3 9
75	0 6	0 8	0 8	0 9	0 10	0 11	1 0	1 1	1 2	1 3	1 3	1 4	1 5	1 5	1 8	1 11	2 2	2 5	3 0	3 5	5 0
101	0 6	0 8	0 8	0 10	1 0	1 1	1 2	1 3	1 3	1 5	1 5	1 5	1 8	1 11	2 2	2 5	3 1	3 9	4 5	5 0	6 3
125	0 6	0 9	0 11	1 0	1 2	1 3	1 4	1 5	1 5	1 8	1 8	1 8	1 11	2 2	2 5	3 1	3 9	4 5	5 0	6 3	7 4
150	0 6	0 9	0 11	1 1	1 3	1 4	1 5	1 6	1 8	1 8	1 11	1 11	2 2	2 5	3 1	3 9	4 9	5 10	6 8	8 4	9 10
175	0 6	0 9	0 11	1 1	1 3	1 4	1 5	1 8	1 8	1 11	2 2	2 2	2 10	3 1	3 5	3 9	4 9	5 10	6 8	8 4	9 10
200	0 6	0 9	1 0	1 2	1 3	1 4	1 5	1 8	1 11	2 2	2 2	2 5	3 1	3 7	3 10	4 1	5 2	6 3	7 4	8 4	10 5
250	0 6	0 9	1 0	1 2	1 3	1 5	1 8	1 11	2 2	2 5	2 9	3 7	4 1	4 5	4 11	5 5	6 8	7 11	8 11	9 10	12 5
300	0 6	0 9	1 0	1 3	1 5	1 8	1 11	2 2	2 2	2 5	2 9	3 7	4 1	4 5	5 0	5 5	6 8	7 11	8 11	9 10	12 5
350	0 6	0 9	1 0	1 3	1 5	1 8	1 11	2 2	2 5	2 9	3 0	4 5	5 0	5 5	5 9	6 8	7 8	9 1	10 4	11 6	14 6
400	0 6	0 9	1 0	1 3	1 5	1 8	1 11	2 2	2 5	2 9	3 0	4 5	5 0	5 5	5 9	6 8	7 8	9 1	10 4	11 6	14 6
450	0 6	0 9	1 0	1 3	1 6	1 9	2 0	2 3	2 6	2 9	3 0	4 5	5 3	5 9	6 8	7 4	8 11	10 5	11 10	13 3	16 5
500	0 6	0 9	1 0	1 3	1 6	1 9	2 0	2 3	2 6	2 9	3 0	4 5	5 3	6 0	6 8	7 4	8 11	10 5	11 10	13 3	16 5
550	0 6	0 9	1 0	1 3	1 6	1 9	2 0	2 3	2 6	2 9	3 0	4 5	5 6	6 4	7 1	7 9	9 3	10 9	12 5	14 0	17 7
600	0 6	0 9	1 0	1 3	1 6	1 9	2 0	2 3	2 6	2 9	3 0	4 5	6 0	6 8	7 5	8 2	9 11	11 7	13 3	14 11	18 2

PARCELS POST

Postage rates for the delivery within the Commonwealth of parcels by parcels post are as follows:—

PARCEL RATES

Within the Commonwealth—

Scale	Destination	1 lb.	2 lbs.	3 lbs.	5 lbs.	8 lbs.	11 lbs.
1.	Within 30 miles of office of posting	6d.	9d.	1/-	1/3	1/6	1/9
2.	Within State, but beyond 30 miles	9d.	1/-	1/3	1/6	2/-	2/9
3.	Adjoining States—See local Post Office	1/-	1/6	2/-	2/6	3/6	5/-
4.	Elsewhere within the Commonwealth	1/3	2/-	2/9	3/6	5/-	7/3

Scale 4 rates apply to parcels for Papua and New Guinea and for the following islands:—New Britain, New Ireland, New Hanover, Admiralty, Bougainville and Buka.

Beyond the Commonwealth.—See Post Office Guide.

PACKET POST

The postage rate on small packets of merchandise, patterns, samples, etc., weighing up to one pound, is: — To anywhere in Commonwealth, 1d. for every 2 ozs. or fraction thereof.

CASH ON DELIVERY POST

Cash on delivery post is a system under which the Postal Department, upon delivery of a parcel on which the prescribed fee has been paid, collects from the Addressee a sum of money fixed by the sender and pays to the sender the amount collected.

The system is designed to meet the requirements of persons who wish to pay on delivery for goods sent to them.

The fee or commission charged by the Postal Department includes the Registration Fee of 3d., and is an addition to the ordinary postage rates.

The Postal Department's scale of charges is as follows:—

Amount to be collected on parcel	Commission
Not exceeding 10/-	9d.
Over 10/-, but not exceeding £1	1/-
Over £1, but not exceeding 30/-	1/3
Over 30/-, but not exceeding £2	1/6
Each additional £1 or fraction thereof	3d. add.

ORDER FORM

Telegrams: Danks, Sydney
Telephones: M 6505 (18 lines)

JOHN DANKS & SON PTY. LTD.

324-330 PITT STREET
SYDNEY

Name.....

Address.....

Forward To.....

By.....

Date.....

Cheque

Money
Order.....

Postal Notes.....

[illegible]

NOTE.—Orders from persons with whom we have no previous dealings should be accompanied by cash, bank draft, postal note or money order. If it is desired to open an account in our books, at least two approved business references should be supplied. Kind attention to the foregoing will obviate delay and inconvenience.

5403

885155b

ORDER FORM

Telegrams: Danks, Sydney
Telephones: M 6505 (18 lines)

JOHN DANKS & SON PTY. LTD.

324-330 PITT STREET
SYDNEY

Name.....

Address.....

Forward To.....

By.....

Date.....

Cheque

Money
Order.....Postal
Notes.....[illegible]

NOTE.—Orders from persons with whom we have no previous dealings should be accompanied by cash, bank draft, postal note or money order. If it is desired to open an account in our books, at least two approved business references should be supplied. Kind attention to the foregoing will obviate delay and inconvenience.

Telegrams: Danks, Sydney
Telephones: M 6505 (18 lines)

324-330 PITT STREET
SYDNEY

<i>Name</i> <i>Address</i> <i>Forward To</i> <i>By</i>	<i>Date</i>..... Cheque..... Money Order..... Postal Notes.....
---	--

[illegible]

NOTE.—Orders from persons with whom we have no previous dealings should be accompanied by cash bank draft, postal note or money order. If it is desired to open an account in our books, at least two approved business references should be supplied. Kind attention to the foregoing will obviate delay and inconvenience.

400

2 N. 1. 1. 1.

100

700

ORDER FORM

Telegrams: Danks, Sydney
Telephones: M 6505 (18 lines)

JOHN DANKS & SON PTY. LTD.

324-330 PITT STREET
SYDNEY

Date.....

Name.....

Address.....

Forward To.....

Bd.....

Cheque

Money
Order.....

Postal
Notes.....

[illegible]

NOTE.—Orders from persons with whom we have no previous dealings should be accompanied by cash bank draft, postal note or money order. If it is desired to open an account in our books, at least two approved business references should be supplied. Kind attention to the foregoing will obviate delay and inconvenience.

THE UNIVERSITY OF CHICAGO

1900-1901

NAME		DEGREE		CLASS		GPA		HONORS	

CATALOGUE "A" OF "DASPYL"

Engineers' and Plumbers' Supplies



**High Pressure Bib
Cocks for Iron Pipe
A1.**

HEAVY WEIGHT FULLWAY
Australian Commonwealth
Standard

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 2".

**High Pressure Bib
Cocks for Iron Pipe
A2.**

MEDIUM WEIGHT

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ",
2".



**High Pressure Bib
Cocks, Special
A3.**

Made in two sizes: $\frac{3}{4}$ " and $\frac{1}{2}$ ".
This cock has been designed to pre-
vent the illegal use of hose where
Water Meters are not fixed, and has
been adopted by the Melbourne and
Metropolitan Board of Works and
other corporations.

**High Pressure
Hose Cocks for
Iron Pipe
A4.**

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ",
2", 2 $\frac{1}{2}$ ", 3".
Supplied without nuts and
tails, unless otherwise speci-
fied.




**High Pressure
Inverted Hose
Cock
A5.**

SYDNEY PATTERN

Made in $\frac{1}{2}$ " only.

Supplied without nuts and tails, unless otherwise
specified.



**High Pressure
Inverted Hose Cock
A6.**

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ",
2".

**High Pressure Stop
Cocks for Iron Pipe
A7.**

MEDIUM WEIGHT

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ",
2", 2 $\frac{1}{2}$ ", 3".



**High Pressure Stop
Cocks for Iron Pipe
A8.**



MEDIUM WEIGHT

Male and Female—Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".
Used extensively with Cap and
Lining for connecting up Bath
Heaters.

**High Pressure Stop
Cocks for Iron Pipe
A9.**

HEAVY WEIGHT FULLWAY
Australian Commonwealth
Standard

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 2".
2 $\frac{1}{2}$ ", 3".



**High Pressure
Cistern Stop Cock
A10.**


Sydney Water Board
Standard

With Straight Union as il-
lustrated or with $\frac{3}{4}$ " Elbow
Union
Made in $\frac{1}{4}$ " inlet $\times$ $\frac{3}{4}$ "
outlet, and $\frac{3}{4}$ " inlet $\times$ $\frac{1}{2}$ "
outlet.

**High Pressure Stop
Cocks with Union
A11.**

HEAVY WEIGHT FULLWAY
Australian Commonwealth
Standard

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".



**High Pressure
Shower Cocks
A12.**

Sydney Water Board Standard


Rough or Polished

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 2".

**High Pressure Ferrule
Stop Cocks for Lead
Pipe
A13.**

MEDIUM WEIGHT

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 2".




**High Pressure
Ferrule Stop Cocks
for Iron Pipe
A14.**

M.M.B.W. Standard
HEAVY WITH FULL
WATERWAY

Outlet Tail Piece, Screwed
Gas Thread
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ",
2".

Also with Plain Tail Piece
for Lead



**High Pressure Ferrule
Stop Cocks with Male
Ends for Iron Pipe
A15.**


Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 2"



**High Pressure Ferrule
Stop Cocks with Male
Ends for Iron Pipe
A16.**

Perth Pattern

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1"



**High Pressure Ferrule
Stop Cocks with Bend
Screwed Male for Iron
A17.**

M.M.B.W. Standard

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 2".

**High Pressure Main
Stop Cocks for Iron
Pipe with Elbow
Union
A18.**

Sizes: $\frac{1}{2}$ ", 1", $\frac{3}{4}$ " $\times$ 1",
1" $\times$ 1 $\frac{1}{2}$ ".



**High Pressure Main
Stop Cock for Lead
Pipe
A19.**

Sydney Water Board Standard
Sizes: $\frac{3}{4}$ ", 1".

FOR HIGHEST QUALITY INSIST ON "DASPYL"



**High Pressure Path
Cocks for Iron Pipe
A30.**

Sydney Water Board Standard
Sizes: $\frac{1}{2}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 2", 2 $\frac{1}{2}$ ", 3".
Also made in 1" inlet x $\frac{3}{4}$ " outlet, both Female ends.

**Press Button Spring Shower Cocks
A31.**



NON-CONCUSSIVE
Sydney Water Board
Standard

Used largely for showers
in Swimming Baths, etc.
Self-closing prevents waste
of water.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".


**Press Button
Spring Bib
Cock
A32.**

NON-CONCUSSIVE
Sydney Water Board
Standard
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".



**Right Angle Press Button
Spring Cock A33.**

Size: $\frac{3}{4}$ ".



To stop the jarring in
Water Pipes when these
Spring Cocks are shut
off, use Concussion Jet
fixed in the supply pipe
about a foot away from
the Spring Cock, it effectually stops all jar or
hammer in the main.

**Bib Pattern Press
Button Spring Cock
A34.**

Size: $\frac{3}{4}$ ".

Also with long nose as used for
State Schools.
Size: $\frac{3}{4}$ ".



**Press Button
Spring Bib
Cock
A35.**

Size: $\frac{1}{2}$ ".




**Tank Cocks
Brass Levers
G.M. Plugs
A36.**

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ", 1", 1 $\frac{1}{2}$ ",
1 $\frac{3}{4}$ ", 2".



**Walpole Self-Closing Cock
A37.**



With Lever Specially
Suitable for Tanks
Size: $\frac{3}{4}$ "



The Walpole Cock is
fitted with an adjustable
spring, which closes the
tap the moment the
handle is released, thereby
minimizing the risk of water running to waste.
The handle is also removable.

**Walpole Self-
Closing Cock with
T-Head
A38.**

Size: $\frac{3}{4}$ ".



**Tank Cock
(Straight)
A39.**

With Union for Hose.
Sizes: $\frac{1}{2}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ",
2", 2 $\frac{1}{2}$ ", 3".
Also with Solid Plugs
Tinned for Milk, etc.



**Right Angle Non-
Leak Tank Cock
A40.**

Size: $\frac{3}{4}$ ".



**Low Pressure
Stop Cocks
A45.**

Male and Female for Iron
Tee Heads, G.M. Plugs.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".



**Low Pressure
Stop Cocks
A46.**

Tee Heads, Brass Plugs,
Female both ends.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".

**Danks' Patent Non-
Leak Tank or Low
Pressure Tap
A47.**

Supersedes the Plug Tap.
Has leather washer, which
can be renewed in a few
minutes.
Size: $\frac{3}{4}$ ".



**Low Pressure Bib
Cocks
A48.**

For Iron Tee Heads, G.M.
Plugs.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".




**Lock-Up Tank
Cocks
A49.**

Brass Lever
Size: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".

**Brass Main Cocks
A50.**

FULL ROUND WAY
For Gas Mains and Low
Pressure Water.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ",
2", 2 $\frac{1}{2}$ ", 3", 4".
Also Medium Pattern.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", $\frac{3}{4}$ ", 1".



**Milk
Separator
Cocks
A51.**

The Cock may be had separate from the Pan.
(Nickel Plated)



**Brass Main Cocks
A52.**

With Tee Heads.

FULL ROUND WAY
For Gas Mains and Low Pressure
Water.

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 2".
Also Medium Pattern.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", $\frac{3}{4}$ ", 1".

**Racking Cock
A53.**

Heavy Strapped Pattern
With Grated End.
Size: $\frac{3}{4}$ ".




**Racking Cocks
(Open Ends)
A54.**

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{3}{4}$ ", $\frac{3}{4}$ ", 1".

**Bottling Cocks
A55.**

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{3}{4}$ ", $\frac{3}{4}$ ", 1".



**Straight Tapping
Cocks
A56.**

With Unions.
Made in one size only.

**Milk Cocks (Sydney Pattern)
A57.**

Long Shank. Solid Plug to
conform to Board of Health
Regulations.
Polished Brass or Nickel
Plated.
Size: $\frac{3}{4}$ ", 1".
Stocked by Sydney House
only.




**Milk Cocks
A58.**

Right Angle, Hollow Plug.
Made in Gun Metal, tinned
all over, and to suit Iron or
Lead Pipe.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 2".

**Milk Cocks
A59.**

Male and Female Ends.
With Solid Plug.
Gun Metal Tinned.
Sizes: 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3".



**Milk or Cream
Cocks
A60.**

Gate Pattern.
With Distance Piece
and Flange.
Gun Metal Tinned.
Sizes: 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3".

**Milk or Cream
Cocks
A61.**

Pull-over Slide.
With Distance Piece,
Flange and Lock Nut.
Gun Metal Tinned.
Sizes: 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ ", 2",
2 $\frac{1}{2}$ ", 3".




**Molasses Gate
A62.**

Lock-up Type.
For Treacle, Oil or other
Heavy Liquids.
Sizes: $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ ", 2".


Beautiful Enduring Modern

SIRDAR

DOMESTIC WATER FITTINGS



A20.
Sirdar High Pressure Bib Cocks
Chromium Plated.
Size: $\frac{1}{2}$ ".




A21.
Sirdar High Pressure Toilet Cocks
Chromium Plated.
Size: $\frac{1}{2}$ ".



A22.
Sirdar High Pressure Stop Cocks
Chromium Plated.
Size: $\frac{1}{2}$ ".




A23.
Sirdar High Pressure Stop Cock
With Evertite Union
Chromium Plated.
Size: $\frac{1}{2}$ " Gas to take $\frac{3}{4}$ " Copper Tube.



A24.
Sirdar Concealed Stops
Chromium Plated.
Size: $\frac{1}{2}$ ".
These Stops are for use in tiling work when pipes are to be concealed.



A25.
Sirdar Extension Piece
Chromium Plated.
Size: $\frac{1}{2}$ ".




A26.
Sirdar Swivel Outlet
Chromium Plated.
Size: $\frac{1}{2}$ ".



A27.
Sirdar Fixed Outlet
Chromium Plated.
Size: $\frac{1}{2}$ ".

A28.
Sirdar Basin Set
With Fixed Outlet
Chromium Plated.
Size: $\frac{1}{2}$ ".
Underneath Connections
Made in $\frac{1}{2}$ " Copper Pipe.





ORDER BY NUMBER, DO NOT CUT


Insist on SIRDAR for QUALITY and VALUE

TOILET COCKS**Toilet Cocks****A63.****HEAVY WEIGHT**
Australian Commonwealth
StandardNickel or Chrome Plated. China
Disc marked Hot or Cold.
Also made to Sydney Water
Board Standard.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".**Toilet Cock****A64.****MEDIUM WEIGHT**Nickel or Chrome Plated. China
Disc marked Hot or Cold.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".**Easy Clean Toilet Cocks****A65.****STANDARD PATTERN**Nickel or Chrome Plated. China
Disc marked Hot or Cold.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".**A66.****Press Button Toilet Cock**Australian Commonwealth Standard
Nickel or Chrome Plated. China
Disc marked Hot or Cold.
Made in $\frac{1}{2}$ " only.**Cam-Action Toilet Cock****A67.**Nickel or Chrome Plated. China
Disc marked Hot or Cold.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".

Opens with half a turn and automatically shuts off when hand is removed. A great water saver, very popular for use in hotels, guest houses, etc.

A68. Bib CocksWith Capstan Head
HEAVY WEIGHTAustralian Commonwealth
Standard
Also to Sydney Water Board
Standard.
Nickel or Chrome Plated. China
Disc marked Hot or Cold.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".**Easy Clean Bib Cock****A69.****STANDARD PATTERN**Nickel or Chrome Plated. China
Disc marked Hot or Cold.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".**"DASPYL" means Quality****EASY CLEAN BIB COCK (T-Head)****A70.****STANDARD PATTERN**Nickel or Chrome Plated.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".**Bib Cocks**With Capstan Heads
MEDIUM WEIGHT**A71.**Nickel or Chrome Plated. China
Disc marked Hot or Cold.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".**Cam-Action Bib****A72. Cock**Nickel or Chrome Plated.
China Disc marked Hot or Cold.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".

Opens with half a turn and automatically shuts off when hand is removed. A great water saver and very popular for use in Hotels, Guest Houses, etc.

**A73. Cam-Action Stop Cocks**Nickel or Chrome Plated.
China Disc marked Hot or Cold.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".**EASY CLEAN STOP COCKS****A74.****STANDARD PATTERN**Nickel or Chrome Plated. China
Disc marked Hot or Cold.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".**Easy Clean Stop Cocks (T-Head)****A75.****STANDARD PATTERN**Nickel or Chrome Plated.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".**Easy Clean Stop Cock with Evertite Union****A76. Union****STANDARD PATTERN**Nickel or Chrome Plated. China
Disc marked Hot or Cold
Sizes: $\frac{1}{2}$ " gas to take $\frac{3}{4}$ " copper tube.**A77. Stop Cocks**With Capstan Heads
HEAVY WEIGHTAustralian Commonwealth
StandardAlso to Sydney Water Board
Standard.
Nickel or Chrome Plated. China
Disc marked Hot or Cold.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".**Stop Cocks****A78.**With Capstan Heads
MEDIUM WEIGHTNickel or Chrome Plated. China
Disc marked Hot or Cold.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".**Packed Gland Bib****A79. Cocks**For Iron
Brass Levers.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".**Hot Water Cocks****A80.**Ebony Handles
Quick Action. Polished.
Size: $\frac{1}{2}$ ", $\frac{3}{4}$ ".**Urn Cocks****A81.**Polished Brass with Ebony
Handles
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ", 1".
Can be supplied Nickel
Plated if desired.**Fountain Cocks****A82.**Polished Brass
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ".**Filter Cocks****A83.**With Taper Thread.
Brass Polished
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ".
Also Nickel Plated.**Draw-off Cocks****A84.**

For Kerosene, Oil, etc.

Size: Screwed $\frac{1}{2}$ " Gas.
Finished in plain Brass
or Nickel Plated.**LABORATORY FITTINGS****Laboratory Cock****A85.**

With Flange and Bend

**Laboratory Cock****A86.****Laboratory Cock****A87.**

TREBLE

**Laboratory Cock****A88.**SINGLE
Lever Handle.**DANKS' FOR BATHS AND BATHROOM ACCESSORIES**



**Laboratory
Cock
A89.**

Single Lever Handle.
With Flange.

**Laboratory
Cock
A90.**

Double Right Angle
Lever Handles.
With Flange.



**Laboratory
Cock
A91.**

Double Right Angle
Lever Handles.
Without Flange.

**Laboratory
Cock
A92.**

Double Right Angle.
Without Flange.



**Laboratory
Cock
A93.**


Double Right Angle.
With Flange.

A94. Laboratory Cock

Double
Straight-
Through
Lever
Handles.
With Flange.




HOSPITAL COCKS



**HOT AND COLD
COMBINATION
Treadle Valves
A95.**
Floor Pattern
For use in Hospitals.

**HOT AND COLD
COMBINATION
Treadle Valves
A96.**

Wall Pattern
For use in Hospitals.




**Sanitary Drinking
Faucets
A97.**

Upright with Self-Closing
Valve
Screwed $\frac{1}{2}$ " Gas.
Nickel Plated.

**Press Button
A98.**

Right Angle
Screwed $\frac{1}{2}$ " Gas.
Nickel Plated.

For other patterns of Drinking
Fountains and Faucets, see our
Special Fountain Pamphlet.



BALL COCKS



**Ball
Cock
A99.**

LAMBERT PATTERN
Made in Gun Metal to
4"; above that size in
Cast Iron flanged with
Gun Metal Valves.
This Ball Cock is a
Fullway Type that
works equally well at
either high or low
pressure.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2",
2 $\frac{1}{2}$ ", 3", 4", 5", 6", 7".

**Ball Cocks
A100.**

CROYDEN PATTERN
For High or Low
Pressure.

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1",
1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3",
4".



A111. Ball Cocks

For Closet Cisterns, etc. M.M.B.W. STANDARD
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".




High or Low Pressure

The body of this Ball
Cock is made in two
pieces (see arrow) for the
purpose of getting at the Valve and Valve Seat
easily for any necessary repairs.

The "GILLESPIE" BALL VALVE "DASPYL" MAKE

This Valve is
quick in ac-
tion, and gives
a full flow as
soon as it op-
erates. It occu-
pies less room
in the trough
or tank, as a
six inch ball is
sufficient for
all sizes. No
tools are required for adjustment. All washers can
be changed by the fingers while the pressure is on.
NOTE.—The "Gillespie" Ball Valve requires the
delivery pipe to be of the same size or larger
than the valve.
Sizes: 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ ", 2".



A120.

A121. Booth's Equilibrium Valve

One of the most reliable Ball Cocks, has a full flow
and requires only a short lever and small ball in
all sizes. Sizes: 2" Screwed, 3" and 4" Flanged.
Sydney House only.




A122. Ideal Float Valve

For use on
Horse, Cattle
and Sheep
Troughs.
Low Pressure
Fullway



Will work under the lowest pressure.
Sizes: 1", 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3".

A123. Ball Cocks



BIB PATTERN
High Pressure.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".
The Ball Cock is fit-
ted with a Hot Water
Valve, and is therefore
very suitable for Hot
Water Cisterns, etc.

**Ball Cocks
A124.**

PERTH PATTERN
Size $\frac{1}{2}$ "



UNIONS, BENDS, ETC.

**Straight Ferrule
Union
A125.**



For Lead Pipe
Male Ends, Ground Joint.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ ", 2".
Can also be supplied with tail ribbed for hose.

**Bent Ferrule
Union
A126.**



For Lead Pipe
With Ground Joint.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".

**Bent Ferrules, Brass
A127.**

For Iron Pipe
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".



**Brass Bends
A128.**

As used in Service Connections
of Copper Pipe.
Female both ends.
Approved by Sydney Water
Board.
Sizes: $\frac{1}{2}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ ", 2".



**Brass Bends
A129.**

As used in Service Connections
of Copper Pipe, Male and
Female.
Approved by Sydney Water
Board.
Sizes: $\frac{1}{2}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ ", 2".



**Brass Adaptors
A130.**

For connecting Copper Water
Service Pipes to Main and Stop
Cocks.
Approved by Sydney Water
Board.
Sizes: $\frac{1}{2}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ ", 2", $\frac{3}{4}$ " x
 $\frac{1}{2}$ ", 1" x $\frac{3}{4}$ ", 1 $\frac{1}{2}$ " x 1".



**Straight
Connections
A131.**

For Lead and Iron Male
Ends
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".



**Straight
Connections
A101.**

For Lead and Iron
Female Ends.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".



**Plumbers'
Unions
A132.**

Ground Joint for Lead
Pipe
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".



**Caps and Linings
A133.**

Strong for Water.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ ", 2",
2 $\frac{1}{2}$ ", 3".




**Caps and Linings
A134.**

Gas for Iron.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ ",
2".



Ball Cocks forwarded complete
with Balls unless otherwise specified

DANKS' FOR ALL PLUMBERS' TOOLS AND REQUIREMENTS



**Union for Toilet
A135. Cocks**

Made in 1/2" only.
Stocked by Sydney House
only.

Barrel Unions

A136.

Female for Brass
Sizes: 1/2", 3/4", 1", 1 1/4", 1 1/2", 2".



**Barrel Unions,
Brass
A137.**

Male and Female for Iron.
Sizes: 1/2", 3/4", 1", 1 1/4", 1 1/2", 2".

Also Male and Female for
Brass.
Sizes: 1/2", 3/4", 1", 1 1/4", 1 1/2", 2".



Barrel Unions, Brass

A138.

Female Ends, Ground Joints
Sizes: Gas, 1/2", 3/4", 1", 1 1/4", 1 1/2", 2".



Gas Union

A139.

IRON AND COMPO.
Tinned and Screwed Female
Sizes: 1/2", 3/4", 1", 1 1/4", 1 1/2", 2".



**Brass Main Bushes,
Taper**

A140.

Sizes: 1/2" x 1/2", 1" x 1/2".
A very handy bush for C.I.
Mains when fixing New Services
in Old Tappings.



**Extension Piece
for Bib Cocks**

A141.

Nickel and Chrome
Plated.
Sizes: 1/2" x 2", 1" x 2".
Melb. Pattern Round
Socket End.

Sizes: 1/2" x 2", 3/4" x 2", 1" x 2", 1 1/4" x 2", 1 1/2" x 2", 2" x 2".



**Brass Breeching
Pieces**

A142.

Sizes: 1/2" x 1", 3/4" x 1", 1" x 1", 1 1/4" x 1", 1 1/2" x 1", 2" x 1".

Stocked by Sydney House
only.



Matching Piece

A167.

Sizes: 1/2", 3/4", 1", 1 1/4", 1 1/2", 2" x 1/2".
1", 1" x 1/2".
Other sizes available if required.



**Shower Bath
Valves**

A143.

Sizes: 1 1/2", 1 3/4", 2", 2 1/4", 3".



**Plugs &
Washers**

A144.

M.M.B.W.
Standard
2" Fullway.
Short Pattern for
C.I. Sinks.




**Plugs & Washers
A145.**

M.M.B.W. Standard
Long Pattern for Fireclay Sinks.
Also Sydney Water Board Stan-
dard for Cement Troughs.



**Plugs & Washers
A146.**

Nickel Plated. 2" Fullway for
Enamelled Baths. If required for
1 1/2" waste we can supply a
Reducing Piece.
Made with Brass or Rubber Plugs
as desired.



**Plugs & Washers
A147.**

For Sheet Iron Baths
With Bar Gratings.
Sizes: 1 1/2", 1 3/4", 2", 2 1/4", 3".
Also supplied with Rubber Plugs.



**Plugs & Washers
A148.**

For Troughs, Shallow, Light
Pattern.
Sizes: 1 1/2", 1 3/4", 2".



**Plugs & Washers
A149.**

For Troughs
Deep and Heavy, Square.
Sizes: 1 1/2", 1 3/4", 2", 2 1/4", 3".
1 1/2" and 2" also made M.M.B.W.
Standard Fullway.



**Plugs & Washers
A150.**

For Earthenware Basins
With or Without Overflow.

Sizes: 1 1/2" Way, with O/F.
1 3/4" Way, with O/F.
1 1/2" Way, without O/F.
1 3/4" Way, without O/F.



Also Long Pattern for
Pedestal Basins.

**Trap Screws
A151.**

SQUARE HEAD

Sizes: 1/2", 1", 1 1/4", 1 1/2", 1 3/4",
2", 2 1/4", 3", 4", 5", 6".



**Trap Screws
A152.**

BAR HEAD

Sizes: 1/2", 1", 1 1/4", 1 1/2", 2".



**Copper Shower
A153.**

Nickel & Chrome Plated
Polished Copper. Screw-
ed 1/2", 3/4" & 1" Gas.
Sizes: 6", 7", 8", 9",
10", 12".




**Mixing Shower
A154.**

Nickel Plated
Sizes: 8", 9", 10".



**Ball Jointed Shower
A155.**

Nickel and Chrome Plated
Sizes: 4 1/2", 6".



**Shampoo Spray
A156.**

Nickel Plated
With or without Regula-
ting Screw.

Brass Shampoo Rose

A157.

Nickel Plated



**Shower Arm
A158.**

Nickel or Chrome
Plated




Brass Chain Stays

A159.

Nickel Plated

Also Brass Chain and Ball Chain, Nickel
Plated, for use on Baths and Basins.



**Brass Chandelier
Chain**

A160.

Made in four sizes in Brass
and Nickel Plated. Stocked
in boxes containing 36 ft.



CYANIDE COCKS

Packed Gland Cock


A170.

All iron, flanged.
Sizes: 1 1/2", 1 3/4", 2", 2 1/4", 3", 4".



**Packed Gland Cock
A171.**

For Cyanide.
All Iron Screwed Female
Sizes: 1/2", 3/4", 1", 1 1/4", 1 1/2", 2",
2 1/4", 3", 4".



**Cast Iron Main Cock
A172.**


For Cyanide, etc.
Sizes: 1/2", 3/4", 1", 1 1/4", 1 1/2",
1 3/4", 2", 2 1/4", 3", 4".



**Fullway Gate Valve
A173.**

All Iron, Flanged

Sizes: 2", 2 1/4", 3", 3 1/4", 4",
5", 6".



**Syphon Pot for Gas
Mains**

A174.

2 Quart Screwed.
4 Quart Screwed.
For Cast Iron Main.

DANKS' FOR ALL KINDS OF BUILDERS' HARDWARE



**Easy Clean
Extension Piece
A161.**

Nickel Plated
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".



**Neo Chrome
Extension Piece
A162.**

Size: $\frac{1}{2}$ ".



**Side Outlet
Breeching Piece
A163.**

Size: $\frac{1}{2}$ ".

**Shower Breeching
Pieces
A164.**

WITH UNION

Nickel and Chrome Plated.
Size: $\frac{1}{2}$ ".



**Shower
Breeching Piece
A165.**

Nickel and Chrome
Plated.

Sizes: $\frac{1}{2}$ " with 5"
centres; $\frac{3}{4}$ " with 6"
centres.



**Straight
Breeching
Piece
A166.**

Size: $\frac{1}{2}$ ".



BRAZING METAL Hot Water Fittings


The attention of our clients is particularly called to the following description of Hot Water Fittings to avoid mistakes, as a different standard rules in Melbourne from that in Sydney. The sizes given opposite each article refer to Melbourne Standard only.

Melbourne Standards
Fittings are screwed Gas Standard Threads. The sizes given refer to the outside diameter of the Copper Tube which the fittings suit.

Sydney Standards
All Fittings, $\frac{1}{2}$ " to $1\frac{1}{2}$ ", are screwed Gas, sizes and threads, and work out as follows:—
Outside dia of Copper Tube—
 $\frac{1}{2}$ " 1" 1 $\frac{1}{2}$ " 2" 2 $\frac{1}{2}$ " 3" 4" 6" 8" 10" 12"
will screw $\frac{1}{2}$ " 1" 1 $\frac{1}{2}$ " 2" 2 $\frac{1}{2}$ " 3" 4" 6" 8" 10" 12" gas thread and size.

**Brazing Metal Unions
A185.
MALE AND FEMALE**

Arrow points to loose B.M. Ring for brazing to Tube.
Tube sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ".



**Brazing Metal Unions
A186.**


FEMALE ENDS

Arrow points to loose B.M. Ring for brazing to tube.
Tube sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ".




**Brazing Metal Saddling
Unions
A187.**

Sizes: $\frac{3}{4}$ ", 1".



**Brazing Metal
Nipples
A192.**

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ".



**Brazing Metal
Nipples
HEXAGON CENTRE
A193.**

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ".



**Brazing Metal
Flanged Nuts
A194.**

All screwed in Gas Threads to suit outside diameter of Copper Tube.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ".



**Brazing Metal Tees
A180.**

To suit Copper Tube Outside Diameter.
Size: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ".
If required, screwed 19 threads.



**Brazing Metal
Elbows
A181.**

To suit Copper Tube outside diameter.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ".
If required, screwed 19 threads.



**Brazing Metal Sockets
A182.**

To suit Copper Tube outside diameter.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ".
If required, screwed 19 threads.




**Brazing Metal Tees
With Single Union
A183.**

Fitted with loose B.M. Ring.
All to suit outside diameter of Copper Tube.
Tube sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ".
If necessary, use reducing B.M. Rings.



**Brazing Metal Tees
With Double Unions
A184.**

Fitted with loose B.M. Rings.
All to suit outside diameter of Copper Tube.
Tube Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ".
If necessary, use Reducing B.M. Rings.



**Brazing Metal Unions
A188.**

FEMALE ENDS

All to suit outside diameter of Copper Tube.
Tube sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ".
Obtainable, screwed 19 threads.



**Brazing Metal Unions
A189.**

MALE AND FEMALE

All to suit outside diameter of Copper Tube.
Tube sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ".
Obtainable, screwed 19 threads.



**Brazing Metal Bushes
A190.**

All to suit outside diameter of Copper Tube.
Sizes: $\frac{1}{2}$ " x $\frac{1}{2}$ ", 1" x $\frac{1}{2}$ ", 1" x 1", 1 $\frac{1}{2}$ " x 1", 1 $\frac{1}{2}$ " x $\frac{3}{4}$ ", 1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ " x 2", 2" x 1", 2" x 1 $\frac{1}{2}$ ", 2" x 2", 2" x 2 $\frac{1}{2}$ ".



We also make Bushes, External Gas Thread by Copper Tube sizes.
Obtainable, screwed 19 threads.

**Brazing Metal Socket
Bushes
A191.**

Sizes: $\frac{1}{2}$ " I. x $\frac{1}{2}$ " C., $\frac{3}{4}$ " I. x $\frac{3}{4}$ " C.,
 $\frac{1}{2}$ " I. x 1" C., 1" I. x 1 $\frac{1}{2}$ " C.




The "TITON"

**Compression Coupling
A196.**

The advantage of the "Titon" Compression Coupling over other couplings is its special design, which ensures a perfect joint by simply tightening the nut. No loose rings (to be mislaid) or packing required.

NOTE.—All fittings are screwed Standard Gas Thread, and any end can thus be fitted direct to Wrought Iron pipe Socket, if desired.



**Tee Coupling
A197.**

TREBLE NUT

All Ends for Copper Tube.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ".



"TITON" Tee Coupling A198.

TREBLE NUT REDUCING

All ends for Copper Tube. Sizes:
 $\frac{3}{8}$ " x $\frac{1}{2}$ ", 1" x $\frac{1}{2}$ ", 1" x $\frac{3}{4}$ ", 1 $\frac{1}{2}$ " x $\frac{3}{4}$ "
 $\frac{3}{8}$ ", 1 $\frac{1}{2}$ " x $\frac{3}{4}$ ", 1 $\frac{1}{2}$ " x 1", $\frac{3}{4}$ " x $\frac{1}{2}$ "
 x $\frac{1}{2}$ ", 1" x $\frac{3}{4}$ " x $\frac{3}{4}$ ".

Australian Commonwealth
Standard

Copper Tube suitable for Compression Joints approved by M.M.B.W.

External Diameter Inches	Wall Thickness S.W.G.	Calculated Weight Lb. per lin. ft.
$\frac{3}{8}$	19	0.22
$\frac{1}{2}$	18	0.41
1	18	0.55
1 $\frac{1}{2}$	16	0.92
1 $\frac{1}{2}$	16	1.11
2	16	1.50

Elbow Coupling A199.

DOUBLE NUT



Both ends for Copper Tube.
 Sizes: $\frac{3}{8}$ ", $\frac{1}{2}$ ", 1", 1 $\frac{1}{2}$ ", 2",
 $\frac{3}{8}$ " x $\frac{1}{2}$ ", $\frac{1}{2}$ " Gas Female x $\frac{3}{8}$ "
 Copper Tube, $\frac{3}{8}$ " Gas Female
 x $\frac{3}{8}$ " Copper Tube, $\frac{3}{8}$ " Gas
 Female x 1" Copper Tube,
 $\frac{1}{2}$ " Gas Male x $\frac{1}{2}$ " Copper
 Tube, $\frac{3}{8}$ " Gas Male x $\frac{3}{8}$ " Cop-
 per Tube, $\frac{3}{8}$ " Gas Male x 1"
 Copper Tube.

Straight Coupling A200.

SINGLE NUT

For Copper Tube and Iron Pipe.
 Sizes: $\frac{3}{8}$ " Gas Male x $\frac{1}{2}$ " Copper Tube,
 $\frac{1}{2}$ " Gas Male x $\frac{3}{8}$ " Copper Tube,
 $\frac{3}{8}$ " Gas Male x 1" Copper Tube,
 1" Gas Male x 1 $\frac{1}{2}$ " Copper Tube,
 1 $\frac{1}{2}$ " Gas Male x 1 $\frac{1}{2}$ " Copper Tube,
 1 $\frac{1}{2}$ " Gas Male x 2" Copper Tube,
 $\frac{3}{8}$ " Gas Female x $\frac{1}{2}$ " Copper Tube,
 $\frac{1}{2}$ " Gas Female x $\frac{3}{8}$ " Copper Tube.

Variations in these sizes can be made to specification.




Straight Coupling A220.

DOUBLE NUT

Both ends for Copper Tube.
 Sizes: $\frac{3}{8}$ ", $\frac{1}{2}$ ", 1", 1 $\frac{1}{2}$ ", 2".

Lightning Conductor Tridents A221.




These are made in Copper with four points Platinum tipped, and are the type approved of by the Explosives Department. Copper Wire Rope for same, $\frac{3}{8}$ " diameter or 1 $\frac{1}{2}$ " circumference, and $\frac{1}{2}$ " diameter or 1 $\frac{1}{2}$ " circumference.
 Copper Earthplates, 3 ft. x 3 ft. x 1-16th".

A222.

Copper Hooks for fastening Rope
 Copper Tape, 1" x $\frac{3}{8}$ ".
 Copper Dogs for same.

THE "EVER-TITE" Compression Coupling



A223.

The "Ever-Tite" is a high pressure Compression Coupling for copper tube connections; supplied tested by the M.M.B.W. when required.

All fittings are screwed Standard Gas Thread, and any end can thus be fitted to Wrought Iron Pipe Socket if desired.

Tee Couplings A224.

TREBLE NUT

All ends for Copper Tube.
 Sizes: $\frac{3}{8}$ ", $\frac{1}{2}$ ", 1", 1 $\frac{1}{2}$ ", 2".



Tee Coupling A225.

TREBLE NUT REDUCING

All ends for Copper Tube.
 Sizes: $\frac{3}{8}$ " x $\frac{1}{2}$ " x $\frac{3}{8}$ ", $\frac{1}{2}$ " x $\frac{3}{8}$ " x $\frac{1}{2}$ ",
 1" x $\frac{3}{8}$ " x $\frac{1}{2}$ ", 1" x 1" x $\frac{3}{8}$ ",
 1" x 1" x $\frac{3}{8}$ ", 1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ " x $\frac{3}{8}$ ",
 1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ " x 1".



Elbow Coupling A226.

DOUBLE NUT

Both ends for Copper Tube.
 Sizes: $\frac{3}{8}$ ", $\frac{1}{2}$ ", 1", 1 $\frac{1}{2}$ ", 2".



Straight Coupling A227.

SINGLE NUT

For Copper Tube and Iron Pipe.

Sizes:	$\frac{3}{8}$ "	Gas Male	x	$\frac{1}{2}$ "	Copper Tube
	$\frac{1}{2}$ "	Gas Male	x	$\frac{3}{8}$ "	Copper Tube
	$\frac{3}{8}$ "	Gas Male	x	$\frac{3}{8}$ "	Copper Tube
	$\frac{3}{8}$ "	Gas Male	x	1"	Copper Tube
	1"	Gas Male	x	1"	Copper Tube
	1"	Gas Male	x	1 $\frac{1}{2}$ "	Copper Tube
	1 $\frac{1}{2}$ "	Gas Male	x	1 $\frac{1}{2}$ "	Copper Tube
	1 $\frac{1}{2}$ "	Gas Male	x	1 $\frac{1}{2}$ "	Copper Tube
	2"	Gas Male	x	2"	Copper Tube



Straight Coupling A228.

DOUBLE NUT

Both ends for Copper Tube
 Sizes: $\frac{3}{8}$ ", $\frac{1}{2}$ ", 1", 1 $\frac{1}{2}$ ", 2".



Tee Coupling A229.

For Copper Tube with Iron Pipe Branch.
 Sizes: $\frac{3}{8}$ " I. x $\frac{1}{2}$ " O.
 Sizes: $\frac{1}{2}$ " I. x $\frac{1}{2}$ " O.



Elbow Coupling A230.

Sizes: $\frac{3}{8}$ " Copper x $\frac{1}{2}$ " Iron
 $\frac{1}{2}$ " Copper x $\frac{1}{2}$ " Iron.




Elbow Coupling A231.

Sizes: $\frac{3}{8}$ " Copper x $\frac{1}{2}$ " Iron
 $\frac{1}{2}$ " Copper x $\frac{3}{8}$ " Iron.



BRASS FITTINGS



Brass Vents A232.

Size: 9" x 3".
 Rough, Polished or Plated.

Sydney House only.

Brass Cylinder Plates A233.

Sizes: $\frac{3}{8}$ ", $\frac{1}{2}$ ", 1", 1 $\frac{1}{2}$ ",
 1 $\frac{1}{2}$ ", 2".



Brass Caps A234.

Sizes: $\frac{1}{2}$ " to 2".



Brass N.A.S. Unions A235.

FEMALE

Sizes: $\frac{3}{8}$ " to 2".
 Sydney House only.



Brass N.A.S. Unions A236.

MALE AND FEMALE
 Sizes: $\frac{3}{8}$ " to 2".
 Sydney House only.



Gun Metal N.A.S. Unions A237.

FEMALE AND MALE AND
 FEMALE


Sizes: $\frac{3}{8}$ " to 2".
 Sydney House only.



Garage Swivel A238.

Sizes: $\frac{3}{8}$ ", $\frac{1}{2}$ ", 1".

This fitting, as well as being used for car washing, can be adapted to any use where swivel action is required.



Brass Elbows A239.

FEMALE

Sizes: $\frac{3}{8}$ " to 3".
 Plain and Reducing



Brass Elbows A240.

MALE AND FEMALE
 Sizes: $\frac{3}{8}$ " to 2".



Brass Bends A241.

MALE

Sizes: $\frac{3}{8}$ " to 2"



Brass Bends A242.

MALE AND FEMALE

Sizes: $\frac{3}{8}$ " to 2".
 Brass Bends may also be had in Double Female.



Brass Tees A243.

Straight Through and
 Reducing

Sizes: $\frac{3}{8}$ " up to 4".




Traps, Junctions, Grates, Etc.

Brass Crosses

Straight Through and Reducing
A244.

Sizes: $\frac{1}{2}$ " to 2".



Brass Sockets

A245.

Sizes: $\frac{1}{2}$ " to 3"



Brass Elbows

A246.
WITH LUGS
Size: $\frac{1}{2}$ ".

Brass Hexagon Sockets

A247.

Sizes: $\frac{1}{2}$ " to 3".



Plain Brass Sockets

A248.

Sizes: $\frac{1}{2}$ " to 1"

Brass Nipples

A249.

Sizes: $\frac{1}{2}$ " to 3".



Brass Hexagon Nipples

A250.

Sizes: $\frac{1}{2}$ " to 3".
And reducing sizes.

Brass Hexagon Bushes

A251.

Sizes: $\frac{1}{2}$ " to 3".



Brass Bushes

A252.

Sizes: $\frac{1}{2}$ " to 2"

Gun Metal Cylinder Bosses

A253.

Sizes: Govt. Pattern, $\frac{1}{2}$ " to 2";
Light Pattern, $\frac{1}{2}$ " to 2".



Brass Plugs


A254.
SCREWED GAS

Long Taper (as shown).
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1"; Short: $\frac{1}{2}$ " to 3".
Sydney House size: $\frac{1}{2}$ " up to 4"

Brass Lock Nuts

A255.

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1",
1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 4".



Brass Flanges

A256.

Sizes: $\frac{1}{2}$ " to 3".
Also Brass Flanges.
Table D Sizes: $\frac{1}{2}$ " to 4".
Obtainable from
Sydney House.



Brass Traps

A257.

With Trap Screw
Both Ends Female.
P Pattern.

Sizes: 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3".
Sizes without Trap Screw: 1 $\frac{1}{2}$ ", 2".



Brass Traps

A258.

With Trap Screw

Both Ends Female.
S Pattern.
Sizes: 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ ", 2".



Brass Traps

A259.

With Loose Nut and Trap Screw
Outlet Ends Female.
P Pattern
Sizes: 1 $\frac{1}{2}$ ", 2"



Brass Traps

A260.

With Loose Nut and Trap Screw
Outlet Ends Female.
S Pattern.
Sizes: 1 $\frac{1}{2}$ ", 2".



ORDER BY NUMBER ONLY
DO NOT CUT CATALOGUE

Brass Traps

A261.

With Loose Nuts and Trap
Screws
S Pattern
Sizes: 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ ",
1 $\frac{1}{2}$ " and 2".
Stocked by Sydney House
only.



A262. Brass Traps

With Loose Nuts and Trap Screws
P Pattern
Sizes: 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ ",
1 $\frac{1}{2}$ " and 2".
Stocked by Sydney House only.



Hospital Trap

A263.

With Trap Screw

Specially designed for use
above floors.
Sizes: 2", 2 $\frac{1}{2}$ ".



Brass Elbows

A264.

Sizes: 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ ", 2" in 15, 30,
45, 60, 75, 85 and 88 $\frac{1}{2}$ degrees.
Sizes: 2 $\frac{1}{2}$ " and 3" in 45, 75,
85 and 88 $\frac{1}{2}$ degrees.



Brass Elbows

A265.

With Trap Screw.
Sizes as No. A264



Brass Outlets

A266.

For Two Compartment
Cement Wash Troughs.
Country Pattern: 1 $\frac{1}{2}$ ".
M M B.W. Pattern: 2".



Brass Junctions

(Fullway)
A267.

Also 2" x 45 Double
Junctions.

Dia. of Pipe	Dia. of Branch	Angle
1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
2" x 1 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
2" x 1 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
2" x 2"	x 45, 75, 85, 88 $\frac{1}{2}$	
2 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
2 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
2 $\frac{1}{2}$ " x 2"	x 45, 75, 85, 88 $\frac{1}{2}$	
2 $\frac{1}{2}$ " x 2 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
3" x 1 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
3" x 2"	x 45, 75, 85, 88 $\frac{1}{2}$	
3" x 2 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
3" x 3"	x 45, 75, 85, 88 $\frac{1}{2}$	



Brass Junctions

A268.

With Inspection Opening
Also 2" x 45 Double
Junctions.

Dia. of Pipe	Dia. of Branch	Angle
1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
2" x 1 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
2" x 1 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
2" x 2"	x 45, 75, 85, 88 $\frac{1}{2}$	
2 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
2 $\frac{1}{2}$ " x 2"	x 45, 75, 85, 88 $\frac{1}{2}$	
2 $\frac{1}{2}$ " x 2 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
3" x 1 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
3" x 2"	x 45, 75, 85, 88 $\frac{1}{2}$	
3" x 2 $\frac{1}{2}$ "	x 45, 75, 85, 88 $\frac{1}{2}$	
3" x 3"	x 45, 75, 85, 88 $\frac{1}{2}$	



Brass Junctions

A269.

PARALLEL
Plain and with Inspection
Opening

Dia. of Pipe	Dia. of Branch
1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ "	x 1 $\frac{1}{2}$ "
1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ "	x 1 $\frac{1}{2}$ "
1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ "	x 1 $\frac{1}{2}$ "
2" x 1 $\frac{1}{2}$ "	x 1 $\frac{1}{2}$ "
2" x 1 $\frac{1}{2}$ "	x 1 $\frac{1}{2}$ "
2" x 2"	x 2"



Brass Junctions

A270.

Angle: 45°, 88 $\frac{1}{2}$ °.

Plain and with Inspection
Opening.

Dia. of Pipe	Dia. of Branch
1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ "	x 1 $\frac{1}{2}$ "
1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ "	x 1 $\frac{1}{2}$ "
1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ "	x 1 $\frac{1}{2}$ "
2" x 1 $\frac{1}{2}$ "	x 1 $\frac{1}{2}$ "
2" x 1 $\frac{1}{2}$ "	x 1 $\frac{1}{2}$ "
2" x 2"	x 2"



We can also supply Double Brass Junctions, plain
only. Angle 45°/88 $\frac{1}{2}$ °.

Sizes: 1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ ", 2" x 1 $\frac{1}{2}$ ", 2" x 2".



Brass I.O. Sockets

A271.

Sizes: 1 $\frac{1}{2}$ ", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3".

Brass Sanitary Sockets


A272.

With Large Access
Door
Sydney House only.
Sizes: 2", 2 $\frac{1}{2}$ ", 3".



Ext. Pieces for Brass Traps
A273.

Size Lengths
1½" x 2", 3", 4", 6"
1½" x 3", 4", 6"
2" x 3", 4", 6", 8", 9", 12"
2½" x 3", 4", 6", 9"
3" x 3", 4", 6", 9"



Brass Nut and Tail Reducing Pieces
A274.

Nut is screwed to suit 2" Fullway thread with Tailpiece screwed 1½" Standard Male Thread.
Also made with nut screwed 2" Standard and Tailpiece 1½" Standard Thread.



Brass Reducing
A275. Piece

For Brass Traps
Male and Female.
Sizes: 2" x 1½".
Standard Gas Threads.



Caps and Linings
(Plain)
A276.

Sizes: 1½", 1", 2" and 2" Fullway.



Male End Caps and Linings
A277.

Sizes: 1½", 1", 2" Fullway
and 2½", 3".
Also made in 1½" for Cisterns
Screwed 1½" on Tail.



Caps and Linings
ADJUSTABLE
A278.
(Brass)

Sizes: 1½", 1", 2".



Brass Socket Connections
A279.

For connection on Lead Pipe
to Iron.
Made with Screwed End,
Female.
Sizes: 1½", 1", 2".



Slip Thimbles
(Brass)
A280.

For connecting Sheet Iron Pipe
to Lead.
Sizes: 1½", 2", 2½".


Brass Ferrules
A281.

Beaded for C.I. Pipe and
Lead Pipe.
Sizes: 2", 2½", 3", 4".



Brass Ferrules
A282.

Plain for Lead Pipe to Sheet
Iron Vent Pipe.
Sizes: 2", 2½", 3", 4".



Floor Wastes
A283.

For Lead Floors
Sizes: 1½", 1", 2".



Hospital Pattern Floor Waste
A284.

Sizes: 2", 2½", 3".
The top of this waste is re-
movable by taking out set
screws.



Cup Pattern Floor Waste
A285.

The grating in this waste
screws into the body.
Made in 2" size only.



Grates
A286.
(Brass Bar)

Sizes: 1½", 1", 1½", 2", 2½", 2½", 2½",
3", 3½", 4", 4½".



Flush Screwed Grating
A287.

Trap Screw Pattern in Cast Brass
Sizes: 3", 3½", 4".
Sydney House only.




Screwed Floor Wastes
A288.

Public Works Pattern
Made in 3" only.



Youngson's Grate
A289.

Stocked by Sydney House
only.



This fitting has been designed
to make a good connection
with the "Palazzi" Gully
Riser, preventing seepage and
making holes or depressions
in the floor around it. The
square pattern top is more
adaptable with tiling than the round grate. It is
adjustable to exact floor level, and saves cost on
the plumbing and floor laying work. The grid
can be easily removed for access to gully.

Wright's Pattern Drained Grates
A290.

Reg. No. 7351.
A favoured Grate, made with
both Round and Square Tops, for
use on floor level of Bathrooms, Laundries, Lava-
tories, etc.
Approved by the Water, Sewerage and Drainage
Board of Sydney. Made in 4" only.



Flap Valves
A291.

For Floor Wastes, etc.
Sizes: 1½", 1", 2".



Domed Urinal Wastes
A292.

Standard Patterns.
Sizes: 2", 2½".

Double Union Urinal Tees
A293.

Female Standard Gas Thread
Loose Rings in Unions to
fit Copper Tube.
Sizes: Iron Copper
1½" x 1"
1½" x ¾"
1" x 1"
¾" x ¾"



URINAL SPREADERS
Button Pattern
A294.

Screwed ¾" Brass Thread.



Union Pattern
A295.

With Lugs
¾" Copper Tube size.



Button Pattern
A296.
With Lugs
Size: ½" and ¾" Iron.



Flat Pattern
A297.
Size: ¾" Iron.



Brass Urinal Caps
A298.
Screwed Gas Thread.
Sizes: ½", ¾".

"PALAZZI" BRASS GULLIES
Stocked by Sydney House only

By a suitable arrangement of waste pipes and the
use of the "Palazzi" Brass Gullies, the cost of
installing lavatory ranges can be materially dimin-
ished—particularly in tall buildings, where a fur-
ther economy may be effected by the omission of
many of the vent pipes usually fitted. If desired,
these gullies may with safety be placed in floors
that are only 8" thick, without any portion showing
through the ceiling. Single and double inlet risers,
inlets of which are screwed 2", are furnished as
accessories to enable a basin, bath or other waste
pipe to be connected. All inlets and outlets are
at an angle of 95 degrees, giving a grade of about
1 in 14. Suitable plain risers and gratings are
supplied when required, as well as a screwed
extension ferrule, the latter being used when it is
desired to connect the outlet to a cast-iron pipe.
The gullies all have 4" inlets, but may be supplied
with 2", 2½", and 3" outlets. Where they are used
with double inlet risers, the size having a 3" outlet
is recommended.

"Palazzi" Brass Gullies and Risers
A310.

Patent No. 18719
Stocked by Sydney House only.
Sizes: 4" x 2", 4" x 2½", 4" x 3"



"Palazzi" Double Inlet Riser
A311.
Size: 4" x 2".



"Palazzi" Single Inlet Riser
A312.
Size: 4" x 2".

Riser Extension
A313.

With Trap Screw Grating
Suitable for the extension of No.
Size: 4" x 6", 9", 12" in length.




"Palazzi" Brass Ferrule
A314.

For connecting W.I. Pipes to
Cast Iron Soil Pipe Fittings.
Sizes: 2", 2½", 3".

"PALAZZI" BREECHING CONNECTION

A315.

Stocked by Sydney House only.



These connections are designed for use on 1½" and 2" water services, and are furnished with two 1" main cocks at the inlet ends, and a "Y" piece threaded externally to take 2" wrought iron pipe, and 1½" internally to take 1½" pipe at outlet. The copper pipes intervening between main cocks and "Y" pieces are screwed together and sweated at all joints. The curved branch and annealing of the copper tube enables the plumber to readily adjust the unions to any slight variation in the position of main cocks.

Order by Number Only—
DO NOT CUT CATALOGUE

Lead Traps with Cleaning Screws

Lead S Trap

A316.

Sizes: 1½", 1¾", 2", 2½", 3", 4".



Lead P Trap

A317.

Sizes: 1½", 1¾", 2", 2½", 3", 4".



Lead P Traps

A318.


With Long Outlets

Sizes: 1½", 2".
May be had without Cleaning Screw if required.

Lead Bends

A319.

Equal and Unequal
Sizes: 1½", 2", 3", 4".



Lead Pedestal Traps

A320.

Sizes: 1½", 1¾", and 2".



Sockets

A321.

Cast Lead or Brass.



For Closet Pans with 4" Outlets.
Lead Sockets for Slop Hoppers,
3" Outlets.

Lead Caps

A322.

For Sealing Vent Horns on Pans.
Sizes: 3½", 3¾"



Lead Cones

A323.

For Flush Pipes or Vent Horns
of Closet Pans.

Sizes: 2½" x 1½", 3", 3½" x 1½",
3½" x 1½", 3½" x 2", 3½" x 2".

Lead Tacks

A324.

For Lead Pipes

Sizes: 1½", 1¾", 2",
2½", 3", 4"



Lead Seals

A325.


Used by Sewerage Authorities for
fixing to Cisterns when tested.



Copper Connections

A326.

WITH ROLLED ENDS



½" Nut both ends and Matching Piece for ½"
Iron Pipe.

Copper Basin Connection

A327.

M.M.B.W. PATTERN




Size: ½" x 14½" long.
One ½" Nut, one ¾" Nut and Matching Piece
for ½" Iron Pipe.

Copper Cistern Connection

A328.

M.M.B.W. PATTERN



Size: ½" x 12½" long.
One ½" Nut, one ¾" Nut.

Galvanised Sheet Iron Flush Pipes

A329.



Offset 1", 2", 4".
N.P. Copper Flush Pipes Made to Order.



BRASS SCREWED BATH
Plugs and Washers
A330.

Sizes: 1½", 2" and 2" Fullway.

Plugs and Washers

A331.

FOR TROUGHS

Deep and Heavy Square.
2" Standard Size, Screwed 2"
Male.



Trap Screws

A332.

For Lead Traps, etc.
Sizes: ¾", 1", 1½", 1¾".




BRACKET CLIPS

Bracket Clip

A333.

With Buffer
N.P. or Chrome.
Screwed ¾" Whitworth at
back.
1½" Copper Tube size.
1½" Standoff only.



Bracket Clip

A334.

Without Buffer
Screwed ¾" Whitworth at
back.
Copper Tube sizes: ¾", 1", 1½", 2".
1", 1½", 1¾", 2".
Iron Pipe sizes: ¾", 1", 1½", 1¾", 2".
Made with 1" and 1½" Standoff.



Band Buffer Clip

A335.

1½" Copper Tube
size
Nickel or Chrome
Plated.



Galvanised Beaded Clips

A336.

For Pipes

Sizes: ½", ¾", 1", 1½", 1¾", 2".



N.P. Band Clips

A337.

For Copper Tube
Sizes: ½", ¾", 1".
For Iron Pipe—Sizes: ½", ¾".
Larger sizes to order.



W.I. Band Clips

A338.

For Cast Iron Soil Pipes.
Size: 4".



Flush Pipe Buffer Clip

A339.

Nickel Plated or Gal. Iron
Size: 1½", 1¾".



Flush Pipe Clip

A340.

Without Buffer
Nickel Plated
Sizes: 1½", 1¾".



Vent Pipe Stays

A341.

For 3" and 4" Vents
Ends for Stays screwed ¾"
Gas.



Galvanised Post Clip

A342.

For 3" Vent x 4" Post.



Block Clips

GALVANISED S.I.

A343.

For 3" and 4" Vents for
standing Vent Pipes off walls.





W.I. Bolted Clips
A344.

With Shanks 4" to 12" long.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2",
 $2\frac{1}{2}$ ", 3", 4".

Also made with Galvanised
Fronts.

Galvanised Clips
A345.

For Sheet Iron Vent Pipe,
etc.
Sizes: $1\frac{1}{2}$ ", 2", $2\frac{1}{2}$ ", 3", 4", 6".



**Galvanised Wire
Strainers**
A345a.

For Vent Pipes, etc.
Sizes: $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2", $2\frac{1}{2}$ ", 3", 4".

Galvanised Educt Cowls
A346.

Sizes: 3", 4"



Galvanised Sheet Iron Vent Pipe
A.347.



Sizes: $1\frac{1}{2}$ " and
2" in 3 ft
lengths; 3" and
4" in 3 ft. up
to 36 ft.

Offsets—
Sizes: $1\frac{1}{2}$ ", 2",
3", 4", with
offsets up to
9".

Bends—
Sizes: $1\frac{1}{2}$ ", 2",
3", 4".
Degrees: 45,
75, 90.

**Brass Vent Pipe
Branches**
A.348.

For connecting Lead Vent Pipes
to Sheet Iron Vents.
Sizes: 3" x $1\frac{1}{2}$ ", 3" x 2", 4" x 3".



Wrought Iron Hooks
A349.

For W.I. and Compo Pipe.
Galvanised.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2",
 $2\frac{1}{2}$ ", 3", $3\frac{1}{2}$ ", 4", 6".

Tinned Compo Hooks.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ", $\frac{5}{8}$ ", $\frac{3}{4}$ ", 1".



**Manhole
Steps**
A350.


In Black or Galvan-
ised Wrought Iron.



"D.P.L." W.C. Cisterns
A351.

Full Bore Flush

Ball Cock and
Overflow are inter-
changeable.
The Ball is sus-
pended and cannot
strike the bottom
of the cistern.
Supplied also with
Brackets if de-
sired.



Capacity: 1, 2 and 3 gallons.
Painted and Glass Enamelled.



Cistern Pulls
A352.

Galvanised Pull with Chain
China Pull with Rubber Ring
and Brass or N.P. Chain.
Rubber Pull with N.P. Link,
Variegated Colouring.

I.R. Seat Buffers
A353.



Long White. White Pin. Screw Hole.


N.P. Seat Bolts and Nuts
A354.



Size: $3\frac{1}{2}$ " x 5-16ths".

Brass Urinal Bolts & Nuts
A355.

Size: 2" x $\frac{1}{4}$ ".



Seat Hinges
A356.

Butterfly Pattern
Nickel Plated on Brass.
Double or Single Flap.

EXPANSION PLUGS

Expansion Plugs
A357.

Brass and I.R. for testing
W.I., S.W., or Lead Pipes.
Sizes: 2", 3", 4", 6", 9", 12",
15", 18".



Expansion Plugs
A358.

With Drain Cock
Sizes: 4", 6", 9", 12", 15", 18"
18" Size made in Cast Iron




PLUMBERS' TOOLS

We carry a large range of
Plumbers' Tools by leading
manufacturers.

BOXWOOD DRESSERS
BENDING STICKS
BOSSING STICKS
MALLET, TURNPINS
BOBBINS
FOOTPRINT
WRENCHES
VISES, BLOW LAMPS
OSTER STOCKS and
DIES, Ordinary and
Receding
DUO DIE STOCKS
CHATWIN'S RATCHET
and WALWORTH
STOCKS and DIES
VULCAN WRENCHES
BASIN WRENCHES
PIPE CUTTERS
TAPPING FRAMES
DRILLS,
RATCHET BRACES
SNIPS, LADLES
MELTING POTS
Etc., etc.

DANKS' FOR BILLABONG AND COO-EE WINDMILLS

The "HUSH" Silent Flusher . . .



A359.

Constructed for Fitting on Either Hand and will work against Any Pressure over 8 ft.

The "Hush" is a mechanically efficient Flush Valve made in our own factory from high grade Gun Metal.


It is easy to install and has not to be disconnected for adjustments or repairs. The efficiency and neat appearance of the "Hush" make it the leading Flushing Valve in the Commonwealth.

The "Hush" is easily operated by moving the handle in any direction.

Approved by the Melbourne and Metropolitan Board and Water Boards of other States. Finished in Nickel or Chrome.

FLUSHER BEND

For connecting up the Flusher with the Pan.



DANKS
for
QUALITY



Rubber Force
Cups

A360.

This article is made in the form of a stout I.R. Cup with a wood handle, and is very useful in cleaning stoppages in Basin Wastes, etc.

A361. THE "HERCULES" PUMP

The "Hercules" is practically both a Lift and Force Pump. The patent Rubber Force Cup gives the Pump a reciprocating action, and with but little effort obstinate obstructions are speedily removed.

The "Hercules" is not an air pump, its action is Hydraulic, and it is the only pump fitted with the Patent Steel Reinforced Rubber Cone.

HEAVY BRASS BARREL

Length, 1 ft. 8 ins.; Dia., 1 1/2 in. The price of the "Hercules" brings this useful little pump within the reach of every Plumber, and no Plumber's Kit is complete without it.



Observe the steel plate which is embedded in cones.



A special feature of this Pump is that it will rapidly withdraw any obstruction.



ARMOURED CANE DRAIN CLEANING MACHINES

A362.

30 ft. long in ten 3 ft. lengths.




Illustration shows: (a) Scraper, (b) Rods and wheel, (c) Single rod, (d) Key, (e) Ferret, (f) Plunger, (g) Cleaner in action.

MANY ADVANTAGES OVER CANE ROD MACHINES

Being Rigid an end thrust is obtained sufficient to remove almost any form of stoppage.

Flexible enough to pass through bends, junctions or traps. Elasticity—will always recover and revert to their normal position.

Lockfast—joints being flushed with the rod, there is nothing to catch in the drain.

Seated inside with the finest quality cane rod, which cannot scrub up or wear out, and nothing can pass to the inside of rod.

Each set complete with 10 Rods, Wheel, Ferret, Plunger, Key, and Scraper.

DANKS' FOR THE LATEST IN WALLPAPERS

Cast Iron Sewerage Fittings



**Plain Junctions
A363.**

Sizes Degrees
4 x 4; 45, 75, 85, 88½
4 x 3, 2½, 2; 45, 75, 88½
3 x 3, 2½, 2; 45, 75, 88½
2½ x 2½, 2; 45, 75, 88½
2 x 2; 45, 75, 88½



**Pan Junctions
A371.**

I.O. 4" Close Up, 4½", 9",
11", 13½" and 18" wall.
Close Up has R. or L.H. I.O.
Others have I.O. on back.
All 77½°.



**4" Garage Bends
A379.**

Set of three.
For Triple Interceptor Trap.



**Plain Inverted
Junctions
A364.**

Sizes Degrees
4 x 3, 2½, 2; 45, 88½
3 x 3, 2½, 2; 45, 88½
2½ x 2½, 2; 45, 88½
2 x 2; 45, 88½



**4" I.O. Junctions
A372.**

Degrees: 45, 75, 85, 88½
I.O., R.H., L.H., or on back.
Reducing Sizes Made to Order.




**Adjustable Tops
A380.**

Sizes:
4 x 4, 4 x 3, 4 x 2.



**Parallel Junctions
A365.**

Sizes:
4 x 4.
4 x 3.
4 x 2.



**Double
Junctions
A373.**

I.O., 4".
45, 88½°.




**Adjustable Tops, 4"
A381.**

Double Straight Through



**Parallel Inverted
Junctions
A366.**

Sizes:
4 x 3.
4 x 2.



**Double Junctions
A374.**

I.O., 4".
45°.



**Adjustable Tops, 4"
A382.**

Double Right Angle.



**Plain Junctions
A367.**

Size: 4 x 4; 45/88½°.
Or with I.O., R.H., L.H., or
on back.



**Plain Bends
A375.**

Sizes:
4"; 15, 30, 45, 60, 75, 85 and
88½°.
2", 2½", 3"; 15, 30, 45, 60,
75, 88½°.




**Adjustable Tops, 4"
A383.**

Vertical Frogmouth.



**Plain Double
Junctions
A368.**

Size: 4"; 45/88½°.



**I.O. Bends
A376.**

Sizes:
4"; 15, 30, 45, 60, 75, 85,
88½°, I.O., R.H., L.H. or
on back.
I.O. on back.
2", 2½", 3"; 45 and 88½°



**Adjustable Tops, 4"
A384.**

Horizontal Frogmouth



**Plain Double
Junctions
A369.**

Size: 4"; 45°.




**Plain Pan Bends
A377.**

Size:
4" for Close Up, 4½", 9"
and 11" Wall.
Vented Pan Bends made
to Order.



**Disconnecter
Trap, 4"
A385.**



**Plain Pan
Junctions
A370.**

Size: 4".
Close up, 4½".
9", 11", 13½" and 18" wall



**I.O. Pan Bends
A378.**

Size:
4" for 4½", 9" and 11"
Wall.



**Disconnecter
Trap, 4"
A386.**

With Soil Socket.

SEE PAGE 34 FOR METHOD OF ASCERTAINING RIGHT OR LEFT HAND FITTINGS

Cast Iron Sewerage Fittings



Boundary Trap
A387.


Size: 4".



Sockets
A395.

Sizes: 4", 3", 2½", 2".
4" and 3", also without
Inside Bead.

Inspection Covers
A422.




Size:
36" x 24", 24" x 24"
Light.
24" x 24" Heavy
21" x 17", Ordinary
21" x 18" and 21" x
12", Hinged.



Gully Trap
A388.

Size: 4".




Blank End
A396.
WITH SCREWED BRASS
CAP

Size: 4", 3".
Also 4" for Level Inlets.

Extensions
Ordinary
A423.



Sizes:
4" x 6", 9", 12", 15" and 18".
For connecting Stoneware to Cast Iron.



Urinal Trap
A389.


Sizes: 2", 2½", 3".
Screwed or Spigot Outlet.



Blank Ends
A397.

Sizes: 4" and 3".


Extensions
Plain Pan
A424.



Sizes:
4" x 6", 9", 12", 15", 18", 24"
and 36".



Silt Trap
A390.
WITH GRATE AND GALVANISED
BUCKET
4" Outlet.



Boundary Covers
A398.

LIGHT
Sizes:
6", No. 198.
4", No. 197.

Extensions
Vented Pan
A425.



Sizes:
4" x 9", 12", 15", 18", 24".



Gully Top
Round
A391.

Size 4".



Combination Ground
Vent
A399.

Size 4".

Offsets
A426.



Sizes:
4" x 2", 3", 4½", 6", 9".
2", 2½", 3" x 2", 3", 4½", 6".



Level Inlet Single
A392.


Sizes:
4" x 4", 4" x 3", 4" x 2".



Ashdown Ground
Vent
A400.

Size 4".

Soil Pipe Plain
A427.




Sizes:
4" x 3 ft., 6 ft. and 9 ft.
2", 2½", 3" x 3 ft. and 6 ft.
only.



Level Inlet
Double
A393.

Sizes:
4" x 4", 4" x 2"



Mica Flap Vent
A420.

Size: 4".

Soil Pipe with I.O.
A428.




Sizes:
2", 2½", 3", 4" x 3 ft. only.



Reducers
A394.

Sizes:
4" x 3", 4" x 2½", 4" x 2",
3" x 2".



Boundary Covers
A421.
HEAVY

Sizes:
6", No. 200.
4", No. 199.

6" SOIL PIPE
and Fittings
MADE TO ORDER

GLASS ENAMELLED PIPE
and Fittings
MADE TO ORDER

SPECIAL FITTINGS
MADE TO SPECIFICATION

FOR HIGHEST QUALITY, INSIST ON "DASPYL"

Cast Iron Sewerage Fittings




**Grates, D.T.
A429.**

For 6", 4" and 3"
Stoneware Pipes.



**Grates, D.T.
A432.**

For 4" Stoneware Pipes with
2" hole in centre.




**Grates, D.T.
A435.**

Domed for 4" Stone-
ware Pipes.




**Gully Grates
A430.**

Sizes:
6 1/2" diameter,
URINAL
5 1/2" diameter.



**Grates
A433.**

(MILD STEEL)
For Garage Pits,
25" x 25".



**Flat Grates
A436.**

LIGHT
12" x 12", 18" x 18".
HEAVY
12" x 12", 12" x 18",
24" x 24".



**Dished Grates
A431.**


Sizes:
9" x 9",
12" x 12".



**Grates for Silt
Traps
A434.**

11 1/2" diameter.

A437.
**Bitumen in 9 lb. Blocks
specially prepared for
joints of Closet Pans, etc.**



**Flaring Tools
A418.**

These tools are
used for flaring
copper tube when
used with EVER-
TITE FITTINGS.

Sizes: 1/2", 3/4", 1",
1 1/4", 1 1/2",
1 3/4", 2".

All copper tube sizes

Variations in the above sizes may be obtained.

**The "Danks" 1 inch Stand-Pipe Hydrant
A419.**

Of Special Interest to Councils

The Danks 1 in. Stand-Pipe Hydrant fits into the fire plug in the usual way, and the barrel being made of 1 inch gal-
vanised wrought iron pipe, will stand up to the hard usage
fittings of this kind are subjected to. Its uses are many, and
it is specially adaptable for washing down drains, supplying
water for concrete mixing and road work generally.

For Street Watering and Fire Hydrants, see
pages 22 and 27.



STEAM COCKS, Etc.



**Deep Barrel Steam
Cock
A441.**

GUN METAL

Male and Female Screwed Ends.
Sizes: 1/2", 3/4", 1", 1 1/4", 1 1/2",
2", 2 1/2", 3", 4".



**Three-Way Plug
Cock
A443.**

GUN METAL

Screwed.


Sizes: 1/2", 3/4", 1", 1 1/4", 1 1/2", 2"

**Flanged Steam
Cock**

A444.

GUN METAL
Plain Plug.

Sizes: 1", 1 1/2", 1 3/4", 2",
2 1/2", 3", 4".



**Deep Barrel Steam
Cock**

A442.


GUN METAL

Female Screwed Ends.

Sizes: 1/2", 3/4", 1", 1 1/4", 1 1/2",
2", 2 1/2", 3", 4".



**DANKS for the Best in
BATHS & BATHROOM WARE**



**Packed Gland Steam
Cock**

A445.

GUN METAL

Oval Top, Male and Female Ends.
Sizes: 1/2", 3/4", 1", 1 1/4", 1 1/2",
2", 2 1/2", 3", 4".

DANKS' FOR PAINTS, VARNISHES AND PAINTERS' NEEDS

Steam Cocks, Valves, Etc.

Packed Gland Steam Cock

A446.

GUN METAL

Oval Top, Female Ends.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 4".



Three-Way Gland Cock

A447.

GUN METAL

Oval Top, Screwed
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3".




Packed Gland Flanged Steam Cock

A448.

GUN METAL

Heavy Pattern, Fullway.
Sizes: 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 4".




Packed Gland Flanged Steam Cock

A449.

GUN METAL

Right Angle.
Sizes: 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3".



Three-Way Packed Gland Cock

A450.

GUN METAL

Flanged
Sizes: 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3".



Packed Gland Cock

A451.

ALL IRON

Screwed female.
Sizes: $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 4".




Packed Gland Cock

A452.

ALL IRON


Flanged.
Sizes: 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 4".



Packed Gland Steam Cock AND RIGHT ANGLE CHECK VALVE COMBINED

A453.

Gun Metal, Flanged.
Sizes: $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ".



Steam Cock AND STRAIGHT CHECK VALVE COMBINED

A454.

Screwed Male and Female
Sizes: $\frac{1}{2}$ " x $\frac{1}{4}$ ", $\frac{3}{4}$ " and $\frac{1}{2}$ ".



Steam Valves

Steam Valves

A455.

GUN METAL

Screwed
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 4".



Steam Valves

A456.

GUN METAL

Flanged.

Sizes: $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 4".



Steam Valves

A457.

GUN METAL

Right Angle, Flanged.

Sizes: $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3".



Steam Valves

A458.

Right Angle, Screwed.

Sizes: $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2".



Steam Valves

A459.

Screwed, Fitted with Jenkin's Type Renewable Disc.

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3".



Needle Valves

A460.

Right Angle.

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".



Needle Valves

A461.

For Oil, Petrol, etc.

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ".

Renewable Discs and Seats

A462.

FOR STEAM VALVES



Steam Valves

A463.

SCREWED, RENEWABLE WHITE BRONZE SEAT

Regrindable Reversible Valve

200 lbs. Working Pressure.

Bronze Composition.

Sizes: $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2".

Also Flanged.



Fullway Gate Valves

A464.

Screwed, All Brass.

Sizes: $\frac{3}{4}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 4".



Fullway Gate Valves

A465.

Flanged, All Brass.

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 4".



Gate Valves

A466.

QUICK ACTING WITH LEVER

Gun Metal, Screwed.

Sizes: 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3".


A466a.

GATE VALVES

Quick Acting, with Lever

Cast Iron, Flanged.

Sizes: 4", 5", 6".



Gate Valves


A467.

Flanged.

Bolted Top

Made in Gun Metal and Brass.

Sizes: 2", 2 $\frac{1}{2}$ ", 3", 3 $\frac{1}{2}$ ", 4", 5", 6".



Flanged Gate Valve

HEAVY CAST IRON

A468.

Bronze Mounted

Sizes: 2", 3", 4", 6", 7".



Fullway Gate Valves

A469.

(Flanged)

Iron Body, Brass Mounted.

May also be had in All Iron.

Sizes: 2", 2 $\frac{1}{2}$ ", 3", 3 $\frac{1}{2}$ ", 4", 5", 6", 7", 8", 9", 10", 12".



Lever Throttle Valve

A470.

For working pressure up to 75 lbs.

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ".



Globe Valves

CAST IRON BODY

Gun Metal Fittings

Flanged.

Sizes: 2 $\frac{1}{2}$ ", 3", 4", 5", 6".



Right Angle Globe Valves


A472.

CAST IRON BODY

Gun Metal Fittings

Flanged.

Sizes: 2 $\frac{1}{2}$ ", 3", 4", 5", 6".



The "Reliance" Patent Gas Valve

A473.

This patent valve is designed so that it may be closed after being open for long periods, thus preventing the dangerous and costly lagging off of the main which occurs when the old type valve jams and refuses to close, often through the oxidising influence associated with gas mains.

A special feature covers a grease packed crosshead in which the spindle is encased when the valve is open, eliminating corrosion or the accumulation of foreign matter and making certain that the valve will close.

Used by the largest gas company in Australia, and indispensable to all gas companies. Made in sizes up to 36" diameter in vertical or horizontal designs.



STEAM VALVES (Cont.)



Lock Up Safety Valve
A474.


Gun Metal, Screwed and Flanged
Screwed Male: $\frac{3}{4}$ ", $\frac{5}{8}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2".
Flanged: $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2".
Also made in Cast Iron, Gun Metal
Mounted, Flanged.
Sizes: $2\frac{1}{4}$ ", 3", $3\frac{1}{2}$ ", 4", 5", 6".

Pop Safety Valve
A475.

With Side Outlet
Gun Metal.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2".



Lever & Weight Safety Valve
A476.



Gun Metal with
Iron Lever and
Weight.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1",
 $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2".

May also be had with Cast Iron Body Flanged.
Sizes: $2\frac{1}{4}$ ", 3", 4".

WATER REDUCING VALVES

We are makers of Water Reducing Valves suitable for reducing pressure up to 200 lbs. They are similar in operation to the Steam Reducing Valve, but the valves are operated by Plungers which work in a gun metal lined cylinder. These Valves have proved invaluable to Water Trusts, and are used by them throughout the Commonwealth. They prevent many of the accidents in O.L. Mains through variations in pressure.

Sizes: 3", 4", 5", 6", 8", 9", 10", 12".
We also make these valves in larger sizes and for higher pressures.





Straight Check Valves
A477.

Gun Metal, Screwed.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ", $\frac{5}{8}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ",
2", $2\frac{1}{2}$ ", 3".

Straight Check Valve
A478.

Gun Metal, Flanged.
Sizes: 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2", $2\frac{1}{2}$ ", 3".




Check Valves
A479.

Right Angle
Gun Metal, Screwed.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2".

Check Valves
A480.

Right Angle
Gun Metal, Flanged.
Sizes: 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2", $2\frac{1}{2}$ ", 3".



Swing Check Valves
A481.

Gun Metal, Screwed.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2",
 $2\frac{1}{2}$ ", 3".
Also made with Leather Face
Valves, screwed.
Sizes: $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2".



Vertical Check Valve
A482.

Gun Metal, Screwed.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2".

Whistle Valve
A483.


Adjustable Lever
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", $1\frac{1}{4}$ ",
 $1\frac{1}{2}$ ", 2".




STEAM PRESSURE REDUCING VALVES

A484.

G.M. Screwed, G.M. Flanged,
O.I. Flanged.
Size: $\frac{1}{2}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2", $2\frac{1}{2}$ ",
3", 4", 5", 6".



Connect valve perfectly level to steam pipes. Fill lower portion with cold water to its full capacity. This must be particularly attended to or I.R. diaphragm will be destroyed; the condensation of steam will be sufficient to provide for this after first filling. The valve is then ready for use, turn on steam and regulate to required pressure, which is to be ascertained by a pressure gauge on low pressure side of valve. If the valve is reducing the pressure too much, compress spring by screwing regulating bolt upwards. If not reducing sufficient, release spring by unscrewing regulating bolt.



High-Low Steam Pressure Reducing Valves
A485.


Designed especially for use in radiator work.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", $1\frac{1}{4}$ ".
Important — When ordering, always state Pressure at which Valve is to be worked.

Expansion Joints
A486.



Made in all Gun Metal, or in Cast Iron with Gun Metal slide.
Screwed.
Sizes: 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2",
 $2\frac{1}{2}$ ", 3", $3\frac{1}{2}$ ", 4".
Made also with Flanged Ends


ORDER BY NUMBER—
Do Not Cut Catalogue.



Hexagon Steam Unions
A487.

Gun Metal
Screwed Male and Female.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ", $\frac{5}{8}$ ", 1", $1\frac{1}{4}$ ",
 $1\frac{1}{2}$ ", 2", $2\frac{1}{2}$ ", 3".

Pet or Air Cocks



Straight
A488.

With Lever Handle and Capped Top
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ ".

Straight
A489.
With Lever Handle and Union

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ ".



Bent Pet Cock
A490.

With Lever Handle and Cleaning Pin
Asbestos packed.
Sizes: $\frac{1}{2}$ ".



Bent
A491.

With Lever Handle, Union and Cleaning Pin
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ ".



Bent
A492.

With Lever Handle and Cleaning Pin
Capped top.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ ".




Straight
A493.

With Lever Handle
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ ".




Bent
A494.

With Lever Handle and Cleaning Pin
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ ".



Straight
A495.

With T Handle
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".




Bent
A496.

With T Handle
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".



Pressure Gauge Cocks
A497.

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ".




Hexagon Steam Unions
A498.

Gun Metal
Screwed Female.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2",
 $2\frac{1}{2}$ ", 3".

DANKS' FOR ALL ELECTRICAL FITTINGS


BOILER GAUGE MOUNTINGS



"Daspyl" Ordinary Pattern A499.
Sizes: 1", 2", 3", 4", 5", 6".

"Daspyl" Gland Pattern A500.
Sizes: 1", 2", 3", 4", 5", 6".

AUTOMATIC SHUT-OFF GAUGE MOUNTINGS



"Daspyl" Asbestos Packed A520.

Suitable High Pressure
Fitted with a special valve which automatically stops the flow of scalding water from boiler should gauge glass break.
Made in Light and Heavy Patterns.
Size: 3".

"Daspyl" Asbestos Packed A521.


FOR HIGH PRESSURE
Fitted with valve which automatically stops the flow of scalding water from boiler should gauge glass break.
Made in Light and Heavy Patterns.
Size: 3" Round Flanges.



"Daspyl" A522.

FOR ORDINARY PRESSURES
This gauge mounting is of the gland pattern, and is fitted with a valve which automatically stops the flow of scalding water from boiler should gauge glass be broken.
Size: 3".

WATER GAUGE WITH GUARDS



Plain Pattern A523.
WITH GUARDS

Screwed Gas Thread takes Glass
1 1/2" x 12".
2" x 12".

A524.

GAUGE GLASSES (Plain)
Diameter: 3/4", 1", 1 1/4", 1 1/2", 2".
Length: 12", 13", 14", 15", 16".
Special sizes and lengths to order.



Expansion Tank Gauge A525.

Sizes: 1/2" Gas, 3/4" Gas.

Gauge Glass Protectors A526.

"DASPYL"
Are made to suit customer's gauge mountings in two patterns.




Plate Mounted
Steel Wire




WHEN ORDERING

State style required and give measurements shown on detailed diagram.

Example Order—Please forward one Steel Wire Gauge Glass Protector to suit a mounting of the following measurements:—

A = 8 3/4"; B = 10 3/4"; C = 1 1/2" in both cases; D = 1 1/2"; E = 3-16ths" in both cases; F = 13-16ths" in both cases.



THE "SYPHONIA" STEAM TRAP A527.

For automatically draining condensed steam from Steam Pipes, Steam Coils, Radiators, Steam Engine Jackets and Cylinders, and all steam-heated constructions, without loss of steam.

Sizes Made

No.	Inlet Outlet		Extreme Dimensions			Maximum Working Pressure
	Size	Size	Length	Width	Height	
3	1"	1 1/4"	1' 10"	8 1/2"	1' 4 1/2"	100 lbs.
5	1 1/2"	2"	2' 5"	10 1/2"	1' 7 1/4"	80 lbs.

Draining Capacity of Traps

Size of Trap Inlet	1"	1 1/2"
lbs. of water discharged per hour at 212° Fah.	500	1000



The "Midget" Steam Trap A529.

For all places where steam power is used.
Sizes: 1/2", 3/4", 1", 1 1/4", 1 1/2", 2".

The "Roma" Steam Trap A528.

Inverted Bucket Float Type for pressures up to 1000 lbs. per sq. inch and for Superheated Steam.
Sizes: 1/2", 3/4", 1", 1 1/4", 1 1/2", 2".



"XL-96" Improved Ejectors A530.



Lifts 22' to 25'.
Elevates 25' to 125'.
30 to 100 lbs. pressure—no lift.


Size Number	1	2	3	4	5	6	7*	8*	10
Pipe Connection—Steam	3/8"	1/2"	3/4"	1"	1 1/4"	1 1/2"	2"	2 1/2"	
Pipe Connection—Suction and Delivery	1/2"	3/4"	1"	1 1/4"	1 1/2"	2"	2 1/2"	3"	4"

*Sizes 7 and 8 have iron body, brass jets and steam connection. Other sizes all brass.

AUTO-POSITIVE INJECTORS

A531.

Automatic and Re-starting for High Pressures and Hot Water Supply.




While a large majority of boilers carry less than 150 lbs. pressure, the usual high working pressure of the ordinary automatic injector, there is an increased demand for an injector operating between 150 and 200 lbs. pressure. There is also a demand for an injector that will handle a water supply that has become heated by use of the syphon (or ejector) and in other ways, and is consequently too hot for injectors of the usual automatic type. We offer to the public the "Auto-Positive," especially designed to meet these requirements.

Sizes:

113—Screwed	3/4"	Gas.
115—Screwed	1"	Gas.
117—Screwed	1 1/4"	Gas.
119—Screwed	1 1/2"	Gas.
121—Screwed	1 3/4"	Gas.
123—Screwed	2"	Gas.

Showing Extra Parts for Auto-Positive Injectors A532.




8—Steam Plug.
X—Steam Jet.
G—Suction Jet.
H—Delivery Jet.
4—Delivery Plug.
N—Overflow Plug.
L—Pressure Valve.
M—Pressure Valve Collar.
K—Vacuum Valve.
I—Coupling Nut.
J—Tail Piece.



Automatic Injector A533.

Style left hand back.
Suction left.
Discharge back.

Size	Horsepower based on ordinary tub boiler	Horsepower based on 30 lbs. water per H.P. per hour	Pipe Connection
OO	4 to 8	6 to 12	1/2"
A	8 to 16	10 to 20	3/4"
AA	12 to 22	15 to 30	1"
B	17 to 32	22 to 45	1 1/4"
BB	20 to 45	25 to 60	1 1/2"
C	40 to 65	45 to 80	2"
CC	45 to 80	50 to 100	2 1/2"
D	50 to 100	60 to 135	3"
DD	75 to 135	85 to 165	4"
E	100 to 180	125 to 235	5"
EE	115 to 235	150 to 320	6"



Showing Extra Parts of Automatic Injector A534.

R—Steam Jet.
S—Suction Jet.
Y—Delivery Jet.
O—Plug.
V—Tail Piece.
X—Coupling Nut.
N—Overflow Hinge.
P—Overflow Valve.
Z—Overflow Cap.



Noiseless Water Heater or Steam Muffler
A535.

The use of this heater does away with all noise such as otherwise occurs when heating a tank or barrel of water or other liquid with steam. Of special value to creameries, chemical works, breweries, etc.

Size No.	Capacity*	Steam Pipe	Discharge Pipe
G	50 imperial gals.	1 1/2"	1 1/2"
H	63 imperial gals.	1 1/2"	1 1/2"
J	83 imperial gals.	1 1/2"	1 1/2"
K	104 imperial gals.	1 1/2"	1 1/2"
L	146 imperial gals.	1 1/2"	1 1/2"
M	209 imperial gals.	1 1/2"	2"

*Number of gallons of water heated from 70 degrees to 210 degrees in 30 minutes, with 70 lbs. steam pressure.

Fusible Plugs, "Daspyl"
A536.

GUN METAL
Sizes: 3/4", 1", 1 1/4", 1 1/2", 2".



STEAM WHISTLES



Steam Whistle Organ
A537.
WITH LEVER VALVE

Sizes: 1", 1 1/2", 1 3/4", 2", 2 1/2", 3", 4".
Size of Thread, Gas: 3/4", 1", 1 1/4", 1 1/2", 1 3/4".
With Flange at Extra Cost.

Steam Whistle
A538.

WITH COCK
Sizes: 1 1/2", 1 3/4", 2", 2 1/2", 3", 4".
Size of Thread, Gas: 3/4", 1", 1 1/4", 1 1/2", 1 3/4".
The 4" Whistle is made with a Valve and Lever instead of a Plug Cock as shown.

Steam Whistle, Triple Diapason
A539.

Size: 1 1/2", Flanged
Its Big Points are:—
Carrying Power.
Tone.
Efficiency.
It can be heard for miles.
The domes are 3 1/2", 4" and 5" in diameter.



GAUGES
FOR ALL PURPOSES

A540.

Steam, Water, Air, Altitude and Vacuum

Diameter of Dials: 2 1/2", 3", 4", 5", 6"



Pressure Gauge Syphons
A541.


A Gauge Syphon is indispensable wherever a gauge is used for steam pressure, and the Syphon should be of such construction that it will have a capacity sufficient to fill the gauge spring with water.
Sizes: 1/2", 3/4", 1".

Pressure Gauge Cocks see page 17, col. 3, no. A497.

LUBRICATORS

Glass Needle Lubricators
A542.

With loose Wire and Brass Lined Wooden Plug suitable for Shafting, etc., and used largely on Agricultural Machinery.



Size Number: 1, 2, 3, 4, 5, 7, 8, 10.



Oil Syphon, Slide Top
A543.

"DASPYL"

Gun Metal

Size, Diameter .. 1/2 1 1 1/2 1 3/4 2 2 1/2 3 4
Size of thread, gas 1/2 3/4 1 1 1/4 1 1/2 1 3/4 2



Pressed Steel Compression Grease Cup
A544.

Suitable for Bearings of all Descriptions.

Size Number	00	0	1	2	3	4
Capacity, ounces ..	1/2	2/3	1	2	3 1/2	5
Outside dia., inches	1 1/2	1 5/8	1 7/8	2 1/4	2 3/4	3 1/16
Gas thread, inches	1/2	3/4	1	1 1/4	1 1/2	1 3/4



Sight Feed Oiler
A545.

WITH SNAP LEVER
With Ball in Shank

Suitable for Bearing and Cylinders of Gas and Oil Engines.
Brass Mounted.

Size No.	1	1 1/2	2	3	4	5	6
Capacity, ounces ..	1	1 1/2	2 1/2	4	5	10	18
Outside diameter of glass, inches ..	1 1/2	1 3/4	2	2 1/4	2 3/4	3	3 1/2
Height of glass, inches ..	1 1/2	1 3/4	1 3/4	2 1/4	2 3/4	3	4
Gas thread, inches ..	1/2	3/4	1	1 1/4	1 1/2	1 3/4	2

Regulated Feed Grease Cup
A546.

This grease cup has a check spring inside to prevent cap jarring off with vibration. This spring also regulates feed of grease.



No.	K25	26	27	28
Outside diameter ..	1 1/2"	1 3/4"	1"	1 1/2"
Screwed, gas ..	1/2"	3/4"	1/2" & 1/4"	1"



Spring Lid Lubricators (OR OIL CUPS)
A547.

For use on all kinds of machinery, motor cars, etc.

No.	Across Hex.	Screwed Gas
SL2	1"	1/2"
SL3	1 1/4"	3/4"
SL4	1 1/2"	1"
SL5	1 3/4"	1 1/4"

A548.

Similar to above, but without interior tube for wick.

No.	Across Hex.	Screwed Gas
23	1"	1/2"
24	1 1/4"	3/4"
25	1 1/2"	1"
26	1 3/4"	1 1/4" 26 thread

Suet Lubricator
A549.
"DASPYL"

Gun Metal. Ordinary.
Size Diameter .. 1 1/2 1 3/4 2 2 1/2 3 3 1/2
Size of Thread, Gas 1/2 3/4 1 1 1/4 1 1/2 1 3/4



Tallow Cup
A550.

Double. "Daspyl."
Size, Diameter .. 1 1 1/2 1 3/4 2 2 1/2
Size of Thread, Gas 1/2 3/4 1 1 1/4 1 1/2 1 3/4

Lubricator, Plain
A551.

Size .. 0 1 2 3 4 5
Capacity, ozs. 1 1 1/2 1 3/4 2 1/2 4 5



Lubricator, Sight-Feed
A552.

Sizes .. 0 1 2 3 4 5
Capacity, ozs. 1 1 1/2 2 1/2 4 5 10



Order by Number Only.
Do Not Cut Catalogue.

The name "Daspyl" is your Guarantee of Highest Quality and Keenest Value.

SLUICE VALVES

A560.


FLANGED OR
FAUCET

Victorian Water
Supply and Mel-
bourne and Met-
ropolitan Board
of Works Stand-
ard

Valve and Chest
Gun Metal

Faced, and Gun
Metal Spindle
and Nut.

A561.



For Sluice Valve Covers
See Page 22

Size	Approx. Weight in lbs.	Flanged Length, Face to Face	Dia. of Flanges	Faucet Approx. weight in lbs.
3	90	8 1/2	7 1/2	100
4	120	9 1/2	8 1/2	123
5	173	10	10	191
6	223	10 1/2	11	248
7	364	12 1/2	12	358
8	431	15 1/2	13 1/2	420
9	564	15	14 1/2	549
10	595	16	16	576
12	813	14 1/2	18	728
13	850	15 1/2	19 1/2	850
14	952	16 1/2	20 1/2	950
15	1162	17 1/2	21 1/2	1128
16	1176	17 1/2	22 1/2	1176
18	1776	20 1/2	25 1/2	—
20	2128	18	27 1/2	1931
24	4032	21	32 1/2	4032

CAST IRON WATER PIPES, Crosses, Tees, Bends.




Cast Iron Crosses,
Faucet Ends
A562.

Sizes: 3", 4", 5", 6", 7", 8", 9",
10", 12".

Cast Iron Crosses, Faucet Ends
REDUCING

Size:	Size:	Size:
4" x 3"	8" x 5"	10" x 6"
5" x 3"	8" x 6"	10" x 7"
5" x 4"	8" x 7"	10" x 8"
6" x 3"	9" x 3"	10" x 9"
6" x 4"	9" x 4"	12" x 3"
6" x 5"	9" x 5"	12" x 4"
7" x 3"	9" x 6"	12" x 5"
7" x 4"	9" x 7"	12" x 6"
7" x 5"	9" x 8"	12" x 7"
7" x 6"	10" x 3"	12" x 8"
8" x 3"	10" x 4"	12" x 9"
8" x 4"	10" x 5"	12" x 10"

In the above the first size given refers to diameter
of Main and the second size to that of the two
Branches.



Cast Iron Bends
A563.

90 DEGREES

With two Faucets

Made to special order only.

Cast Iron Springs
A564.

45 DEGREES

Sizes: 3", 4", 5", 6", 7", 8", 9", 10", 12".
Springs made to any degree to special order.




Cast Iron Bends
A565.

90 DEGREES

SPIGOTS & FAUCETS

Sizes: 3", 4", 5", 6", 7", 8", 9",
10", 12".



Cast Iron Tees,
Faucet Ends
A566.

All equal

Sizes: 3", 4", 5", 6", 7", 8", 9",
10", 12".

Cast Iron Tees
A567.

Faucet and Spigot in Main Faucet Branch
Sizes: 3", 4", 5", 6", 7", 8", 9", 10", 12".

Cast Iron Tees
A568

REDUCING

Faucet Ends

Sizes.

4" x 3"	8" x 5"	10" x 6"
5" x 3"	8" x 6"	10" x 7"
5" x 4"	8" x 7"	10" x 8"
6" x 3"	9" x 3"	10" x 9"
6" x 4"	9" x 4"	12" x 3"
6" x 5"	9" x 5"	12" x 4"
7" x 3"	9" x 6"	12" x 5"
7" x 4"	9" x 7"	12" x 6"
7" x 5"	9" x 8"	12" x 7"
7" x 6"	10" x 3"	12" x 8"
8" x 3"	10" x 4"	12" x 9"
8" x 4"	10" x 5"	12" x 10"

Cast Iron Water Pipes
A569.

WITH SHALLOW FAUCET

Designed specially to economize
Lead in jointing.



Victorian Water Supply and
M.M.B.W. Standard

Size	Approx. Weight per 9' length c. qr. lbs.	Approx. Weight per 12' length c. qr. lbs.	Thickness
3	1 0 10	—	1/16
4	1 1 20	—	1/16
5	2 0 14	—	1/16
6	2 1 24	—	1/16
7	3 0 7	4 0 17	1/16
8	3 2 23	4 3 9	1/16
9	4 2 21	6 0 2	1/16
10	5 1 23	7 0 14	1/16
12	6 3 18	9 0 0	1/16

Pipes over 6" diameter made only in 12 ft. lengths
unless specially requested in 9 ft. In latter case an
extra rate is charged

The approximate weight of Lead used in jointing
these pipes is as follows—3", 2 1/2 lbs.; 4", 3 1/2 lbs.;
5", 6 lbs.; 6", 8 lbs.; 7", 8 1/2 lbs.; 8", 9 1/2 lbs.; 9",
12 lbs.; 10", 14 1/2 lbs.; 12", 17 1/2 lbs.

Cast Iron Sockets
A570.

Sizes: 3", 4", 5", 6", 7", 8", 9",
10", 12".




Cast Iron Faucet and
Flanged Piece
A571.

Sizes: 3", 4", 5", 6", 7", 8", 9", 10",
12".

Cast Iron Thimbles
A572.

To Slip over Pipe

Sizes: 3", 4", 5", 6", 7", 8", 9",
10", 12".



Cast Iron Caps
A573.

If required we tap these caps to take
W.I. Pipe.

Sizes: 3", 4", 5", 6", 7", 8", 9", 10", 12".



Cast Iron Dead Ends
A574.

If required we tap these Dead Ends to
take W.I. Pipe.

Sizes: 3", 4", 5", 6", 7", 8", 9", 10", 12".



Cast Iron Flanged
Crosses
A575.

Made to special order only.



Cast Iron Bends
A576.


90 DEGREES

Flanged Ends

Made to special order only.

Cast Iron Flanged
Pipes
A577.

Faced Ends. In 9 ft. lengths.
Sizes: 3", 4", 5", 6".




Cast Iron Flanged
Tees
A578.

Made to special order only.

Cast Iron Distance
Pieces
A579.

For Fire Plugs, etc.

Diameter: 3". In 6", 9", 12", 15",
18" and 24" lengths.



Cast Iron Spigot
and Flanged
Piece
A580.

Sizes: 3", 4", 5", 6", 7",
8", 9", 10", 12".

Cast Iron Tees, Fire Plug
A581.

With Outlet to Suit Fire Plugs

Sizes: 3", 4", 5", 6", 7", 8", 9",
10", 12".



Sluice Valve Keys
A582.

Long (as illustrated).
Short, made in one piece.





C.I. Bolted Thimbles
A583.

For Repairing Fractures in C.I. Mains, etc.
Sizes: 2", 2½", 3", 4", 5", 6", 9".

FIRE PLUGS AND ACCESSORIES



Fire Plugs
A584.

Victorian Water Supply and Melbourne and Metropolitan Board of Works Standard. Supplied complete with Balls and Washers

Fire Plugs, Patent Spring
A585.

The action of these will be readily understood by a study of the sectional drawing herewith. In place of the usual ball, a Gun Metal Spherical Segment is substituted, and kept in place against the ring by the springs as shown. This keeps all offensive matter out of the mains when the pressure is low. Another important point is that in hot districts the India Rubber, Ebonite or other balls quickly perish or crack, necessitating frequent renewals, while in this type the fault is impossible. We have supplied these Fire Plugs in large quantities to the Country Water Trusts in this and other States.



Copper Cage
A586.

With heavy Brass Spring for inserting into Fire Plugs in order to keep the ball against the seat when the pressure in main is low. Also showing Ebonite Fire Plug Ball



C.I. Flanges for Fire Plugs
A587.

Used for connecting Fire Plugs to Wrought Iron Pipe Mains, with bolt holes to suit flanges of Fire Plugs and tapped for pipe sizes: 1½", 2", 2½", 3".



Fire Plug Covers
A588.

Victorian Water Supply and Melbourne and Metropolitan Board of Works Standard.

These covers are made to suit M.M.B.W. Standard Fire Plugs.



C.I. Inspection Boxes
A589.

In one size only and stocked by Sydney House.


Sluice Valve Covers
A590.

Victorian Water Supply and Melbourne and Metropolitan Board of Works standard.



C.I. Footpath Boxes
A591.

FOR STOP COCKS
Sizes, inside measurement: 4" x 4", shallow; 4" x 4", deep.



Also Flat Covers for leading into Stone Flags, Horse Shoe Shape.



C.I. Footpath Box
A592.

New Pattern

For Concrete Roads.
Size: 6½" x 6½".

C.I. Footpath Box
A593.

Fitzroy Pattern



C.I. Footpath Box
A594.

For Stop Cocks
Sydney Water Board Standard Pattern.
Stocked by Sydney House only.



PILLAR HYDRANTS
A595.

This type of Street Hydrant is now being used in place of the ordinary Fire Plug by the Melbourne and Metropolitan Board of Works, and is usually fixed on kerb or footpath. Single Outlet, as shown, and Double Outlet.

Can also be supplied with Flanged Base to sit on Tee Piece if required.

Blow-Off Hydrant Valves
A596.

For Double Hydrants.
Size: 2½" F.B.



Screw Down Hydrant
A597.

With 3" Flange

Body of Cast Iron with Bronze Gland and Valve Seat.



Main Clips
A598.

WROUGHT IRON
To prevent cracking or fracturing C.I. Mains when tapping for water service, or when used blank for repairing or strengthening mains. Made with four bolts as shown, and also with two bolts.

Size of Main	Size of Tapping	Size of Main	Size of Tapping
2½"	1"	7"	2"
3"	1"	8"	2"
4"	1"	9"	2"
5"	1½"	10"	2"
6"	1½"	12"	2"



Main Clip
A599.


MALLEABLE IRON

Very useful for repair purposes oft preventing the necessity of putting in a new length of pipe.
Sizes: ½", ¾", 1".



Clips for W.I. Pipe
A600.

Size of Pipe	Size of Tapping
1½"	1"
1¾"	1"
2"	1"
2½"	1"
3"	1"
3½"	1"
4"	1"
4½"	1"
5"	1"
5½"	1"
6"	1"



C.I. "D" Retention or Back Pressure Valves
A601.

FOR WATER MAINS

Made in 3" and 4" Flanged or Spigot and Faucet Ends; 5" up to 8" Flanged ends only.



A602.

As above, Flanged.


C.I. Hatch Boxes
A603.

FOR WATER MAINS

Used for the purpose of enabling Mains to be scraped and cleaned
Sizes: 4", 5", 6", 7", 9", 12".



Above illustration shows section of Hatch Box.



Mill Cocks
A620.

Gun Metal Flanged

This Cock is made for fixing underground in brick pits, and is for use in the yards of workshops, etc., where anything projecting above ground is likely to be damaged.

These cocks are largely used by the Victorian Railways.
Size: 2" with 2½" Nut and Tail.
C.I. Covers and Frames for same to fit Pits, inside measurement: 18½" square.



C.I. Air Escape Valves
A621.

For Water Mains

Screwed or Flanged.
Sizes: 1", 1½", 2", 2½", 3", 4".



Brass Air Escape Valves
A622.


For Wrought Iron Pipes

Sizes: ½" and ¾" Gas.



Jets and Cones
A623.

When fitted in a W.I. Tee Piece as shown in sectional drawing, this handy contrivance is used as an ejector for emptying cellars, basements, etc., of water. In fixing it may be found necessary to adjust the Jet to get the desired result
Sizes: ½", ¾", 1".



Concussion Jet
A624.

Used in fitting up Press Button Spring Cocks to stop jarring in Water Pipes when Cocks are shut off.
Size: ¾".



Cold Water Ejector
A625.


An efficient appliance for raising water from cellars, basements, etc., by means of the water pressure from street mains.
Sizes: ½", ¾", 1", 1½".



FOR HIGHEST QUALITY, INSIST ON "DASPYL"

Automatic Water Ejectors

AUTOMATIC SYPHONS or CELLAR PUMPS



(1)

Automatic Water Ejector, "Daspyl" A626.

Patent Automatic Syphon or Cellar Pump, worked by water pressure from ordinary main, a connection being made from the service pipe to the inlet of the valve, which is operated by the lever attached to a copper float. This float is set to hang in an excavation below the cellar floor, into which all water accumulating, drains. As the water rises it acts upon the float, thus opening the valve, the syphon immediately ejecting the water into the street channel or elsewhere through the delivery pipes. As the water falls in the excavation in the cellar, so also does the copper float, which closes the valve and stops the syphon from working until the water rises sufficiently to open valve. Sizes: $\frac{1}{2}$ ", 1".


(2)

Automatic Water Ejector A627.

An improved Automatic Syphon which has an action on the high pressure inlet, whereby it



(2)



(3)

does not operate till the well in which the syphon works is full. It then lets in the high pressure, which continues till the well is empty. By thus it will be seen that any waste through the syphon "dribbling" is saved. Size: $\frac{1}{2}$ ".

Automatic Water Ejector A628.

Made in two sizes: $\frac{1}{2}$ " with 1" discharge; 1 $\frac{1}{2}$ " with 2" discharge.

Directions for Fixing:

The size of the well required is 1' 9" x 1' x 2' deep. It firmly fitted with iron pipes no other support is required. Do not fix the Ejector lower down than is necessary; every foot lower may mean much extra drainage and also greater proportionate cost to elevate. No stop cocks or unions are required, but may be used for convenience in fixing. Keep the well as clear of refuse as possible, as owing to the very strong suction in this Ejector some of the perforations are liable to become clogged with paper, etc., and so prevent the greatest economy possible. With this view in mind it is well to unscrew and clean out the suction pipe say once or twice a year, or as occasion might require.




Malleable Iron Unions A635.

Galvanised and Black
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 4".

Unions, Iron with Brass Seat A636.

Galvanised and Black
This union is a great favourite with Steam and other Fitters, the iron to brass connection preventing rusting. The ground Ball Joint dispenses with Gasket and makes a tight connection even though the alignment of pipe be imperfect. Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2".



Hexagon Nipples A637.

Supplied in Black, Galvanised or Steam Malleable Iron.

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 4".
3" x $\frac{1}{2}$ ", $\frac{3}{4}$ " x $\frac{1}{2}$ ", $\frac{3}{4}$ " x $\frac{3}{4}$ ", $\frac{3}{4}$ " x 1", 1" x $\frac{1}{2}$ ", 1 $\frac{1}{2}$ " x 1", 1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ ", 2" x 1 $\frac{1}{2}$ ", 2 $\frac{1}{2}$ " x 2", 3" x 2 $\frac{1}{2}$ ".

Order by Number Only—
DO NOT CUT CATALOGUE.



A638.

Malleable Iron Bushes Galvanised and Black

Sizes: $\frac{1}{2}$ " x $\frac{1}{2}$ ", $\frac{3}{4}$ " x $\frac{1}{2}$ ", $\frac{3}{4}$ " x $\frac{3}{4}$ ", $\frac{3}{4}$ " x 1", 1" x $\frac{1}{2}$ ", 1" x $\frac{3}{4}$ ", 1" x 1", 1 $\frac{1}{2}$ " x $\frac{1}{2}$ ", 1 $\frac{1}{2}$ " x $\frac{3}{4}$ ", 1 $\frac{1}{2}$ " x 1", 1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ ", 2" x $\frac{1}{2}$ ", 2" x $\frac{3}{4}$ ", 2" x 1", 2" x 1 $\frac{1}{2}$ ", 2 $\frac{1}{2}$ " x 1", 2 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ ", 2 $\frac{1}{2}$ " x 2", 3" x 1", 3" x 1 $\frac{1}{2}$ ", 3" x 1 $\frac{1}{2}$ ", 3" x 2", 3" x 2 $\frac{1}{2}$ ", 4" x 2", 4" x 2 $\frac{1}{2}$ ", 4" x 3".

"DASPYL" means QUALITY.




Lead Main Connections A629.

Made in Light and Heavy Weight.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 2"

Rathbone Nipples A630.


For inserting into Fibrolite Pipe when a tapping is necessary.

Size: $\frac{1}{2}$ ".




Lever or Wrenches for Cocks A631.

Malleable Iron




Square



Diamond

Long W.I. Nipples A632.

Galvanised or Black
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 2", 2 $\frac{1}{2}$ ", 3", 4"; each size in lengths of 3", 4", 6".



Space W.I. Nipples A633.

Galvanised or Black

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 2". Also in Brass.



Malleable Iron Return Bends A634.

OPEN PATTERN
Galvanised or Black

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 2".



Malleable Iron Three-Way Elbows A639.

With Extra Branch or Side Outlet
Galvanised and Black.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 2".



Malleable Iron Four-Way Tees A640.

With Extra Branch or Side Outlet
Galvanised and Black.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 2".



Malleable Iron Five-Way Crosses A641.

With Extra Branch or Side Outlet
Galvanised and Black.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 2".



Malleable Iron Y Pieces A642.

Galvanised

Branch is at an angle of about 45 degs.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 2", 2 $\frac{1}{2}$ ", 3", 3 $\frac{1}{2}$ ", 4".

PRESSED STEEL SPLIT PULLEYS

A643.

Prices on application.

Sizes: Diameter from 3" up to 60".

Width of face: 2" up to 12".




WOOD SPLIT PULLEYS

A644.

Prices on application.

Sizes: Diameter from 4" up to 48".

Width of face: 3" up to 12".



1.

2.

3.

4.



5.



6.



7.



8.



9.



10.



11.



12.

Malleable Iron Fittings

A645.

Galvanised and Black.

(1) Bends, Male and Female

(2) Bends, Female.

(3) Elbows, Female.

(4) Elbows, Male and Female.

(5) Tees (even and reducing).

(6) Crosses (even and reducing).

(7) Caps.

(8) Locknuts.

(9) Sockets (plain and reducing).

(10) Flanges.

(11) Plugs.

(12) Junctions, 45 degrees.

Tees, Elbows and Crosses also obtainable with Side Outlet.

WROUGHT IRON PIPES and FITTINGS

DANKS for PICKS, CROWBARS, SHOVELS & EXCAVATING TOOLS

WROUGHT IRON PIPES AND FITTINGS

A646.

Note—Iron Pipe sizes are the internal diameters of the pipes, and the fittings screwing on the outside of the pipe are said to be of the size of the pipe they fit.

No. Internal Diameter in Inches

TUBES—

1. Tubes.
2. Long Screws, 3 to 23 1/2" long
3. Bends.
4. Springs, not socketed.


FITTINGS—

5. Elbows, square.
6. Elbows, round.
7. Tees.
8. Crosses.
9. Sockets, plain.
10. Sockets, Reducing
11. Flanges.
12. Caps.
13. Plugs.
14. Backnuts.
15. Nipples.

COCKS—

16. Main Cocks, Cast Iron.
17. Main Cocks, with Brass Plugs.

For approximate weights of W.I. Pipes and Fittings, see Page 30.



Australian Leather Belting

Australian Leather Belting

A647.

Sizes from 1" up to 6".

SOLID ROUND LEATHER BELTING

Sizes: 3/16ths", 3/8", 5/16ths", 1/2", 3/4", 1".



"Flexo-Grip" Belt Dressing

A648.

This Belt Paste adds life and gripping properties to belts, allowing them to be worked slack, and at the same time making it possible for them to generate more power than would be practicable if tight.

In 1 lb., 2 lb., 5 lb. and 10 lb. tins.
Also in 1 lb. sticks.

Belt Fasteners, Belt Lacing, Shafting, Ball Bearings, Pulley Couplings, Hangers and other Transmission Goods.

"PENETRENE"

A649.

THE JOINT BREAKER

"Penetrene" is the greatest help to engineers for removing rusted nuts in any type of work. Put up in 6 oz., 15 oz., 1 qt., 1/2 gal., 1 gal., 4 gal. tins, and 5 gal. Drums.

Flake or Powdered Graphite

A650.


FINE OR COARSE

In 1 lb., 5 lb. and 10 lb. tins.



DANKS' FOR BATHS AND BATHROOM ACCESSORIES

BRASS GAS FITTINGS



A651.

A652.


A653.



A657.



A654.



A655.



A660.



A656.




A662.



A658.



A659.



A666.



A661.



A663.



A664.




A665.




A671.



A667.



A668.



A669.



A670.



A672.



A673.

BRASS GAS FITTINGS

A651—Compo Cocks, Tinned Ends. Sizes: $\frac{1}{2}$ ", $\frac{3}{8}$ ", $\frac{1}{4}$ ".

A652—Union Cock. Sizes: $\frac{3}{8}$ ", $\frac{1}{2}$ " Brass, and $\frac{1}{4}$ " Iron.

A653—Flexible Tube Cock. Sizes: $\frac{3}{8}$ ", $\frac{1}{2}$ " Brass, and $\frac{1}{4}$ ", $\frac{3}{8}$ ", $\frac{1}{2}$ " Iron. Male or Female.

A654—Cigar Cock for Brass. Size: $\frac{1}{2}$ " Brass.

A655—Male End Cock for Brass. Size: $\frac{3}{8}$ ".

A656—Nose Cock for Brass. Sizes: $\frac{3}{8}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ "; Iron, $\frac{1}{4}$ ", $\frac{3}{8}$ ", $\frac{1}{2}$ ".

A657—Pendant Cock. Sizes: $\frac{3}{8}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ " Brass; $\frac{1}{4}$ ", $\frac{3}{8}$ ", $\frac{1}{2}$ " Iron.

A658—Bunsen Rose or Atmospheric Burner. Sizes: $\frac{1}{4}$ ", $\frac{1}{2}$ ", $2"$, $2\frac{1}{2}"$, $3"$.

A659—Elbow Cock. Sizes: $\frac{3}{8}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ " Brass; and $\frac{1}{4}$ ", $\frac{3}{8}$ ", $\frac{1}{2}$ " Iron.

A660—Single Swivel Cocks. Sizes: $\frac{1}{2}$ " x $\frac{3}{8}$ ", $\frac{3}{4}$ " x $\frac{1}{2}$ ", $\frac{1}{2}$ " x $\frac{3}{8}$ " Brass; $\frac{1}{4}$ " x $\frac{3}{8}$ ", $\frac{3}{8}$ " x $\frac{1}{2}$ " Iron.

A661—Brass Elbow. Sizes: $\frac{3}{8}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ", $1"$.

A662—Nose Pieces for Brass. Sizes: $\frac{3}{8}$ ", $\frac{7}{16}"$, $\frac{1}{2}"$, $\frac{3}{4}"$, $\frac{7}{16}"$ F. x $\frac{1}{2}"$ M., $\frac{1}{2}"$ F. x $\frac{1}{2}"$ M., $\frac{3}{4}"$ F. x $\frac{1}{2}"$ M., $\frac{3}{4}"$ F. x $\frac{3}{4}"$ M. Also Iron Pipe size, Female End.

A663—Ceiling Plate. Sizes: $\frac{3}{8}$ ", $\frac{1}{2}$ ", $\frac{3}{4}"$, $\frac{1}{2}"$, $1"$, $1\frac{1}{2}"$ Brass; $\frac{1}{4}"$, $\frac{3}{8}"$, $\frac{1}{2}"$, $1"$ Iron.

A664—Straight Dropscrew for Brass. Size: $\frac{3}{8}"$ x $1\frac{1}{2}"$.

A665—Brass Tee for Brass. Sizes: $\frac{3}{8}$ ", $\frac{1}{2}"$, $\frac{1}{2}"$ x $\frac{3}{8}"$, $\frac{3}{4}"$ x $\frac{1}{2}"$, $\frac{3}{4}"$, $1"$.

A666—Brass Cross for Brass. Sizes: $\frac{3}{8}$ ", $\frac{1}{2}"$, $\frac{3}{4}"$, $\frac{1}{2}"$.

A667—Elbow Dropscrew for Brass. Sizes: $\frac{3}{8}"$ x $1\frac{1}{2}"$, $\frac{1}{2}"$ x $1\frac{1}{2}"$.

A668—Double Swivel. Sizes: $\frac{3}{8}$ ", $\frac{1}{2}"$, $\frac{1}{2}"$ x $\frac{3}{8}"$, $\frac{3}{4}"$ x $\frac{1}{2}"$, $\frac{3}{4}"$ x $\frac{3}{4}"$ Brass; $\frac{1}{4}"$, $\frac{3}{8}"$, $\frac{1}{2}"$ x $\frac{1}{4}"$, $\frac{3}{8}"$, $\frac{1}{2}"$ x $\frac{3}{8}"$ Iron.

A669—Universal Swivels for Iron. Sizes: $\frac{1}{4}"$, $\frac{1}{2}"$ x $\frac{1}{4}"$, $\frac{3}{8}"$, $\frac{1}{2}"$ x $\frac{1}{4}"$, $\frac{3}{4}"$, $\frac{1}{2}"$ x $\frac{3}{8}"$, $\frac{3}{4}"$ x $\frac{1}{2}"$.

A670—Air Bulb for Iron. Sizes: $\frac{1}{4}"$, $\frac{3}{8}"$, $1"$, $1\frac{1}{2}"$.

A671—Flexible Tube Nozzle for Brass. Size: $\frac{3}{8}"$. Male or Female.

A672—Brass Socket for Brass. Sizes: $\frac{1}{4}"$, $\frac{3}{8}"$, $\frac{1}{2}"$ x $\frac{1}{4}"$, $\frac{3}{8}"$, $\frac{1}{2}"$ x $\frac{3}{8}"$, $\frac{3}{4}"$ x $\frac{1}{2}"$, $\frac{3}{4}"$ x $\frac{3}{4}"$, $1"$.

A673—Single Swivel. Sizes: $\frac{3}{8}"$, $\frac{1}{2}"$, $\frac{1}{2}"$ x $\frac{3}{8}"$, $\frac{3}{4}"$ x $\frac{1}{2}"$, $\frac{3}{4}"$ x $\frac{3}{4}"$ Brass; $\frac{1}{4}"$, $\frac{3}{8}"$, $\frac{1}{2}"$ x $\frac{1}{4}"$, $\frac{3}{8}"$, $\frac{1}{2}"$ x $\frac{3}{8}"$ Iron.

We also stock Fittings for the Installation of Bottle or Rock Gas.

A674. Italian Hemp Packing

A long strand packing for jointing screwed water pipes and fittings.

A675. Jute Packing

For Jointing C.I. Mains

A676. Lead Wire Packing

Sizes: 20, 18, 16, 14, 12 gauge. $\frac{1}{8}"$, $\frac{3}{16}"$, $\frac{1}{4}"$, $\frac{5}{16}"$, $\frac{3}{4}"$.



Fluxite Soldering Paste

A677.

A Flux that solders practically any metal (except Aluminium). Invaluable to engineers.

It does not corrode, and is thoroughly reliable for electrical work. With it dirty, greasy and even painted metals (except iron) may be soldered without cleaning or preparation. Being a paste, it can be safely carried in the Tool Bag. It is self adhesive, economical in use, and effects a big saving in time and solder. Put up in Handy Midget, Medium and Large Tins.

A678. Sheet Insertion

A general purpose packing. Made in $\frac{1}{32}"$, $\frac{1}{16}"$, $\frac{1}{8}"$, $\frac{3}{16}"$, $\frac{1}{4}"$, $\frac{5}{16}"$, $\frac{3}{4}"$ thick.



"Zenith" Twist Packing

A679.

(Any size by unstranding) In 1 lb. spools.

$\frac{1}{4}"$ contains 120 ft. to lb.
 $\frac{3}{16}"$ contains 75 ft. to lb.
 $\frac{1}{8}"$ contains 50 ft. to lb.

Made of a material that heat cannot affect, has high tensile strength, and each strand is so thoroughly saturated with graphite grease lubricant that it does not harden in service.

An ideal packing for small valve spindles such as globe valves, blow off cocks, injectors, etc.



"Jay-Dee" Sheet Packing

A680.

An excellent jointing for steam and motor work.

This packing makes a perfectly tight joint; one that will not squeeze, blow or burn out. Sold in sheets $39\frac{1}{2}"$ square, $\frac{1}{32}"$, $\frac{1}{16}"$, $\frac{1}{8}"$ and $\frac{3}{16}"$ thick.

A681. Pipe Joint Compound

This compound is a substitute for Red Lead. It makes as tight a joint, yet it preserves the threads and allows of the joints being disconnected with ease. It goes further, therefore it is cheaper, as well as better than Red Lead. In 1 lb., 5 lb., 10 lb. tins



Packings—Asbestos Cord or Yarn

A682.

Sizes: $\frac{1}{4}"$, $\frac{3}{16}"$, $\frac{1}{2}"$, $\frac{5}{16}"$.

Plated: $\frac{1}{4}"$, $\frac{3}{8}"$, $\frac{1}{2}"$, $1"$.

Asbestos Lagging

A683.

For Steam and Hot Water Pipes. Sizes: $\frac{1}{2}"$, $\frac{3}{4}"$, $1"$.



Do Not Cut Catalogue—
ORDER BY NUMBER.

DANKS' FOR ALL ELECTRICAL FITTINGS



**"Lomoto"
Packing
A684.**

Round or Square

Each strand a reservoir of lubricant. Plaited, round or square. For all steam pressures. Especially adapted to high pressure and superheated steam.

Does not harden in service.
Sizes stocked: $\frac{1}{8}$ ", $\frac{1}{4}$ ", $\frac{3}{8}$ ", $\frac{1}{2}$ ".

**Greasy Hemp Packing
A685.**

Sizes: $\frac{1}{8}$ ", $\frac{1}{4}$ ", $\frac{3}{8}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".

Hand plaited, soaked in tallow
A splendid packing for lifts and hydraulic work

You are cordially invited to write for particulars of any special size or design of any item in this Catalogue you may require.

Sundry Products—See also Pages 24, 25

**Agnew's Iron Cement
A686.**

A chemically prepared compound in powdered form, applied as a paste or putty.

Suitable for repairing leaks or breaks in castings and for making connections in steam or hydraulic work.

It is quick hardening. Sold in tins with directions in each.
 $\frac{1}{2}$ lb. and 1 lb. tins and larger.



**Asbestos Millboard
A688.**

In sheets 40 x 40".
Thickness: $\frac{1}{32}$ " to $\frac{1}{16}$ ", $\frac{1}{8}$ ", $\frac{3}{16}$ ", $\frac{1}{4}$ ".

**Leather Valve Washers
A689.**

For H.P. Cocks
Sizes: $\frac{1}{8}$ " up to 3".
Standard and Medium


**Fink Washers
A690.**

For Hot Water Cocks
Sizes: $\frac{1}{8}$ " up to 3".

**Baker's Soldering and
Tinning Flux
A691.**

Liquid Flux. The Super Flux for General Use. Quick, clean and economical. Tins as well as cans, and makes a clean, strong joint that will withstand any amount of strain.

In 3 $\frac{1}{2}$, 8, 12, 20, 32 fl. oz. tins, and in $\frac{1}{2}$ and 1 gal. cans and in bulk



**Hair Felt
A687.**

For Covering Hot Water Pipes

In sheets 32" x 20".

Also in Rolls 6 ft. wide with Hessian Reinforced Centre and Strips 36' long x 2" x 4".



**Case Hardening
Compound
A692.**

"KASENIT"

A uniform and effective Case Hardening Compound for all kinds of Iron and Steel.
In $\frac{1}{2}$ lb., 1 lb., 3 lb. and 7 lb. tins.

WATER METERS


A693.

NAMES OF WATER METER PARTS

As per Numbered Diagram and Illustration of Spare Parts.

1. Body.
2. Works Plate.
3. Top Frame.
4. Name Plate.
5. Drum, Spindle and Worm.
6. Dial Pan.
7. Dial.
8. Flap Lid.
9. Glass Retaining Ring.
10. Glass.
11. Nut and Tail (2), for Inlet and Outlet.
12. Drum Spindle.
13. Grease Cup.
14. Grease Cup Strainer.
15. Spring Bracket.
16. Tangent.
17. Balance Weight for Dial Pan.
18. Toe Pin.


19. Stuffing Box Spindle and (40) Wheel.
20. Intermediate (40) Wheel and Pinion.
21. (60) Wheel for Dial.
22. (100) Wheel for Dial.
23. (101) Wheel for Dial.
24. Tangent Wheel and Worm.
25. Dial Spindle.
26. Drum Spindle Worm.
27. German Silver Bush for Drum.
28. Stuffing Box Barrel.
29. Stuffing Box Cup.
30. Set Screw and Washer for Works Plate.
31. No. 2 Screw used on Toe Pin, Strainer and Tangent Bracket.
32. No. 3 Seal Screw for Works Plate.
33. No. 4 Seal Screw for Works Plate.
34. No. 5 Screw for Works Plate.
35. No. 6 Screw for Name Plate.
36. Large Hand.
37. Small Hand.
38. (Not illustrated), Leather Washer for No 12 Nut and Tail.



At left:

**Spare Parts of
Water Meter**

Refer to Table above for name, and diagram for location of parts.




FOR HIGHEST QUALITY, INSIST ON "DASPYL"

WATER METERS

(CONTINUED)

A694.



These Meters are made in Gun Metal throughout, in sizes from $\frac{1}{2}$ " to $1\frac{1}{2}$ ", and have screw connections. Sizes 2" to 12" are made with Cast Iron or Gun Metal bodies, have flanged connections and a separate dirt box.

Larger sizes are made to suit special requirements. These figures are in accordance with the Melbourne and Metropolitan Board of Works requirements, and we have supplied several thousands to that body. The amount of water a meter will deliver under above conditions is as follows:—

Meter delivers from	Gals. per hour
$\frac{1}{2}$ "	50 to 300
$\frac{3}{4}$ "	110 " 1000
1"	275 " 2500
$1\frac{1}{4}$ "	400 " 3500
$1\frac{1}{2}$ "	570 " 5000
2"	2000 " 7000
3"	4500 " 14,000
4"	7000 " 23,000
5"	10,000 " 32,000
6"	16,000 " 46,000

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2", 3", 4", 5", 6", 7", 8", 10", 12".



Cast Iron Cover A695.


For Water Meters
Two sizes to suit $\frac{1}{2}$ " to 1" Meters, and $1\frac{1}{4}$ " to $1\frac{1}{2}$ ".

Water Meter A696.

Sydney Water Board Standard
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2", 3".

The illustration represents Meters in $\frac{1}{2}$ " to $1\frac{1}{2}$ ".

The 2" and 3" Meters have separate Dirt Boxes. Stocked by Sydney House only.



Cast Iron Covers A697.

FOR WATER METERS
Sydney Pattern

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2", 3".



SPECIAL NOTE!

Nuts and Tails for Melbourne, Sydney and Adelaide.

Fire Hose Cocks and Unions (Figs. A698, A699, A700, A702, A703), in Col. 2, can be had in reducing sizes for $1\frac{1}{4}$ ", $1\frac{1}{2}$ " and 2" Canvas Hose.

FIRE HOSE COCKS HYDRANTS CAPS NUTS TAILS Etc



Fire Hose Cocks A698.


$5\frac{1}{8}$ Threads to inch.
(Sydney Standard)
Right Angle Pattern.
Made in three sizes.

Inlet		Outlet
2"	x	2"
2"	x	$2\frac{1}{2}$ "
$2\frac{1}{2}$ "	x	$2\frac{1}{2}$ "

Nuts and Tails supplied at extra cost if required.

Fire Hose Cocks A699.

$5\frac{1}{8}$ Threads to inch.
(Sydney Standard)
With 45 degrees Angle Nose.
Made in $2\frac{1}{2}$ " only.
Nuts and Tails supplied at extra cost if required.
Other Fire Brigade Standards made to specifications.



Fire Hose Cocks A700.

"Alexandra Pattern"
(FULLWAY)

5 Thread Melbourne Fire Brigade Standard.
Sizes: $1\frac{1}{2}$ ", 2" and $2\frac{1}{2}$ ".
Noses of all sizes screwed to take $2\frac{1}{2}$ " in F.B. Standard Nuts.
Also in 3 Thread Country F.B. Standard.


Canvas Hose A701.

Sizes: $1\frac{1}{2}$ ", 2", $2\frac{1}{2}$ ".
Also made in the same pattern to suit $5\frac{1}{8}$ Thread Sydney F.B. Standard; Country Fire Brigades Board Standard; Adelaide Fire Board Standard.

Fire Hose Cocks A702.

Stop Cock Pattern
Made in two sizes, both fitted with $2\frac{1}{2}$ " 5 Thread Melbourne F.B. Standard Nuts and Tails.

Size of Inlet: 2", $2\frac{1}{2}$ ".
Also made in same pattern to suit $5\frac{1}{8}$ Thread Sydney F.B. Standard.



Fire Hose Unions A703.

$2\frac{1}{2}$ " Gun Metal
5 Thread, Melbourne F.B. Standard.

Also made in Country Fire Brigade Board Standard; Adelaide F.B. Standard.

Fire Brigade Y Pieces A704.

$2\frac{1}{2}$ " Gun Metal
5 Thread Melbourne F.B. Standard.

Also made in Country Fire Brigade Board Standard; Adelaide F.B. Standard.



Gun Metal Hydrant Cap A705.

With Outlet Screwed,
1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2".
Melbourne F.B. Standard, $2\frac{1}{2}$ ", 5 Thread.
Sydney F.B. Standard, $2\frac{1}{2}$ ", $5\frac{1}{8}$ Thread.



Brass Hose Nuts and Tails A706.

5 Thread Nut with Tail.
Screwed $2\frac{1}{2}$ " Gas Thread.
Melbourne F.B. Standard.

Gun Metal Hydrant Cap A707.

Melbourne F.B. Standard, $2\frac{1}{2}$ ", 5 Thread.
Sydney F.B. Standard, $2\frac{1}{2}$ ", $5\frac{1}{8}$ Thread.



A708.

Brass Matching Pieces

5 Thread Melbourne F.B. Standard.
 $2\frac{1}{2}$ " F.B. to Gas Thread.
Sizes: $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2", $2\frac{1}{2}$ ", 3".

Copper Fire Hose Directors A709.

5 Thread Melbourne F.B. Standard.
Size .. $1\frac{1}{2}$ " $1\frac{1}{4}$ " 2" $2\frac{1}{2}$ " $2\frac{1}{2}$ " $2\frac{1}{2}$ " $2\frac{1}{2}$ " $2\frac{1}{2}$ "
Length .. 16" 17" 18" 12" 18" 24" 30" 36"
With or Without Loose Male Ends.
 $5\frac{1}{8}$ Thread, Sydney F.B. Standard.

Country Fire Brigade Board Standard.
Adelaide F.B. Standard.

Canvas Hose A710.

We stock good quality Canvas Hose for Fire Extinction, Street Sluicing, etc., in the following sizes:—
1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2", $2\frac{1}{2}$ ", 3".



Hose Bracket (SWINGING) A711.

For Canvas Hose
In sizes to take:
100 ft. of $2\frac{1}{2}$ "
100 ft. of 2"
100 ft. of $1\frac{1}{2}$ "




Fireman's Key A712.

For Couplings, Hydrants.
Finished in Japanned Steel, Polished Steel, Polished Steel and Nickel Plated.

FIRE HYDRANTS A713.


With Copper Barrels, Gun Metal Mountings and Revolving Heads
Made in: Single Head as shown, Double Head, Double Head with Lever Handle and three Thread Competition Outlets. For those requiring a very light Hydrant we make them in Aluminium, single and double head, the weight of a Double Hydrant in this metal being approximately 8 lbs.

These Hydrants are made to suit Standard Fire Plugs.



Street Watering Hydrants A714.

With Universal Joint and 30" Director.
5 Thread Standard Outlet.



Bi-Sulphide Injector

A715.

Component Parts (See Fig. on left)



This highly efficient injector is largely and successfully used to eradicate pests on sugar cane, etc.

Fig.

1. Plunger Handle.
2. Pins for Locking Ring.
3. Locking Ring.
4. Measuring Socket.
5. Collar.
6. Plunger.
7. Pin.
8. Setscrew.
9. Plunger Casing.
10. Handle Rod.
11. Handle.
12. Cap Nut.
13. Filling Plug.
14. Top of Container.
15. Tube Container.
16. Plunger Spring.
17. Bottom of Container.
18. Packing Washer.
19. Washer.
20. Gland.

Fig.

21. Ball.
22. Stop Pin.
23. Nut.
24. Valve Rod.
25. Valve Tube.
26. Valve Spring.
27. Valve Seat.
28. Valve Washer.
29. Valve Nut.
30. Setscrew.
31. Footstep.
32. Driving Spike.
33. Valve Casing.
34. Washer.
35. Pins for Measuring Socket.
36. Plunger Guide.
37. Collars for Plunger.
38. Pin for Collar.
39. Washer.
40. Valve Seat Washer.



COPPER TUBES

Australian Commonwealth Standard

As Specified by the Melbourne and Metropolitan Board of Works and Sydney Water Board for Reticulation Purposes.
For Working Pressure up to 200 lbs. per Square Inch.

TABLE I.

Suitable for Screwed Connections.

Nominal Outside Diameter	Actual Outside Diameter	Wall Thickness	Inside Diameter of Tube	British Standard Pipe Thread	Number of Threads per Inch	Wall Thickness at Root of Thread	Calculated Weight
Inches	Inches	S.W.G.	Inches	Inches	Inches	Inches	Lbs. per lin. ft.
$\frac{3}{8}$	0.381	16	0.064	0.253	$\frac{1}{8}$	28	0.042
$\frac{1}{2}$	0.515	14	0.080	0.355	$\frac{1}{4}$	19	0.048
$\frac{5}{8}$	0.622	13	0.092	0.538	$\frac{3}{8}$	14	0.048
$1\frac{1}{8}$	1.038	13	0.092	0.854	$\frac{1}{2}$	14	0.048
$1\frac{3}{8}$	1.289	12	0.104	1.081	1	11	0.056
$1\frac{1}{2}$	1.630	12	0.104	1.422	$1\frac{1}{2}$	11	0.056
$1\frac{3}{4}$	1.862	12	0.104	1.654	$1\frac{3}{4}$	11	0.056
$2\frac{1}{8}$	2.335	11	0.116	2.103	2	11	0.064
$2\frac{3}{8}$	2.948	11	0.116	2.716	$2\frac{3}{8}$	11	0.064
$3\frac{1}{8}$	3.456	10	0.128	3.200	3	11	0.072

TABLE II.

Suitable for Compression or Brazed Joints.

External Diameter	Wall Thickness	Calculated Weight	External Diameter	Wall Thickness	Calculated Weight
Inches	S.W.G.	Lbs. per lin. ft.	Inches	S.W.G.	Lbs. per lin. ft.
$\frac{3}{8}$	19	0.10	$\frac{1}{2}$	16	1.31
$\frac{1}{2}$	19	0.22	$\frac{3}{4}$	16	1.50
$\frac{5}{8}$	18	0.41	$1\frac{1}{8}$	14	2.34
1	18	0.55	1	14	2.83
$1\frac{1}{8}$	16	0.92	$1\frac{3}{8}$	12	4.28
$1\frac{1}{4}$	16	1.11	1	12	4.91

Useful Information

WEIGHT OF A SUPERFICIAL FOOT OF PLATES, DIFFERENT METALS, IN LBS.

Thickness Inches	Iron	Steel	Brass	Copper	Lead	Zinc	Thickness Inches	Thickness Millimetres
$\frac{1}{16}$	2.5	2.6	2.7	2.9	3.7	2.3	.0625	1.59
$\frac{1}{8}$	5	5.1	5.5	5.8	7.4	4.7	.125	3.17
$\frac{3}{16}$	7.5	7.7	8.2	8.7	11.1	7.0	.1875	4.76
$\frac{1}{4}$	10	10.2	11.0	11.6	14.8	9.4	.25	6.35
$\frac{5}{16}$	12.5	12.8	13.7	14.5	18.5	11.7	.3125	7.94
$\frac{3}{8}$	15	15.3	16.4	17.2	22.2	14.0	.375	9.52
$\frac{7}{16}$	17.5	17.9	19.2	20.0	25.9	16.4	.4375	11.11
$\frac{1}{2}$	20	20.4	21.9	22.9	29.5	18.7	.5	12.7
$\frac{9}{16}$	22.5	23.0	24.6	25.7	33.2	21.1	.5625	14.29
$\frac{5}{8}$	25	25.5	27.4	28.6	36.9	23.4	.625	15.87
$\frac{11}{16}$	27.5	28.1	30.1	31.4	40.6	25.7	.6875	17.46
$\frac{3}{4}$	30	30.6	32.9	34.3	44.3	28.1	.75	19.05
$\frac{13}{16}$	32.5	33.2	35.6	37.2	48.0	30.4	.8125	20.64
$\frac{7}{8}$	35	35.7	38.3	40.0	51.7	32.8	.875	22.22
$\frac{15}{16}$	37.5	38.3	41.2	42.9	55.4	35.1	.9375	23.81
1	40	40.8	43.9	45.8	59.1	37.5	1.000	25.4

For Metals ordered by measure, the following may be regarded as equivalents:—

$\frac{1}{4}$ inch as equal to 3 W.G.	$\frac{3}{32}$ inch as equal to 13 W.G.
$\frac{3}{16}$ " " " " 7 "	$\frac{1}{16}$ " " " " 16 "
$\frac{1}{2}$ " " " " 10 "	$\frac{1}{32}$ " " " " 21 "

DANKS' FOR TOOLS FOR EVERY TRADESMAN

LEAD PRODUCTS..

LEAD PIPE

A553.

Three-eighth Inch to Six Inches
Coils up to 1" weigh about 1½ cwt. each.

Size, ins.	Weight in lbs. per yard
¾	2½, 3.
1	3, 4½, 5, 6.
1½	5, 7½.
2	4½, 5, 6, 7, 8, 9, 12.
2½	5, 6, 7, 8, 9, 10, 12, 15.
3	9, 10, 12, 14, 17, 22.
3½	7½, 10, 11, 13, 16, 20, 27, 30.
4	17, 19, 21.
5	17, 18, 20, 25, 28, 40, 45.
6	21, 27, 29, 37, 60.
8	21, 24, 27, 30, 34, 40.
10	27, 40.
12	20, 28, 34, 40, 60.

The standard weights for high pressures are: ¾", 6 lbs.; 1", 9 lbs.; 1½", 15 lbs.; 2", 22 lbs.; 2½", 30 lbs.; 3", 45 lbs. to the yard.

Unless otherwise ordered, we always forward High Pressure Lead Pipe.

We can also supply: 2½", 19½ lbs. to the yard. 6", 36 lbs. and 60 lbs. to the yard.

COMPO. PIPE FOR GAS

A554.

Inside Diameter	Approx. Weight per yd., Ordinary	Approx. Weight per yd., Heavy
¾	12 ozs.	—
1	15 ozs.	2 lbs. 10 ozs.
1½	2½ lbs.	3 lbs.
2	3 lbs.	4½ lbs.
2½	4½ lbs.	5 lbs. 10 ozs.
3	6 lbs.	—

LEAD SOIL AND WASTE PIPE

We stock the above as shown in table herewith. It is made in 11 ft. lengths, and the thickness is equal to that of Sheet Lead as given. The approximate weights per length are appended for each size.

Thickness equal to Sheet Lead		6 lbs.	7 lbs.	8 lbs.	10 lbs.
Size	Length in feet	Approx. weight per length in lbs.			
1½	11	24	27½	32	—
1½	11	28	32½	38	—
1½	11	32	38	42½	—
2	11	36	43	47½	—
2½	11	47	55	64	—
3	11	56	66	75	—
4	11	73	86	99	125

We also make up Waste Pipe, in 60 ft. Coils, as follows.—

1½", equal to 6 lbs. Sheet Lead.
1½", equal to 7 lbs. Sheet Lead.
1½", equal to 7 lbs. Sheet Lead.
1½", equal to 6 lbs. Sheet Lead.

¾", 4½ lbs., and 1", 6 lbs., to the lineal yard is also used and stocked as Waste Pipe.

TIN PIPE


Size in Inches	Approx. Weight per yard	Size in Inches	Approx. Weight per yard
outside dia.	5 ozs.	¾ inside dia.	24 ozs.
"	7½ ozs.	"	13 ozs.
inside dia.	9 ozs.	"	30 ozs.
"	10 ozs.	"	2 lbs.
"	16 ozs.	"	3 lbs.
"	10 ozs.	1	3½ lbs.

Larger Sizes to Special Order

TIN-LINED LEAD PIPE

We make this description of Pipe with a pure Tin Lining to suit the requirements of the Board of Health in the "Pure Food Act." It is approved of in two sorts, viz.:—Light Tin Lined Lead Pipe and Heavy Tin Lined Pipe. They both weigh about 1 lb. to the lineal foot; ¾" Pure Tin Pipe is also approved of, and it weighs about ½ lb. to the lineal foot.

Size ¾" only in Light and Heavy Weight.



Lead Tennis Court Lines A555.

Made in sets sufficient to mark a full-sized tennis court.

In widths, 1" and 2"; 1½" and 2".

Special Nails can be supplied for fixing the lines; 50 lbs. being required for one court.

Lead Damp Course A556.

Made in widths: 4½", 9", 14", 18".

Weights: 1 lb., 2 lbs., 3 lbs. and 4 lbs. to the square foot

Lead Wool A557.

For Caulking the Joints of Water Mains
Made in Hanks weighing approximately 1 lb.



Lead Wire A558.

Made in 20 gauge up to ½" in diameter



SHEET LEAD A559.

The following are the usual sizes in which Lead is rolled, but a slight variation in the length is occasionally met with.

Weight per Sq. Foot	Length	Width	Approximate Weight
2½	25ft.	7ft. 4in.	4cwt. 0qr. 10lbs.
3	30ft.	7ft. 8in.	6cwt. 0qr. 18lbs.
3½	30ft.	7ft. 8in.	7cwt. 0qr. 21lbs.
4	34ft.	7ft. 9in.	9cwt. 1qr. 18lbs.
4½	34ft.	7ft. 9in.	10cwt. 2qr. 10lbs.
5	34ft.	7ft. 9in.	11cwt. 3qr. 1lb.
6	34ft.	7ft. 9in.	14cwt. 0qr. 13lbs.
7	34ft.	7ft. 9in.	16cwt. 1qr. 24lbs.
8	34ft.	7ft. 9in.	18cwt. 3qr. 8lbs.

Rolls of Lead, 4 lbs. to 8 lbs., can be supplied on special order 40 ft. long by 8 ft. wide. Lead can be rolled ½" up to 1" thick on special order, but not more than 30 ft. long.

BELLS

Australia's Finest Quality



FOR CHURCHES, SCHOOLS, SHIPS, FIRE TOWERS, etc. A438.

For many years past our Bells have been used throughout the Commonwealth and in the Islands. They are made of genuine bell metal, and possess the real bell tone.

Bells up to 20" diameter can be fitted with our Patent Jointed Clappers and Triggers, which obviate the necessity of swinging the bell, and allow of the ropes being conducted to the most convenient position.

We make angle steel towers for use where belfries are not available, and all types of structures for hanging bells.

Sizes and Approximate Weight of Bells

(All bells are measured across the mouth.)

Size	Approx. Weight	Size	Approx. Weight
8	12 lbs.	18	141 lbs.
9	20	20	210
9½	24	22	280
10	30	24	339
11½	44	25	390
12	50	26	452
13½	60	28	585
14	75	36	1065
16	106	38½	1344

Unless otherwise ordered, Bells with ordinary Clapper will be sent.

Patent Clappers and Gudgeons with bearings for mounting are made to suit different size bells.

A439. Hand Bells
Sizes: 6" and 7".

A440.

Mining Gongs

Gong made in Bell Metal and Frame in Wrought Iron.
Sizes: 6", 7", 8", 9", 10", 12".

DANKS' FOR THE LATEST IN WALLPAPERS

METALS

Aluminium Sheet

Sizes: 4' x 2', 6' x 3'.
Gauges: 14, 16, 18, 20, 22, 24, 26, 28

Brass Sheet

SOFT AND HARD

Sizes: 4' x 2', 6' x 3', 6' x 2', 6' x 2' 6", 6' x 3'.
Gauges: 10, 12, 14, 16, 18, 20, 22, 24, 26, 28.

Brass Strip

Sizes: 3", 3", 1", 1 1/2", 1 1/2", 2" wide.
Gauges: 18, 16.

Brass Rod

Sizes: Round—3/16", 1/4", 5/16", 3/8", 7/16", 1/2", 9/16", 5/8", 11/16", 3/4", 13/16", 7/8", 15/16", 1", 1 1/8", 1 1/4", 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2", 3".

Sizes: Square—3/16", 1/4", 5/16", 3/8", 7/16", 1/2", 9/16", 5/8", 11/16", 3/4", 13/16", 7/8", 15/16", 1", 1 1/8", 1 1/4", 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2", 3".

Sizes: Hexagon—1/2", 5/16", 3/8", 7/16", 1/2", 9/16", 5/8", 3/4", 1", 1 1/8", 1 1/4", 1 1/2", 1 3/4", 2".

Brass Bar

EXTRUDED

Sizes: 1/2", 3/4", 1", 1 1/4", 1 1/2", 2" wide; 1/2", 3/16", 1/2" thick.

Brass Tubing

HARD DRAWN

Gauge: 22 x 3/8", 5/16".
" 20 x 1/2", 5/16".
" 18 x 5/8", 3/4", 3/8", 1", 1 1/4", 1 1/2", 2".
" 16 x 3/4", 1", 1 1/4", 1 1/2", 1 3/4", 2".
" 14 x 1 1/4", 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2", 3".
" 12 x 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2", 3".
" 10 x 1 3/4", 2", 2 1/4", 2 1/2", 3".
" 8 x 2", 2 1/4", 2 1/2", 3".
" 6 x 2 1/4", 2 1/2", 3".
" 4 x 2 1/2", 3", 4", 5", 6".
" 10 x 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2", 3".
Gauge: 12 x 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2", 3".
Gauge: 11 x 2 5/16", 2 3/4", 3".
Screwing: 1 1/2" Gas, 1 3/4" Gas, 2" Gas.

Copper Sheet

HOT AND COLD ROLLED

Sizes: 6' x 2', 6' x 2' 6", 6' x 3', 6' x 4', 8' x 4'.
Gauges: 26, 28.
Weights: 1, 1 1/2, 1 3/4, 2, 2 1/2, 3, 4, 5 and 6 lbs. per square foot.

Ribbon Copper

Sizes: 6" and 12" wide.
Gauges: 34, 36, 38, 40.

Copper Bar

ROUND AND SQUARE

Sizes: 1/4", 5/16", 3/8", 7/16", 1/2", 9/16", 5/8", 3/4", 1", 1 1/8", 1 1/4", 1 1/2", 1 3/4", 2".

Copper Bus Bar

Sizes: 1/2", 3/4", 1", 1 1/4", 1 1/2", 2" wide; 1/2", 3/16", 1/2", 3/8" thick.

Copper Tube

ANNEALED

Gauge: 20 x 3/16", 1/4", 5/16".
" 20 x 1/2" in 20' lengths.
" 18 x 3/8", 1/2".

HARD DRAWN

Gauge: 22 x 3/8".
" 20 x 1/2", 5/16".
" 18 x 5/8", 3/4", 3/8", 1", 1 1/4", 1 1/2", 1 3/4".
" 16 x 3/4", 1", 1 1/4", 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2".
" 14 x 1 1/4", 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2", 3", 4".
" 12 x 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2", 3".
" 10 x 1 3/4", 2", 2 1/4", 2 1/2", 3".
" 8 x 2", 2 1/4", 2 1/2", 3".
" 6 x 2 1/4", 2 1/2", 3".
" 4 x 2 1/2", 3", 4", 5", 6".

Gauge: 13 x 1 1/2", 1 3/4".

Screwing: 1 1/2" Gas, 1 3/4" Gas.

Weight per ft.: .81, 1.05.

Gauge: 12 x 1 1/2", 1 3/4", 1 1/2".

Screwing: 1" Gas, 1 1/4" Gas, 1 1/2" Gas.

Weight per ft.: 1.49, 1.92, 2.21.

Gauge: 11 x 2 5/16".

Screwing: 2" Gas.

Weight per ft.: 3.12.

USEFUL INFORMATION

Approx. Weight of W.I. Pipes and Fittings
(See Page 23)

Size	Tubes				Weight per 1000 ft.			
	wt.	qrs.	lbs.	tons	wt.	qrs.	lbs.	tons
1/2"	—	—	24	—	1	0	16	—
3/4"	—	1	14	—	3	3	0	—
1"	—	2	0	—	5	0	0	—
1 1/4"	—	3	0	—	7	2	0	—
1 1/2"	1	0	0	—	10	0	0	—
2"	1	1	27	—	14	3	18	—
2 1/2"	1	3	19	—	19	0	22	—
3"	2	1	16	1	3	3	20	—
3 1/2"	3	1	26	1	14	3	8	—
4"	4	3	18	2	9	0	12	—
4 1/2"	5	2	17	2	16	2	2	—
5"	7	1	21	3	14	1	14	—

Size	10 Elbows		Fittings 10 Tees		10 Bends	
	lbs.	qrs.	lbs.	qrs.	lbs.	qrs.
1/2"	1	2	1	4	1	2
3/4"	1	8	1	13	2	1
1"	1	14	2	5	3	6
1 1/4"	3	0	3	7	5	14
1 1/2"	4	7	5	9	11	6
2"	7	0	8	6	15	12
2 1/2"	11	0	13	6	23	4
3"	16	0	18	12	33	4
3 1/2"	23	8	29	14	52	10
4"	46	0	51	0	94	0
4 1/2"	62	0	82	0	124	0
5"	110	0	145	0	230	0

USEFUL INFORMATION

Weight per Super Foot of Lead

Inch	Lbs.
1/16	3.7
1/8	7.4
3/16	11.1
1/4	14.8
5/16	18.5
3/8	22.2
7/16	25.9
1/2	29.5
9/16	33.2
5/8	36.9
11/16	40.6
3/4	44.7
13/16	48.3
7/8	51.0
15/16	55.1
1	59.4

WEIGHTS OF COPPER AND BRASS RODS AND BARS

In Lbs. per Lineal Foot

Size	Copper Rod Round	Copper Bar Square	Brass Rod Round	Brass Bar Square	Size	Copper Rod Round	Copper Bar Square	Brass Rod Round	Brass Bar Square
1/8	0.047	0.06	0.044	0.05	1 1/2	3.85	4.91	3.68	4.57
3/16	0.106	0.13	0.10	0.12	1 3/4	4.75	6.06	4.55	5.64
1/4	0.19	0.24	0.17	0.22	1 7/8	5.75	7.34	5.50	6.82
5/16	0.29	0.38	0.27	0.35	2	6.84	8.73	6.55	8.12
3/8	0.43	0.55	0.41	0.51	2 1/8	8.03	10.25	7.68	9.53
7/16	0.58	0.74	0.54	0.69	2 1/4	9.32	11.89	8.91	11.1
1/2	0.76	0.97	0.72	0.90	2 3/8	10.69	13.65	10.23	12.7
5/8	0.96	1.23	0.92	1.14	2 1/2	12.17	15.53	11.64	14.4
3/4	1.19	1.52	1.13	1.41	2 7/8	15.40	19.65	14.74	18.12
7/8	1.71	2.18	1.63	2.03	3	19.01	24.26	18.19	22.56
1 1/8	2.33	2.97	2.23	2.76	3 1/8	23.01	29.36	22.01	27.53
1 1/4	3.04	3.88	2.91	3.61	3 1/4	27.38	34.94	26.20	32.49

WEIGHTS PER SUPERFICIAL FOOT OF COPPER AND BRASS

Rolled to the "Imperial" Standard Wire Gauge

W.G.	Copper lbs.	Brass lbs.	W.G.	Copper lbs.	Brass lbs.	W.G.	Copper lbs.	Brass lbs.	W.G.	Copper lbs.	Brass lbs.
1	13.950	13.350	10	5.952	5.696	19	1.860	1.780	28	.688	.658
2	12.834	12.282	11	5.394	5.162	20	1.674	1.602	29	.632	.605
3	11.718	11.214	12	4.836	4.628	21	1.488	1.424	30	.576	.551
4	10.798	10.324	13	4.278	4.094	22	1.302	1.246	31	.520	.506
5	9.858	9.434	14	3.720	3.570	23	1.116	1.078	32	.464	.450
6	8.928	8.544	15	3.248	3.104	24	1.023	.979	33	.408	.394
7	8.184	7.832	16	2.976	2.848	25	.930	.890	34	.352	.338
8	7.440	7.120	17	2.604	2.482	26	.837	.801	35	.296	.282
9	6.696	6.408	18	2.232	2.126	27	.762	.729	36	.240	.226

DANKS' FOR ALL ELECTRICAL FITTINGS

Containing 70 per cent. of Copper.

[illegible]

Calculated on Basis of Copper at 558 lbs. per cubic foot

"IMPERIAL" WIRE GAUGE THICKNESS																
	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	
	.192	.176	.160	.144	.128	.116	.104	.092	.080	.072	.064	.056	.048	.040	.036	
Outside																
Dia lbs	lbs	lbs	lbs	lbs	lbs	lbs	lbs	lbs	lbs	lbs	lbs	lbs	lbs	lbs	lbs	
1	1.89	1.76	1.39	1.28	0.97	0.89	0.65	0.60	0.53	0.48	0.44	0.39	0.33	0.28	0.26	
2	2.18	2.03	1.64	1.50	1.16	1.07	0.82	0.74	0.65	0.59	0.53	0.47	0.41	0.34	0.31	
3	2.47	2.30	1.88	1.72	1.35	1.25	0.97	0.87	0.77	0.70	0.63	0.56	0.48	0.40	0.37	
4	2.77	2.57	2.36	2.12	1.55	1.42	1.29	1.15	1.01	0.92	0.83	0.73	0.64	0.55	0.47	
5	3.06	2.84	2.61	2.38	1.73	1.60	1.45	1.29	1.14	1.03	0.92	0.81	0.70	0.59	0.47	
6	3.35	3.10	2.85	2.59	1.94	1.78	1.61	1.43	1.26	1.14	1.02	0.90	0.77	0.65	0.53	
7	3.64	3.37	3.09	2.81	2.14	1.96	1.77	1.57	1.38	1.25	1.12	0.98	0.85	0.71	0.64	
8	3.93	3.64	3.34	3.03	2.32	2.13	1.92	1.71	1.50	1.36	1.22	1.07	0.92	0.77	0.64	
9	4.22	3.91	3.58	3.25	2.52	2.30	2.08	1.85	1.62	1.47	1.31	1.15	0.99	0.83	0.71	
10	4.52	4.17	3.83	3.47	2.71	2.48	2.24	1.99	1.75	1.58	1.41	1.24	1.07	0.89	0.71	
11	4.81	4.44	4.07	3.69	2.91	2.66	2.40	2.13	1.87	1.69	1.51	1.32	1.14	0.95	0.71	
12	5.10	4.71	4.31	3.91	3.11	2.84	2.56	2.27	1.99	1.80	1.60	1.41	1.21	1.01	0.71	
13	5.39	4.98	4.56	4.13	3.31	3.01	2.72	2.41	2.11	1.91	1.70	1.49	1.28	1.01	0.71	
14	5.69	5.25	4.80	4.35	3.51	3.19	2.87	2.55	2.23	2.02	1.80	1.58	1.36	1.01	0.71	
15	5.98	5.51	5.04	4.57	3.71	3.38	3.03	2.69	2.36	2.13	1.89	1.66	1.43	1.01	0.71	
16	6.27	5.78	5.29	4.79	3.91	3.57	3.19	2.83	2.48	2.23	1.99	1.75	1.51	1.01	0.71	
17	6.56	6.05	5.53	5.00	4.11	3.76	3.35	2.97	2.60	2.35	2.09	1.83	1.57	1.01	0.71	
18	6.85	6.32	5.77	5.22	4.31	3.95	3.51	3.11	2.72	2.45	2.18	1.92	1.65	1.01	0.71	
19	7.15	6.59	6.02	5.44	4.51	4.14	3.67	3.25	2.84	2.56	2.28	2.00	1.71	1.01	0.71	
20	7.44	6.85	6.26	5.66	4.71	4.32	3.82	3.39	2.96	2.67	2.38	2.08	1.79	1.01	0.71	
21	7.73	7.12	6.50	5.88	4.91	4.50	4.00	3.56	3.11	2.81	2.51	2.21	1.91	1.01	0.71	
22	8.02	7.39	6.75	6.10	5.11	4.68	4.16	3.71	3.25	2.95	2.65	2.35	2.05	1.01	0.71	
23	8.32	7.66	6.99	6.32	5.31	4.87	4.34	3.88	3.41	3.11	2.81	2.51	2.21	1.01	0.71	
24	8.61	7.92	7.23	6.54	5.51	5.07	4.53	4.06	3.58	3.28	2.97	2.67	2.37	1.01	0.71	
25	8.90	8.19	7.48	6.76	5.71	5.26	4.71	4.24	3.76	3.46	3.15	2.85	2.55	1.01	0.71	
26	9.19	8.46	7.72	6.98	5.91	5.45	4.89	4.41	3.93	3.63	3.32	3.02	2.72	1.01	0.71	
27	9.48	8.73	7.97	7.19	6.11	5.64	5.07	4.59	4.11	3.81	3.50	3.20	2.90	1.01	0.71	
28	9.78	8.99	8.21	7.41	6.31	5.83	5.25	4.77	4.29	3.99	3.68	3.38	3.08	1.01	0.71	
29	10.07	9.25	8.45	7.63	6.51	6.01	5.43	4.95	4.47	4.17	3.86	3.56	3.26	1.01	0.71	
30	10.36	9.53	8.69	7.85	6.71	6.21	5.63	5.15	4.67	4.37	4.06	3.76	3.46	1.01	0.71	
31	10.65	9.80	8.94	8.07	6.91	6.41	5.83	5.35	4.87	4.57	4.26	3.96	3.66	1.01	0.71	
32	10.94	10.07	9.18	8.29	7.21	6.71	6.13	5.65	5.17	4.87	4.56	4.26	3.96	1.01	0.71	
33	11.24	10.33	9.43	8.51	7.51	6.99	6.41	5.93	5.45	5.15	4.84	4.54	4.24	1.01	0.71	
34	11.53	10.60	9.67	8.73	7.73	7.21	6.63	6.15	5.67	5.37	5.06	4.76	4.46	1.01	0.71	
35	11.82	10.87	9.91	8.95	7.93	7.41	6.83	6.35	5.87	5.57	5.26	4.96	4.66	1.01	0.71	
36	12.11	11.14	10.16	9.17	8.17	7.65	7.07	6.59	6.11	5.81	5.50	5.20	4.90	1.01	0.71	
37	12.40	11.41	10.40	9.39	8.37	7.85	7.27	6.79	6.31	6.01	5.70	5.40	5.10	1.01	0.71	
38	12.70	11.67	10.64	9.61	8.56	8.03	7.45	6.97	6.49	6.19	5.88	5.58	5.28	1.01	0.71	
39	12.99	11.94	10.89	9.83	8.76	8.23	7.65	7.17	6.69	6.39	6.08	5.78	5.48	1.01	0.71	
40	13.28	12.21	11.13	10.04	8.95	8.41	7.83	7.35	6.87	6.57	6.26	5.96	5.66	1.01	0.71	
41	13.57	12.48	11.38	10.26	9.15	8.61	8.03	7.55	7.07	6.77	6.46	6.16	5.86	1.01	0.71	
42	13.86	12.77	11.67	10.55	9.43	8.89	8.31	7.83	7.35	7.05	6.74	6.44	6.14	1.01	0.71	
43	14.15	13.06	11.94	10.83	9.71	9.17	8.59	8.11	7.63	7.33	7.02	6.72	6.42	1.01	0.71	
44	14.44	13.35	12.23	11.12	10.00	9.45	8.87	8.39	7.91	7.61	7.30	7.00	6.70	1.01	0.71	
45	14.73	13.64	12.52	11.41	10.29	9.74	9.15	8.67	8.19	7.89	7.58	7.28	6.98	1.01	0.71	
46	15.02	13.93	12.81	11.70	10.58	10.03	9.44	8.96	8.48	8.18	7.87	7.57	7.27	1.01	0.71	
47	15.31	14.22	13.10	12.00	10.87	10.32	9.73	9.25	8.77	8.47	8.16	7.86	7.56	1.01	0.71	
48	15.60	14.51	13.39	12.29	11.16	10.61	10.02	9.54	9.06	8.76	8.45	8.15	7.85	1.01	0.71	
49	15.89	14.80	13.68	12.58	11.45	10.90	10.31	9.83	9.35	9.05	8.74	8.44	8.14	1.01	0.71	
50	16.18	15.09	13.97	12.87	11.74	11.19	10.60	10.12	9.64	9.34	9.03	8.73	8.43	1.01	0.71	
51	16.47	15.38	14.26	13.16	12.03	11.48	10.89	10.41	9.93	9.63	9.32	9.02	8.72	1.01	0.71	
52	16.76	15.67	14.55	13.45	12.32	11.77	11.18	10.70	10.22	9.92	9.61	9.31	9.01	1.01	0.71	
53	17.05	15.96	14.84	13.74	12.61	12.06	11.47	11.00	10.52	10.22	9.91	9.61	9.31	1.01	0.71	
54	17.34	16.25	15.13	14.03	12.90	12.35	11.76	11.29	10.81	10.51	10.20	9.90	9.60	1.01	0.71	
55	17.63	16.54	15.42	14.32	13.19	12.64	12.05	11.58	11.10	10.80	10.49	10.19	9.89	1.01	0.71	
56	17.92	16.83	15.71	14.61	13.48	12.93	12.34	11.87	11.39	11.09	10.78	10.48	10.18	1.01	0.71	
57	18.21	17.12	16.00	14.90	13.77	13.22	12.63	12.16	11.68	11.38	11.07	10.77	10.47	1.01	0.71	
58	18.50	17.41	16.29	15.19	14.06	13.51	12.92	12.45	11.97	11.67	11.36	11.06	10.76	1.01	0.71	
59	18.79	17.70	16.58	15.48	14.35	13.80	13.21	12.74	12.26	11.95	11.64	11.34	11.04	1.01	0.71	
60	19.08	17.99	16.87	15.77	14.64	14.09	13.50	13.03	12.55	12.24	11.93	11.63	11.33	1.01	0.71	
61	19.37	18.28	17.16	16.06	14.93	14.38	13.79	13.32	12.84	12.53	12.22	11.92	11.62	1.01	0.71	
62	19.66	18.57	17.45	16.35	15.22	14.67	14.08	13.61	13.13	12.82	12.51	12.21	11.91	1.01	0.71	
63	19.95	18.86	17.74	16.64	15.51	14.96	14.37	13.90	13.42	13.11	12.80	12.50	12.20	1.01	0.71	
64	20.24	19.15	18.03	16.93	15.80	15.25	14.66	14.19	13.71	13.40	13.09	12.79	12.49	1.01	0.71	
65	20.53	19.44	18.32	17.22	16.09	15.54	14.95	14.48	14.00	13.69	13.38	13.08	12.78	1.01	0.71	
66	20.82	19.73	18.61	17.51	16.38	15.83	15.24	14.77	14.29	13.98	13.67	13.37	13.07	1.01	0.71	
67	21.11	20.02	18.90	17.80	16.67	16.12	15.53	15.06	14.58	14.27	13.96	13.66	13.36	1.01	0.71	
68	21.40	20.31	19.19	18.09	16.96	16.41	15.82	15.35	14.87	14.56	14.25	13.95	13.65	1.01	0.71	
69	21.69	20.60	19.48	18.38	17.25	16.70	16.11	15.64	15.16	14.85	14.54	14.24	13.94	1.01	0.71	
70	21.98	20.89	19.77	18.67	17.54	16.99	16.40	15.93	15.45	15.14	14.83	14.53	14.23	1.01	0.71	
71	22.27	21.18	20.06	18.96	17.83	17.28	16.69	16.22	15.74	15.43	15.12	14.82	14.52	1.01	0.71	
72	22.56	21.47	20.35	19.25	18.12	17.57	16.98	16.51	16.03	15.72	15.41	15.11	14.81	1.01	0.71	
73	22.85	21.76	20.64	19.54	18.41	17.86	17.27	16.80	16.32	16.01	15.70	15.40	15.10	1.01	0.71	
74	23.14	22.05	20.93	19.83	18.70	18.15	17.56	17.09	16.61	16.30	16.00	15.70	15.40	1.01	0.71	
75	23.43	22.34	21.22	20.12	19.00	18.44	17.85	17.38	16.90	16.59	16.29	15.99	15.69	1.01	0.71	
76	23.72	22.63	21.51	20.41	19.29	18.73	18.14	17.67	17.19	16.88	16.58	16.28	15.98	1.01	0.71	
77	24.01	22.92	21.80	20.70	19.58	19.02	18.43	17.96	17.48	17.17	16.87	16.57	16.27	1.01	0.71	
78	24.30	23.21	22.09	21.00	19.87	19.31	18.72	18.25	17.77	17.46	17.16	16.86	16.56	1.01	0.71	
79	24.59	23.50	22.38	21.29	20.16	19.60	19.01	18.54	18.06	17.75	17.45	17.15	16.85			

To calculate the weight of Copper Tube Internal Diameter, add the figures given in the bottom of column to the weight given. For example, 2" 14 gauge outside diameter is $1.87 + 0.15 = 2.02$ weight of 2" 14 gauge internal diameter.

USEFUL INFORMATION

SIZES OF PIPES FOR WATER

The table herewith gives the approximate diameters of pipes suitable for passing different quantities of water. When the main does not exceed 200 yards in length, the pipe diameter may be smaller than those indicated below. For mains over 200 yards in length it is desirable that pipe diameters are as per table below.

Galls. per min	Dia. in ins	Galls per min	Dia. in ins
$\frac{1}{2}$	$\frac{1}{2}$	60	4
$\frac{3}{4}$	$\frac{3}{4}$	100	5
$1\frac{1}{2}$	1	160	6
3	$1\frac{1}{2}$	220	7
5	$1\frac{1}{2}$	300	8
10	2	400	9
15	$2\frac{1}{2}$	500	10
20	3	800	12
40	$3\frac{1}{2}$	1000	14

Hose Connections, Sprinklers, Etc.



A201. Nuts, Rings and Tails

Sizes: FOR HOSE.
 $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{4}$ ", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ "
 Nuts:
 $\frac{1}{2}$ ", 1", 1 $\frac{1}{4}$ ", 1 $\frac{1}{2}$ ", 2", — F.B.
 (Screw, Gas Thread.)
 Interchangeable with Hose Unions.
 Sizes $\frac{1}{2}$ ", $\frac{3}{4}$ " and 1" are also made with English Threads if these are required.

Nuts and Tails
 Sizes: FOR HOSE.
 $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{4}$ ", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ "
 Nuts:
 $\frac{1}{2}$ ", 1", 1 $\frac{1}{4}$ ", 1 $\frac{1}{2}$ ", 2", — F.B.
 (Screw, Gas Thread.)
 Interchangeable with Hose Unions.
 Sizes $\frac{1}{2}$ ", $\frac{3}{4}$ " and 1" are also made with English Threads if these are required.

Hose Unions

A203.
 (Screwed Gas Thread.)
 Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{4}$ ", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 4", 5", 6"
 Nuts: $\frac{1}{2}$ ", 1", 1 $\frac{1}{4}$ ", 1 $\frac{1}{2}$ ", 2", — F.B.



Unions $\frac{1}{2}$ " to 1 $\frac{1}{2}$ " are interchangeable with Hose Cocks and Nuts, Rings and Tails; all being screwed Standard Gas Sizes.

Sizes $\frac{1}{2}$ ", $\frac{3}{4}$ " and 1" are also made with English Threads, if these are required.

Hose Unions, and also Nuts and Tails, are stocked with Reducing Tails, for adapting smaller Hose to a larger size Tap.

Nuts and Tails

With Tail Screwed Gas Thread.

Size ... $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1"
 Nuts, Scr. Gas ... $\frac{1}{2}$ ", 1", 1 $\frac{1}{4}$ "
 Tails, Scr. Gas ... $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1"
 In $\frac{3}{4}$ " size Tails screwed $\frac{1}{2}$ " and $\frac{3}{4}$ ".

Hose Pieces




A205.
 To suit Controlling Nozzles or other Sprinklers.
 Screwed $\frac{1}{2}$ " Gas for $\frac{1}{2}$ " Hose.
 " " " " " "
 " " " " " "
 " " " " " "

Brass Connections

A206.
 FOR HOSE AND IRON PIPE.

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{4}$ ", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3".



Matching Pieces

A208.
 The Hose Sizes given are to suit Standard Hose Nuts:

Hose Gas	Hose Gas
$\frac{1}{2}$ " x $\frac{1}{2}$ "	1" x 1"
$\frac{3}{4}$ " x $\frac{3}{4}$ "	1 $\frac{1}{4}$ " x 1 $\frac{1}{4}$ "
$\frac{1}{2}$ " x 1"	1 $\frac{1}{2}$ " x 1 $\frac{1}{2}$ "
1" x $\frac{1}{2}$ "	2" x 2"

Hose Rings FOR BIB COCKS.



A209
 Sizes. Scr. Gas Sizes. Scr. Gas
 $\frac{1}{2}$ " 1" 1 $\frac{1}{4}$ " 2"
 $\frac{3}{4}$ " 1" 1 $\frac{1}{4}$ " 2"
 1" 1 $\frac{1}{4}$ " 1 $\frac{1}{2}$ " F.B.
 1 $\frac{1}{2}$ " 1 $\frac{1}{2}$ " 2" F.B.

"Clinch" Nut and Tail for Hose

A210.

Sizes:
 Gas Hose
 $\frac{1}{2}$ " x $\frac{1}{2}$ "
 $\frac{3}{4}$ " x $\frac{3}{4}$ "
 1" x 1"



"Clinch" Hose Union

A212.

Sizes:
 Gas Hose
 $\frac{1}{2}$ " x $\frac{1}{2}$ "
 $\frac{3}{4}$ " x $\frac{3}{4}$ "



"Clinch" Hose Connection


A213.

Male Thread to Hose
 Sizes:
 Gas Hose
 $\frac{1}{2}$ " x $\frac{1}{2}$ "
 $\frac{3}{4}$ " x $\frac{3}{4}$ "
 $\frac{1}{2}$ " x 1"

The "Clinch" Hose Mender

A214.

Both Ends for Hose
 Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".



Tap Unions, with Rubber Cup

A216.

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ " x $\frac{1}{2}$ ", 1", 1" x $\frac{1}{2}$ ", 1" x $\frac{3}{4}$ ".



The "Tap-Union" Clip

A217.

A simple attachment for effectively holding Tap Union firmly on Tap.

Made of Hard Spring Wire, in two sizes, for $\frac{1}{2}$ " and $\frac{3}{4}$ " Taps.

Universal Director

A218.

Made in Brass.
 Ideal for use in limited areas.
 Swivels in any direction.
 Simple, strong and well-made. Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".
 Supplied without hose cock unless ordered otherwise.

"Evron" Tap Fitting

A219.

Holds hose to tap. Easy to put on and positive in action. With rubber washer.

Sizes:
 Tap Hose
 $\frac{1}{2}$ " x $\frac{1}{2}$ "
 $\frac{3}{4}$ " x $\frac{3}{4}$ "
 $\frac{1}{2}$ " x $\frac{1}{2}$ "
 $\frac{3}{4}$ " x $\frac{3}{4}$ "



Brass Hose Directors (Light)

A300.

With Fixed Jet.
 Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".


Jets Screwed
 Gas, $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".



Brass Hose Directors (Heavy)

A301.

With Loose Jets to 1", and Fixed Jets, 1 $\frac{1}{2}$ " to 2".
 Jets Screwed
 Gas Thread:
 $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", 1 $\frac{1}{4}$ ", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 4", 5", 6", 8", 10", 12", 14", 16", 18", 20", 22", 24", 26", 28", 30", 32", 34", 36", 38", 40", 42", 44", 46", 48", 50", 52", 54", 56", 58", 60", 62", 64", 66", 68", 70", 72", 74", 76", 78", 80", 82", 84", 86", 88", 90", 92", 94", 96", 98", 100".



Controlling Nozzles (in Brass)

A302.

A combination of Solid Jet, Rose Spray, Fine Mist, or Stop Cock, at the will of the user.
 Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".
 $\frac{1}{2}$ " in American Thread.



Butterfly Sprinkler

A303.

Screwed Gas Thread.
 Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ".

Butterfly Sprinklers

A304.

(Improved Pattern)

Screwed Gas Thread
 Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".
 Specially designed to prevent the Fly jamming.



Perfection Sprinklers

A305.

These Sprinklers have no working parts, are practically everlasting, and very effective.



Screwed Gas Thread.
 Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".

Globe Sprinkler (Nickel-plated)

A306.

This Sprinkler throws a splendid Spray, and also has the special feature of evenly distributing the water from the Sprinkler to the extreme edge of circle.

Simple, efficient, and no working parts to wear out.
 Screwed $\frac{1}{2}$ " Gas Thread.



"Daspyl" Spray Nozzle

A307.

A Mist Maker for Ferneries, Plant Houses, etc.
 Also used extensively on Spray Pumps for applying Insecticides, Disinfectants, etc.
 Screwed $\frac{1}{2}$ " Gas Thread.



Dome Sprinkler (Nickel-plated)

A308.

Screwed $\frac{1}{2}$ " Gas Thread.




Oblong Rose Spray

A309.

A Watering Device that gives a gentle sheet of rain-like spray, which waters without damage to even the most delicate seedlings.

Sizes: $\frac{1}{4}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ " Gas Thread.



Brass Roses

A401.

Sizes: For Hose Directors.

$\frac{1}{4}$ " Screwed $\frac{1}{4}$ " Gas

$\frac{1}{2}$ " " $\frac{1}{2}$ " "

1" " 1" "

Also made in Heavy Cast Brass. Sizes: $\frac{3}{4}$ " Screwed $\frac{3}{4}$ " Gas; 5" Screwed, 1" Gas.



Duplex Sprinkler Head

A402.

New Long Life Bearing.

Heads only for Stand

Pipe use.

Screwed $\frac{1}{4}$ " Gas.

Handy Sprinkler

A403.

Screwed $\frac{1}{4}$ " and $\frac{3}{4}$ " Gas. Finished in bright polished and lacquered Brass.



Daspyl Side Spray Sprinkler

A404.

With Controlling Screw.

A Sprinkler that waters without wasting water on the garden paths.

Sizes: $\frac{1}{4}$ ", $\frac{1}{2}$ ".



Side Spray Jet

A405.

This little Jet is a real Mist Maker, and very suitable for spraying Ferneries and other Plant Houses.

Drilled for giving Coarse, Medium or Fine Spray, and are Screwed $\frac{3}{16}$ " Whitworth; $\frac{1}{4}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ " Iron.



Spray Nozzle

A406.

Handy for spraying the under side of leaves or Dwarf Plants. Screwed $\frac{1}{4}$ " Gas.



Spray Nozzle

A407.

The well known Bordeaux type of Graduating Spray Nozzle for general spray work, lime washing, etc. Screwed $\frac{1}{4}$ " Gas Thread.



Three-Jet Spray Nozzle

A408.


Screwed $\frac{1}{4}$ " Gas Thread. Caps are removable for cleaning purposes. This Nozzle can also be supplied with 2 Jets.



Capitol Sprinkler

A409.

Made of Non-corrosive Metal, and no wearing parts. Screwed $\frac{1}{4}$ " Gas.



The Daisy Garden Sprinkler

A410.

Screwed $\frac{1}{4}$ ", $\frac{1}{2}$ " and $\frac{3}{4}$ " Gas.



Supreme Spray

A411.

Used extensively for allaying dust in mines, and also for orchard work. Screwed $\frac{1}{4}$ " Gas Thread. These sprays are made straight as shown; also in an angle of 45°.



The Glider Sprinkler Stand

A412.

To suit Globe, Perfection and other Sprinklers.

STAND ONLY.


The "Glider" is of cast iron and specially made to be pulled about on Lawns, without damaging the grass.



Danks' 2-Wheel Sprinkler Stand

A413.

A simple, portable device, suitable for use with any style of Sprinkler. It will not cut up Lawn, and can be moved about without shutting off the water.



Sprinkler Stands

A414.

Cast Iron "Midget" with Brass Elbow Screwed.

$\frac{1}{4}$ " Gas Male x $\frac{1}{4}$ " Gas Female

$\frac{1}{2}$ " " " x $\frac{1}{2}$ " " "

$\frac{3}{4}$ " " " x $\frac{3}{4}$ " " "

1" " " x 1" " "


To suit Butterfly, New Perfection of other sprinklers.



Sprinkler Stand

A415.

A Pressed Steel Stand that is strong, light and durable, for use with various makes of Sprinklers. Stand Only.



Whirligig Sprinkler

A416.

A cheap, neat and efficient Two-arm Sprinkler. Screwed $\frac{1}{4}$ " and $\frac{3}{4}$ " Gas Thread.



"Cascade" High Pressure 5-Ply Garden Hose



"Cascade" 5-ply High Pressure Garden Hose is specially manufactured in large quantities for us. It is composed of five plies of strong, superior quality woven insertion, interlaid with rubber. The inside lining is of tough, seamless rubber, and the outer rubber covering possesses exceptional wearing qualities. "Cascade" Hose will stand up to the hardest wear to which it can be subjected. It will give years of extra service, whilst its price is the same as many 3-ply hoses of similar quality. In coils of 60 ft. Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".

"Jay Dee" 3-Ply Garden Hose

An Excellent Medium-priced Hose, that will give long and efficient service. In coils of 60 ft. Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".

All Leading Makes of Hose Stocked.

CANVAS HOSE

We stock Good Quality Canvas Hose for Fire Extinction, Street Sluicing, etc., in the following sizes: 1", $1\frac{1}{2}$ ", $1\frac{3}{4}$ ", 2", $2\frac{1}{2}$ ", 3".

Canberra Sprinkler

A417.

Finished in Polished Brass, with Coloured Duco Base.




PRETORIA SPRINKLER

A501.

Chromium Plated

New 4-Arm Design




ORDER BY NUMBER ONLY!

Lykrane Sprinkler

A502.

Revolving or Stationary.



Nozzles adjustable for covering various diameters, for spraying in any direction, and to give coarse, medium to mist-like spray or solid jet. The revolving head is made of bronze.

Sprinkler Stand (Cast Iron)

A503.

With $\frac{1}{4}$ " or $\frac{3}{4}$ " Gas Pipe Connections.

These Stands can be used as shown by screwing the Sprinkler on Pipe, or it can be lengthened to any desired height by attaching Wrought Iron Pipe to same.



DANKS for TOOLS for All Trades

Garden Hose Reels

A504.

HOOP PATTERN.


Size and Capacity:

11 inch holds

60 feet $\frac{3}{4}$ " hose;

13 inch holds

100 feet $\frac{3}{4}$ " hose



Garden Hose Reels

A505.


LEVER PATTERN.

Size and Capacity:

11 inch holds

100 feet $\frac{3}{4}$ " hose.

These Hose Reels are well made of wrought iron, painted or galvanised, and are strong and durable.



ALSO STOCKED: A405a DISAPPEARING JETS. $\frac{1}{2}$ in. THREAD, STRAIGHT OR BORDER TYPES



A506 (at left). "Daspyl" Spike Adaptor for Use with Rose or Side Spray

This Adaptor enables the garden rose or spray to be easily directed at any angle or in any desired position. It facilitates the watering of long stretches of garden without the necessity of holding the hose, and may be moved about while the tap is turned on.



A507 (at right). "Daspyl" Side Spray, with Spike Stand

This Spray forms a most convenient and effective means of watering gardens in sections. It gives a very fine, fan-shaped spray, and the single spike stand permits of turning in any direction or any angle. A particularly valuable feature is that it can be moved from one place to another without turning off the water.



The "Universal" (Regd.) Hose Support

A508.

The "Universal" Hose Support is made with Wrought Iron Stem, which has a step for driving the point into the earth.

The adjustable attachment will hold the Hose Director in any required position when using the ordinary nozzle, rose, or spraying head.

A Screw Holder is provided for conveniently locating the spare rose or other fittings, so that they will not be mislaid.



The Utility Hose Support

A509.

An exceedingly simple contrivance, with a fixed, notch adjustment for holding the Hose Director in any slanting or vertical position. Made with heavy cast iron head and wrought iron stem. Two sizes, to suit $\frac{1}{2}$ " and $\frac{3}{4}$ " Directors.

Do Not Cut
Catalogue
when
Ordering.
Order by
Number
Only.

Border Spray



A511.


The "Danks" Border Spray makes it possible for a border to be well sprayed without the water being wasted on the path. It has great covering capacity, and with it there is more control of the spraying than with the ordinary Sprinkler. The Spray can be directed at different angles, according to requirements, by just turning the pipe round in the supports. The "Danks" Border Spray is 12 ft. long, or any required length, fitted with three Spray Jets, and supplied with two Wrought Iron Supports, as illustrated. Also made with wheels at one end.



The "Daspyl" Sprinkler Trolley

A512.

This unique device is readily adaptable to Sprinklers of various types, and may be used on Bowling, Putting, or other Greens, Croquet and Tennis Lawns, etc. It stands firm, and is easily moved about without causing the slightest damage to the grass. The frame is made of Wrought Iron Tubing, and the rollers of Jarrah, turned smoothly and with rounded edges. The front roller is swivelled. Pipe sizes in this sprinkler are $\frac{1}{2}$ " and $\frac{3}{4}$ ".



Spectacular Sprinkler

A513.

The Spectacular Sprinkler is easily the best yet for the thorough watering of large areas. Its great covering power does away with much of the labor spent on ordinary watering devices. The Spectacular is made in two types—the Stationary (as illustrated) and the Travelling. Both are of special value, and either will cover a larger area, without being moved, than any other make of Sprinkler.

Full particulars will be forwarded on request.

The "DASPYL" Rain Maker

A514.


Made in two sizes: $\frac{1}{2}$ " with 3 ft. arms; $\frac{3}{4}$ " with 7 ft. arms.

For Watering Lucerne Fields, Orchards, Market Gardens, Lawns.

An effective and economical method of Field Irrigation and for lawn watering.

Each complete 1" sprinkler, as shown above, will give a uniform distribution of water over the full area of a circle 42 ft. in diameter. It works at full capacity on a pressure as low as 8 lbs.—which is obtainable from a tank elevated 20 ft.


The Rotary speed of the Sprinkler Arms can be altered to suit requirements, and the Spray may be regulated by the adjustable sleeve. Parts are few, strong, and well made—nothing to get out of order.



"EVENSPRAY"

A510.

For Market Gardens, Lawns, Racecourses, Tennis Courts (Grass and Porous), Golf Courses, Croquet Lawns, etc. In sizes from 2' 6" up to 14' arms. Fine, Medium, Coarse or Adjustable Jets may be supplied.



USEFUL INFORMATION

TO TELL IF BEND OR JUNCTION IS RIGHT OR LEFT HAND

(See pp. 14, 15.)

Lay fitting on floor with I.O. on top and faucet end NEAREST to you. If bend or branch now points to left, fitting is left-handed; if to right, a right-hand fitting.


When ordering such fittings, be sure to state whether you require left or right hand.

the famous

BILLABONG

ENCLOSED GEAR - SELF-OILING

WINDMILL



**Rain Proof
Dust Proof
Leak Proof**

The whole of the working parts are machined to gauges and interchangeability is thus assured.

Owing to the light weight of the Mill Head, less tackle and labour is required when erecting.

MAIN FEATURES:

A Modern Mill designed to give the greatest amount of Power from the Various Wind Pressure —Double Gears, Machine Cut and Ball Bearings on the Main Shaft, with Ball Bearing Race on the

Tower Cap make the New Billabong extremely easy running and very sensitive to changing winds. A spacious Oil Bath and other Self-oiling Devices provide for thorough lubrication throughout, thus but little attention is required. A Cover, made of sheet steel, is fitted so as to ensure a thoroughly Weatherproof Compartment for the Working Parts. The Wind Wheel is our Standard Type, which has always given entire satisfaction. A reliable Brake, with other Special Features, governs the running of the Mill.

**“Built to Withstand the Roughest
Storm - Sensitive to the Slightest Breeze!”**

THE BASIS OF SOUND PUMPING EQUIPMENT


Write to Us, Giving Particulars of Your Pumping Problems — Danks for Quality Products

for a lifetime of Dependable Service . .

COO-EE COO-EE

SELF OILING, ENCASED GEARS WINDMILL

THE COO-EE AUTO-OILED WINDMILL is strongly built, and is very smooth running. It is completely Self-Oiling, and one filling of the Oil Well will last a year. The powerful Coo-ee has strong Double Gears, perfectly balanced and correctly meshed with Double Steel Pinions, and two stout Pitmans carry the strain of the Pump Rod with a perfect lift. The unique Oiling System of the Auto-Oiled Coo-ee provides for thorough lubrication throughout—the Shafts run in oil, and also the Gears, and with every revolution of the Wind Wheel a stream of oil flows into every bearing. Yet there is no waste, as all Surplus Oil flows back into the Gear Case to be used over again. Bearings are of Special High-Grade Bearing Metal, and are practically frictionless. The Coo-ee has been designed to meet the demand for a low-priced outfit and at the same time to give long and satisfactory service.



**TROUBLE PROOF
STORM PROOF
LEAK PROOF**

Manufactured by John Danks, makers of
"BILLABONG" MILLS

BILLABONG ALL STEEL TROUGHING

FOR EVERY TROUGHING NEED

P1.—CATTLE TROUGH

Made up of two or more Standards, as illustrated, 20-Gauge Galvanised Steel Body, and fitted with our Patent Cleaning-out Plug.

Measurements: Height overall, 26"; width, 24"; depth, 12" capacity, about 9 gallons per foot of Troughing.

P2.—SHEEP TROUGH

Identical with Cattle Trough except that Standards are shortened and the capacity is less. Body made from 22-Gauge Galvanised Steel. Fitted with our Patent Cleaning-out Plug.

Measurements: Height overall, 14"; width, 20"; depth, 10"; capacity, about 6 gallons per foot of Troughing.

P3.—STABLE DOOR TROUGH


A specially designed Trough for placing in front of hotels or by the stable door. Made of Heavy Steel Standards with Cross Stays and $\frac{1}{4}$ " Curved Sheet Steel (Painted), and constructed with the same care and thought for effectiveness and permanence which gives superiority to all our Troughings.

Measurements: 8', 10', and 12' long; 20" wide x 10" deep; 8', 10' and 12' long; 24" wide x 12" deep.

P4.—PIG TROUGH

Body of Trough is of 14 W.G. Sheet Steel and sides are protected and strengthened by means of Angle Steel. The ends are of Cast Iron, and afford great strength and a good joint. The troughs are thoroughly coated with paint before leaving our Factory.

Measurements: Note—All Troughing Measurements are approximate, 12" wide, and 4', 6', 8', 9', or 12' in length.



Rigid and strong, these Troughs are thoroughly leak-proof, will not warp or crack, and are quickly and easily cleaned.

FOR HIGHEST QUALITY INSIST ON "BILLABONG AND COO-EE"

USEFUL PUMP INFORMATION

1. TO GIVE SATISFACTION, a pump must be suitable for its duties and properly installed.
2. THE SUCCESSFUL ACTION of a pump depends, firstly, on the suction pipe joints being absolutely air tight.
3. TOTAL SUCTION HEAD should never exceed 20 to 25 feet. This may be computed by adding together the vertical height from lowest summer water level, to centre of pump and the friction in the suction piping.
4. HORIZONTAL SUCTION PIPES when necessary should always fall from the pump; all air will then pass upwards. When this is not convenient, care must be exercised to see that there is no chance of air lodging along the top of the inside of piping. If this may occur it is absolutely essential to fit cocks so that all air may be allowed to escape. When different sizes of horizontal suction piping are used, air cocks are generally necessary. The shorter the suction piping, the greater the efficiency. Never use elbows, and as few bends as possible. When convenient, keep piping underground to avoid frost.

"BILLABONG" LOW DOWN DOUBLE-ACTING FORCE PUMP


With Ratchet Gear

P5.

This Ratchet Gear Pump is easy to operate. There are no complicated parts. The Piston is supplied with Double Cupped Leathers, Polished Steel Piston Rod, Brass Packing Glands, and Rubber-faced Metal Valves. All Waterways are of large capacity. Total Vertical Lift and Force, 50 feet, from water to point of discharge. Suction lift must not exceed 25 feet.

BILLABONG PUMPS

And Pumping Equipment



P5.

Sizes:

Cylinder, 3" x 4" Stroke for 1½" pipe.

Capacity, 480 gals. per hour slip excepted.

Cylinder, 5" x 5" Stroke for 2" pipe.

Capacity, 1680 gals. per hour, slip excepted.

"BILLABONG" LOW DOWN DOUBLE-ACTING FORCE PUMP

P6.

A Durable Pump of large capacity, more heavily constructed than many pumps of its kind now on the market. Has no complicated parts. The Piston has Double Cupped Leathers. Piston Rod is of Polished Steel, Packing Gland is of Brass. Valves, which are all metal and rubber-faced, may be easily and quickly removed by unscrewing the valve covers shown on top of Pump.


All Waterways are of large capacity.

Size: Inside diameter of cylinder, 5 inches.

Stroke, 5 inches.

Pipes: Suction and discharge, 2 inches inside diameter.

Capacity: Per hour at 40 double strokes per minute, slip excepted. Imperial gallons, 1680.



Total Lift and Force, 50 feet from water to point of discharge.


Suction Lift must not exceed 25 feet.

CISTERN LIFT PUMP With Revolving Stand P7.

Total Vertical Suction Lift, 25 feet.

A popular Pump for Cisterns and Shallow Wells. The base is secured to cylinder by lugs and set-screws, which allow the spout to be turned in any direction. Not supplied with Nut and Tail.

No. of Pump	Size Inside dia. of cyl. in inches	Stroke Length in inches	Pipes Inside dia. in inches	Capacity Galls. per hour at 30 Strokes per min. slip excepted
2	2½	5	Suction 1½	159
3	2½	6½	1½	260
4	3	6½	1½	309
6	3½	7½	2	452




USEFUL PUMP INFORMATION

(continued):

5. A FOOTVALVE and strainer are in all cases recommended.
6. DELIVERY PIPES should not be of less diameter than half the bore of the working barrel, and, if of considerable length, larger than this. If delivery pipes are of small diameter, great friction is caused, and much more power than necessary is required to work the pump.
7. STATIC HEAD: This means the height the point of discharge is above the level of the water being pumped.
8. FRICTION HEAD is the term applied to the resistance caused by the friction of the flowing water against the pipe interior. This friction cuts down the effectiveness of the power used, and should be reduced as much as possible. A small pipe offers more friction to a given flow of water than does a larger pipe. Therefore, pipes, of large diameter, and with few bends, are more economical, in the end, as less power is required to pump through them.

SPARE PARTS for all Pumps always available

DANKS' HAND OPERATED PUMPS FOR EFFICIENCY




P9.


POWER ROTARY FORCE PUMPS FOR PUMPING AND CIRCULATING OIL AND OTHER FLUIDS

The gears are machine cut, from high-grade gun metal, and are accurately fitted so as to give a maximum of efficiency. The spindles are mounted in long bearings so as to ensure alignment, thus accurate running is longer maintained.

No. P8.—Single Bearing Type: $\frac{1}{2}$ ", $\frac{3}{4}$ ".
No. P9.—Double Bearing Type: $\frac{1}{2}$ ", $\frac{3}{4}$ ".



P8.



The "Danks" All Brass. Windmill Pump

P10.

An improved windmill pump of our own design and make.

Popular throughout the Commonwealth on account of its durability and efficiency.

Accessibility is a feature. The Bucket or Plunger may be withdrawn by removing the top cover, and an inspection cover is provided for the bottom valve.

Well Finished. Strong. Fitted with Stuffing Box. 2", 2½", 3", 3½", 4", 4½", 5", 6".



P14.

Brass Lined Bore Cylinder

Draw Plunger Type

Made of Galvanised Wrought Iron Pipe; fitted with a liner of Solid Drawn Brass Tube.

Inside diameter of Cylinder	Length of Stroke	Pipe Thread
1½"	The Stroke of these cylinders varies from 20 inches up, according to requirements.	2"
2½"		2½"
2¾"		3"
3½"	When coding or ordering, state stroke required.	3½"
3¾"		4"



P11.

No. of Bolts	Dia. of Barrel	Lth. of Stroke
2	1½"	8"
2	2"	8"
		12"
3	2½"	8"
		12"
3	3"	8"
		12"



P12.

Dia. of Barrel	Lth. of Stroke
2"	8"
	12"
2½"	8"
	12"
3"	8"
	12"
3½"	12"
4"	12"
4½"	12"
5"	12"
6"	12"



P13.

Dia. of Barrel	Lth. of Stroke
2"	12"
2½"	12"
3"	12"



P15.

Dia. of Barrel	Lth. of Stroke
2"	8"
	12"
2½"	8"
	12"
3"	8"
	12"



P16.

Dia. of Barrel	Lth. of Stroke
2"	8"
	12"
2½"	8"
	12"
3"	8"
	12"
3½"	12"
4"	12"
5"	12"
6"	12"



P17.

Dia. of Barrel	Lth. of Stroke
2"	12"
2½"	12"
3"	12"



P18.

Brass Differential Head

Well finished throughout.

Sizes: 1½", 1¾", 2"
Can also be supplied screwed both ends.

Order by
Number.
Do Not Cut
Catalogue.

For WROUGHT IRON PIPES and Fittings for All
Pumping Purposes, See Page 24.

Hand Power Attachment

P19.

This attachment is intended for use on bolted cylinders or bore pumps for operation by hand or windmill power. It is furnished for adjustable strokes of $5\frac{1}{2}$ " x 7" and 9". Conveniently constructed to enable pipe connections to be easily made. A Tee-piece is included for connecting the attachment to pipe.




Semi-Rotary Double-Acting FORCE PUMP

P20.

Description of Pump: Parts and Valves, Brass; Body, Iron.

No. of Pump	Pipes Inside Diameter Suc. Dis.	Capacity Approx. in galls. per hour slip excepted Imper.
0	$\frac{1}{4}$ "	175
1	$\frac{3}{8}$ "	396
2	$\frac{1}{2}$ "	528
3	$\frac{3}{4}$ "	662
4	$\frac{7}{8}$ "	888
5	1"	1132
6	$1\frac{1}{8}$ "	1450
7	$1\frac{1}{4}$ "	1848

Also made in Gun Metal or Brass



The Danks' Oil Pump P21.

For Pumping Oil, Petrol and Other Liquids

Fig. 5151.

Supplied with Suction Pipe and Bend, and with Hose Attachment as illustrated.

Readily attached to Drum. Easy to operate and very efficient.


Made in three sizes: No. 0, $\frac{1}{4}$ "; No. 1, $\frac{3}{8}$ "; No. 2, 1".

These Pumps are popular on account of their utility, and are easy to operate. They are specially suitable for raising water, oils, hot liquids, etc.

Made of Cast Iron, and fitted with Brass Valves; also of Brass throughout, producing a much more durable article, and one that is suitable for use with mineralized waters.

The handle may be placed to work the Pump either vertically or horizontally.

You can
always
depend on
DANKS



BILLABONG HYDRAULIC RAM

P22.

The Billabong Hydraulic Ram is a self-acting Pump, specially suitable for supplying water to Factories, Dairies, Stockyards, Farms, Homesteads, small Towns, etc.

The Valves of this Ram are heavy, and strongly made of Brass.

Construction throughout is of the best, and the materials are of reliable quality.

No. of Ram

Pipes, Inside Diameter

Approx. No. of gallons per minute required to operate Ram

No. of Ram	Drive	Discharge	Approx. No. of gallons per minute required to operate Ram
3	1"	$\frac{3}{8}$ "	$1\frac{1}{2}$ to 4
4	$1\frac{1}{4}$ "	$\frac{3}{8}$ "	3 " 7
5	2"	$\frac{3}{8}$ "	6 " 14
6	$2\frac{1}{2}$ "	1"	12 " 25
7	3"	$1\frac{1}{8}$ "	20 " 40
10	4"	2"	25 " 100

The Capacity of the Hydraulic Ram is entirely dependent upon working conditions.

On receipt of answers to the following questions, we will furnish full particulars of a suitable plant.

Capacity of flow at source of supply in gallons per minute (this is to give an idea of the supply available for Ram). W. Vertical height (or fall) from source of supply, to Ram. X. Distance in which fall is obtained. F. Vertical height from Ram to point of discharge. Gallons required per day (roughly). (Make rough sketch, showing how you intend laying down the pipes).



Table Showing Efficiency of the Hydraulic Ram


Minimum fall of water, in ft., under which ram will effectively elevate water to height given below	2	2	2	3	4	5	6	7	8	10	12
Height, in ft., the water may be elevated	4	6	8	15	24	35	48	63	80	100	120
Length of drive pipe, in ft.	12	12	12	15	20	30	40	50	60	75	95
Proportion of water elevated or discharged by the ram	2/7	1/5	1/7	2/17	1/10	1/12	1/14	2/31	1/17	1/18	1/20

This Table applies only to Billabong Hydraulic Ram, Fig. No. P22.

NOTE: When ordering, refer to Catalogue number. Do not cut Catalogue, as this will destroy its value to you. The illustrations herein are as accurate as possible, but since alterations to goods occasionally occur, we do not bind ourselves to every small detail shown in the drawings.

YOUR PUMPING PROBLEMS CAN BE SOLVED BY DANKS

The "BILLABONG" Australian Centrifugal Pumps



P23.

Sizes: $\frac{3}{4}$, 1, $1\frac{1}{4}$, $1\frac{1}{2}$, 2, $2\frac{1}{2}$, 3, 4, 5, 6, 8.
For Heads up to 60 feet.

GENERAL DESCRIPTION

Shaft of best steel, carried on C.I. Standards, fitted with ball-bearings, reducing Horse Power required. IMPELLER of the enclosed type carried in G.M. Journal.


Stuffing Boxes.—Extra deep stuffing boxes are provided, allowing ample space for packing. The brass gland is strong, well-made and accurately fitted.

Swivelling.—Discharge on all sides can be adjusted to almost any angle without interfering with efficiency.

Priming.—Before starting, prime the pump and suction pipe through the priming plug on top of the pump casing. See that all suction pipe joints are air-tight, and that foot-valve and strainer has ample waterway, and is in good working condition.

Lubrication.—Use Grease. When using Grease, don't pack too tight; use Oil for Gland.

Manufacture.—These Pumps are made only of the best materials, are of superior workmanship, and are well mounted on a substantial base.



P24.


Single Stage Direct-Coupled to Petrol Engine and Mounted on Cast Iron Bedplate, with Tubular Handles for Transport

$1\frac{1}{2}$ " Pump and $1\frac{1}{2}$ - $2\frac{1}{2}$ h.p. Variable Speed Engine.
For Elevations up to 60 feet.

Capacity up to 100 gallons per minute, according to Speed and Elevation

Single Stage High Duty, with
Pulley for Belt Drive


P25.



Sizes: 1, $1\frac{1}{4}$, $1\frac{1}{2}$, 2, $2\frac{1}{2}$, 3. For Heads up to 120 feet.

Single Stage High Duty for Direct
Coupling to Electric Motors


Sizes and Prices
on Application



P26.

With C.I. Bedplate for Electric Motor.

YOU CAN DEPEND ON DANKS' QUALITY



P27. THE "BILLABONG"
Double Acting Piston Pump

An ideal electric pumping outfit. The $2\frac{1}{2}$ " x 4" is a popular household water supply unit, as it can be operated with a $\frac{1}{2}$ h.p. single phase motor, for heads up to 50 feet, and can be fitted with any type of motor, ranging in h.p. from $\frac{1}{4}$ to 1, for heads up to 250 feet.

It can be supplied with the necessary equipment for making it full automatically controlled pneumatic system, for pressure up to 100 lbs. per square inch.
All sizes, viz.: $2\frac{1}{2}$ " x 4", 3" x 5", 4" x 5", 5" x 5", can be supplied, fitted with motors of sufficient horse-power to meet requirements.


"BILLABONG" PUMPS FOR EFFICIENCY AND DEPENDABILITY

THE BILLABONG DOUBLE-ACTING PISTON PUMP

With Fast and Loose Pulley for Petrol Engine or Other Belt Drive.

P28.

Made for elevations up to 250 ft., Head or Equal Pressure.



The "Billabong" Double-Acting Piston Pump is made at our own works. Only expert workmanship and good quality materials enter into its construction.

The "Billabong" combines ample power and large capacity in most compact form. The Base, Cylinder, Bearings, and one Cylinder Head are cast in one piece—ensuring the alignment of Gearing, and giving an unusually rigid construction.

It is specially adapted to meet the demand for a medium-priced power pump to be operated by kerosene or petrol engines, or other belt power. The Piston is made of high-grade carbon steel, and the Piston Rod is brass cased. Gears and Pinions are machine cut from the solid. The Cylinder is brass lined, and the rubber valves are seated on brass. Bucket leathers are cup-shaped. Suction may be taken from either side, and delivery in four different directions.

Size Diam. and Stroke	Inside Dia. of Suction and Delivery	Revolu- tions of Pulley per Min.	Gallons per Hour, not allowing for Slippage	Fast and Loose Pulley	50 100 150 175 250 feet
			Imp.	Dia. Wid h	B H P.
2½" x 4"	1½"	200	339	15" x 23"	½ ¾ 1 1 1 1
3" x 5"	1¾"	200	611	15" x 2½"	¾ 1 1 1 1 1 1
4" x 5"	2"	200	1086	15" x 3"	1 1 1 1 1 1 1 1
5" x 5"	2½"	200	1697	16" x 4"	1 1 1 1 1 1 1 1

Geared 5 to 1. Speed of Crank Shaft, 40 strokes per minute. B.H.P. is that required at Pump Pulley, and expressed in terms of not less than ¾ B.H.P. Efficiency is taken at only 60 per cent.



Pump Jack

P29.

Fitted with Differential Head.


This is a geared power attachment for belt drive, designed for connecting to delivery pipes of Windmill Pumps and Cylinders. No pump standard is required. The gears are placed so as to prevent side thrust on plunger rod.

Gearing 5 to 1. Stroke adjustable to 5 in., 7½ in., 10 in. Fast and Loose Pulleys, 12 in. diameter x 2 in. face. Supplied with wood pitmans and pump rod. Screwed ½ in. Gas Thread at top and ¾ in. Gas Thread at bottom. Clamps take 2 in. pipe.


Deep Well Working Heads

P30, with Single Pulley, 20" x 4".
With Differential Head

	Stroke	Suction Pipe Thread	Discharge Pipe Thread	Strokes per Minute
Single Geared ..	7" & 9"	2"	2"	30 to 40
Takes ¾" Pump Rod.				



P30.



P35.

SPECIFICATION:

This design of Working Head is arranged to give various different strokes to suit Pumps varying in capacity. The Head is of vertical type on large base with round cast iron column.

Gears are machine cut and accurately fitted to operate with the least possible friction. The ratio is 6 to 1. Shafting of Mild Steel, carried in long bearings, cast on iron column, supplied with gunmetal bushes and lubricated with grease cups.

Pitmans are of wrought iron, supplied with grease cups.

Cross Head is cast iron running on Mild Steel guides held in position by sockets cast on column.

All parts are interchangeable.

Can also be supplied with Reduction Gear for direct coupling to electric motor.


P35, with Two Pulleys, 24" x 4"

Fitted with Differential Head.

	Stroke	Suction Pipe Thread	Discharge Pipe Thread	Strokes per Minute
--	--------	---------------------------	-----------------------------	--------------------------

Double Geared—
9", 11", 13" 3" 2" 25 to 40
Takes ¾" Pump Rod.

The items listed, while being representative, do not comprise our entire stocks. Should we not list here the exact types you need, write us—we probably can secure or make it for you.



The Billabong Double-Acting Piston Pump

With Reduction Gear for Electric Motor Drive.

Motor Speed, 1420 Rev.


P36.

Supplied either with or without Base and with or without Motor.

NOTE.—No. P36 is our No. P28 Pump adapted for Electric Motor Drive. And with the exception of a Gear Wheel replacing the Driving Pulleys, the Pumps are identical, and the description given on this page applies to both.

"Billabong" Sheep, Cattle and Pig Troughing Stronger Than Any Other Make

The FORRERS Self Oiling PUMP



P37.

FLOOR SPACE

2½" x 3" Pump: 15" x 34". 4" x 5" Pump: 24" x 54".
3" x 4" Pump: 18" x 42". 5" x 5" Pump: 24" x 56".
6" x 6" Pump: 28" x 66".

The illustration shows the Pump equipped with Fast and Loose Pulleys for engine drive. May be easily changed to "V" Belt drive with motor mounted on Pump or in front.

MOTOR OR ENGINE DRIVE

For General Service.
Fully Enclosed.
Self Oiling.
Back Geared 5 to 1.

100 pounds pressure, or 230 feet elevation.
Continuous performance 24 hours a day
without attention.

SPECIFICATIONS AND CAPACITIES

No.	Diameter	Stroke	Max. speed R.P.M.	Max. gallons per hour	Fast and loose pulleys	Suction and discharge
912 F	2½"	3"	70	450	12 x 2"	1½"
913 F	3"	4"	70	850	14 x 2½"	1½"
914 F	4"	5"	65	1750	16 x 4"	2"
915 F	5"	5"	60	2550	16 x 4"	2½"
916 F	6"	6"	52	3800	24 x 4"	3"

EACH PUMP TESTED UNDER 125 POUNDS PRESSURE

Feet Elevation or Head	25	50	75	100	150	200
H.P. Required, 2½ x 3" Cyl. (70 R.P.M.)	½	1	1½	2	3	4
H.P. Required, 3 x 4" Cyl. (70 R.P.M.)	1	1½	2	3	4	5
H.P. Required, 4 x 5" Cyl. (65 R.P.M.)	1½	2	3	4	5	6
H.P. Required, 5 x 5" Cyl. (60 R.P.M.)	2	3	4	5	6	7
H.P. Required, 6 x 6" Cyl. (52 R.P.M.)	3	4	5	6	7	8

WE ARE SOLE AGENTS FOR FORRERS IN ALL STATES, EXCEPT QUEENSLAND

THE FORRERS HIGH PRESSURE POWER PUMP


Fully Enclosed.
Self Oiling.
Back Geared 5 to 1.
Heavy Duty, for 250 pound pressure.

Specially adapted for Mines, Water Works, Farms, etc. For use in raising water not exceeding 25 feet vertical lift to low water level.

FLOOR SPACE

1½" x 3" Pump: 15" x 34". 3" x 5" Pump: 18" x 54".
2½" x 4" Pump: 18" x 44". 4" x 6" Pump: 24" x 64".
5" x 8" Pump: 40" x 74".

Pump No.	Cylinder brass lined. Diam. & stroke	Usual plunger speed R.P.M.	Capacity. Max. plunger speed R.P.M.	Max. galls. per hour at pump	Max. horse power	Pulleys. Fast and loose	Suction and discharge
931 F	1½ x 3	60	70	215	2	12 x 2	1 x ½
932 F	2½ x 4	60	70	485	4	14 x 2½	1½
933 F	3 x 5	50	55	840	7½	16 x 4	1½
934 F	4 x 6	40	50	1625	14	24 x 4	2
935 F	5 x 8	35	45	3030	18	30 x 6	2½



P38.

In working against pressure the above capacities will be reduced by 5% to 10% on account of slippage.

EACH PUMP TESTED UNDER 300 POUNDS PRESSURE

Feet Elevation or Head	250	300	350	400	450	500
H.P. Required, 2½ x 4" Cyl. (65 R.P.M.)	1½	2	2½	3	3½	4
H.P. Required, 3 x 5" Cyl. (60 R.P.M.)	2	3	4	5	6	7
H.P. Required, 4 x 6" Cyl. (50 R.P.M.)	3	4	5	6	7	8
H.P. Required, 5 x 8" Cyl. (45 R.P.M.)	4	5	6	7	8	9

ANY OF THESE PUMPS CAN BE FITTED WITH "V" ROPE DRIVE

To Lift Water Economically and Efficiently Without Attention to the Plant, Write to Danks

MILK PUMP

P39.

Cylinder.—Gun Metal, 2" diameter x 4" stroke, with Gun Metal Suction and Delivery Valves.

Plunger.—Gun Metal Casing, with Sleeve and Guide.

Crank.—Cast Iron.


Shaft.—Mild Steel running in long bearing.

Pulleys.—Fast and Loose, 15" diameter x 2" face. Machined

Lubrication.—From Grease Cups.


Suit ¾" Suction and Delivery Pipes.

Mounted on strong Cast Iron Standard



The "HANDY" UTILITY PUMP

P40.



For Petrol Drums

For ..

PETROL

KEROSENE

DEISEL OIL

TRACTOR

FUEL

and

OTHER

LIQUIDS

SAFE
RELIABLE
INEXPENSIVE

Adaptable to all Oil Companies. Standard 45, 25, 12 gall. Bulk Drums.

SPECIFICATION: Cast iron Cylinder, Cast-iron Piston and Piston Ring, no Leather Buckets to wear. Adjustable Down Pipe, 6 feet Hose and Nozzle. Capacity, 6 gallons per minute. Easy Pumping. Spare Parts available.



P41.

KEROTIN SPRAY PUMPS

Made with
Graduating
or
Ordinary
Nozzle



P42.

The Kerotin has been a popular spray pump throughout Australia for many years. From time to time improvements have been made, and now we claim it is without a peer for length of life, efficiency and low price. This handy little pump is made of Brass throughout. It is fitted with Ball Valves, and the Air Chamber is our New Type, with air retaining tube. The Kerotin is sent out with 3 feet of strong detachable hose, armoured at pump to prevent kinking, fitted with a 6 inch brass director. The Kerotin discharges a continuous spray, and is an ideal pump for small orchards and the flower garden, for applying lime wash and disinfectants to fowl runs, cattle sheds, etc. The iron and brass footrest makes the pump suitable for use with standard size Kerosene tin or ordinary bucket.

The REGA
Under Arm
Sprayer
P43.



Made entirely of Brass

P44. Veterinary Enema Nozzle

For use with the Kerotin Spray Pump



KNAPSACK SPRAYER

P45.


BRASS ALLOY.

For spraying Arsenate of Lead
Lime Sulphur
Liver of Sulphur Preparations
Bordeaux Mixture
Lime and White Washes
Emulsion Oils
Red and White Oils
Cattle, Sheep and Hog Spraying
Tick and Lice Disinfectants
Insecticides, etc.

Lead Coated

For Acid Content Liquids,
Arsenate Pentoxide, etc.,
in addition to above.

4 Gals. Capacity. 16 lbs. Weight.
THE "Rega" KNAPSACK SPRAYER
(MOLE'S PATENT)
MODEL DE LUXE



PNEUMATIC SPRAYER

P46.

7" x 20" x 3 Galls. Working Capacity, 2 Galls.
Weight, 9 lbs.


Brass throughout, substantially made. All joints soldered inside and out. Double locked and rivetted Seams (brass rivets). Top and bottom domed and double seamed in.

Equipment: 2 feet of ½" x 3 ply Spraying Hose, 6" Brass Director. Auto pop instantaneous cut-off valve Nozzle; The "Rega" Non-Clog Cyclone, with spare discs for fine spray and jet.

GUARANTEED.



NO MORE CARRYING SKIM MILK — INSTAL A DANKS' SKIM MILK PUMP





Bush Fire Fighting Outfit
P47.

A complete plant, including a 100 gallons square Painted Tank, a No. 3 Danks' own make Pump, with Brass Air Chamber, 20 feet best Delivery Hose, and necessary fittings. This Outfit has proved itself very effective for checking Bush Fires. It throws a strong jet of water 30 to 40 feet, and can easily be operated by one man.

Bush Fire Fighting Unit
P48.

This unit consists of a P5 Pump, 3" Bore, complete with Brass Air Chamber, Brass Foot Valve, Brass Nozzle, and all necessary fittings to connect suction and discharge hose to it. Outlet can be placed at any desired angle. It throws a jet of water horizontally to a distance of 40 feet. Takes 1 1/4" suction hose and 1" or 3/4" delivery hose. When ordering, state length of hose required.



The "Daspyl" Boiler Testing Pump
P49.

The "Daspyl" is a very simple and effective pump for testing boilers up to 250 lbs. pressure per sq. inch. The plunger is fitted in a packed gland, with check valves, pressure gauge, and long iron lever, and is mounted on a strong galvanised tank, which makes it the most complete pump of the kind.

It also serves as an auxiliary to a boiler in the shape of a feed pump.

Stock size: 1 1/2". Larger Sizes Made to Order.

DASPYL means QUALITY

The "Rega" Fire Fighting Outfit
P50.

Inexpensive, yet highly efficient — for dealing with bush and grass fires.

Container, Made from Brass Alloy or Galvanised Iron



"Rega" Flame Thrower
P51.

The Cheapest and Quickest Way to Clear Land of Pests and Noxious Weeds.

A GREAT DESTRUCTIVE AGENT


This apparatus projects a fierce, devastating flame, through which travels a fine spray of hot, unburnt oil, consuming stalk, leaf, flower and seed while they are green.

CHEAP TO OPERATE
Shell Fuel Oil is stored at mostly all of the Company's depots. Diesoline or Tractor Distillate can be used, but costs a little more.



Service Cleaning Pump
P52.

Cylinder Pattern.



Gas Syphon Pumps
P53.

For pumping water from Gas Syphon pots.



DANKS Can Supply a Pump for EVERY PUMPING NEED

Driving Point for Abyssinian Well Boring
P54.

The body is made of galvanised wrought iron tube, and drilled. It is then covered with brass gauze, and jacketed with perforated brass. The octagonal point, which is of solid cast iron, is securely riveted to body, and is sufficiently wide in the shoulder to ensure ample clearance for pipe following.

Sizes stocked: 1 1/4", 1 1/2" and 2" diameter.



STOP THAT FIRE! — WRITE TO DANKS FOR FIRE FIGHTING APPLIANCES



Cupped Bucket Washers

Made of high-grade leather
and thoroughly oiled.




P55.—Single Action

P56.—Double Action

For Cylinders with an inside diameter of 1", 1½", 1¾", 1½", 2", 2½", 2¾", 3", 3½", 3¾", 3½", 4", 5", 6".
Larger Sizes Stocked.

Full Range of ALL PUMPING NEEDS Carried—
Pump Rods, Well Rods, Connections, Guides,
Joints, etc.



P57. Tank Connections

Produces a firm and leak-proof connection without
use of solder.

Made of Cast Iron, galvanised; complete with two
Lock Nuts and Long Screw.
¾", 1", 1½", 1¾", 2", 2½", 3", 4".



P58. Tank Washer

Brass. Ready to Solder
and Rivet in place.
¾", 1".

BRASS SOCKET COUPLINGS FOR WELL RODS



P59.—ORDINARY PATTERN

Gas Thread Sizes: ½", ¾", 1", 1½"

Whitworth Thread Sizes: ¾", 7/16", 1", 1½", 2", 2½"



P60.—REDUCING PATTERN

Gas Thread Sizes: ¾" Gas x ½" Gas; 1" Gas x ¾" Gas;
1½" Gas x 1" Gas; 2" Gas x 1½" Gas.

Gas Thread and Whitworth Thread Sizes:

Whitworth Thread Sizes:			Gas Whit.	Gas Whit.	Gas Whit.
¾" x 7/16"	1" x 13/16"	1½" x 1"	¾" x 13/16"	1" x 1"	1½" x 1"
2" x 1½"	2½" x 1½"	3" x 1½"	2" x 1½"	2½" x 1½"	3" x 1½"
3½" x 2"	4" x 2"	5" x 2"	3½" x 2"	4" x 2"	5" x 2"

Clamps for Supporting Pipes in Wells or Bores



P65.

Cast Iron
Light Pattern.
1½", 1¾", 2".




P66.

Cast Iron
Heavy Pattern. Square Opening.
1½" up to 4".

BILLABONG FOOT VALVES and AIR CHAMBERS




P67.



P68.




P69.



P70.



P71.



P72.



P73.



P74.



P75.

P67.—AIR CHAMBER. Cast Iron Dome. Screwed
1½" and 2" Iron Pipe (Male). With or
without T-piece.

P68.—AIR CHAMBER. Cast Iron Top Discharge.
Screwed Top and Bottom. 1½" and 2" pipes.
Drilled for Tap at Side, at extra cost, if
desired.

P69.—All Brass AIR CHAMBER. 1", 1½". Screwed
Iron Pipe. Thread.

P70.—Brass STUFFING BOX and Gland.
1½", 1¾", 2".

P74.—Combined FOOT VALVE and Strainer.
Brass. 1", 1½", 1¾", 2", 2½", 3".

P71.—Brass FOOT VALVE and Strainer, to fit
inside Bore Casing. With Tumbler Valve.
1", 1½", 1¾", 2", 2½", 3", 1½", 1¾" and 2"
sizes can be supplied with Ball Valve.

P72.—Combined FOOT VALVE and Strainer. Cast
Iron, Galvanised. ¾", 1", 1½", 1¾", 2", 2½",
3", 4". Also available in All Brass. Sizes:
1", 1½", 1¾", 2".


P73.—FOOT VALVE and Strainer. As used with
Centrifugal Pumps, etc. Cast Iron, Flanged.
1½", 2", 2½", 3", 4", 5", 6".

P75.—Brass CHECK VALVE. Leather face. 1½",
1¾", 2".

WE CARRY THE LARGEST RANGE OF PUMP FITTINGS IN THE TRADE

BILLABONG STEEL TANK STANDS

CONSTRUCTIONAL DETAILS



BILLABONG GALVANISED STEEL FLUMING

P76.

Better than earth channels which waste water by soakage or fall in and choke. In various styles.

Light, Strong, Movable.

Write for particulars!

GALVANISED WATER TANKS

We manufacture Corrugated Iron Tanks from 100 up to 2000 gallons' capacity, and also supply the material all ready to make Tanks ranging up to 10,000 gallons' capacity.

Full particulars in reference to Gauge of Iron, Capacities and Prices will be sent on application.

The DANKS Bush Shower P77.

An Ideal Unit for a
Hot or Cold Shower
Bath.

The Bush Shower consists of a Strong Semi-Rotary Pump, Check Valve, Galvanised Pipe and Fittings, Shower Head and length of Hose. It is sent out all ready for putting together, and can be erected in 10 minutes


—
APPROXIMATE
WEIGHT,
17 lbs.

—
As Good as an
Extra
Bathroom!



BILLABONG TANK INDICATOR


P78.



Saves Time! Nothing to Go Wrong!
Easily Fitted!


NO WHITE ANTS IN OUR TANK STANDS

PORCELAIN Enamelled Cast-Iron Baths




S1.

Flanged Baths . . .




S2.



S3.

Bath with 3" Roll Edge.

Approximate Sizes overall:
3 R 11: Length, 5', 5' 6", and 6'. Width, 2' 5 1/2".
4 R 11: Length, 5' 9" and 6' 3". Width, 2' 8".



S4.

Galvanised Iron Rolled Edge Bath, on Legs


Size: 5' 8" long x 2' 3" wide Stove Enamelled or Unpainted.

PORCELAIN ENAMELLED CAST-IRON APRON-FRONT BATH


For building into a corner. Also available for building into a recess. These Baths have panel and bath cast in one piece. They are flanged for tiling in as shown in illustration, and can be supplied right- or left-hand. Right-hand is illustrated. Approximate sizes overall: Length, 5' 6"; Width, 2' 5 1/2"; Height, 1' 7".

Diagrams Showing Patterns of Flanged Baths

Nos. 1, 2, 3 and 4 Pattern in 5', 5' 6", and 6', with 1" high Flange. No. 5 Pattern in 5', and 6' 6" length only.



THE WIDTH OF ALL BATHS IS 29 1/2".



Illustrating No. 5 Standard Flange Bath, set in left-hand position, and "Whitehall" Basin. These Baths can be adapted to any position.

Cast-Iron Porcelain Enamel Pedestal Wall and Angle Basins

Supplied with One or Two Tapholes as required.

All Basins are supplied complete with 1½" plug and washer, cap and lining chain and stay, and grating where required

BATHS
AND
BASINS
ARE
SUPPLIED
IN
FIFTEEN
BEAUTIFUL
COLOURS



Size: 22" x 16"
Bowl: 15" x 10½"

S5.


Size: 24" x 18"
Bowl: 17" x 12½"



Size: 25" x 20"
Bowl: 14" x 10½"

S6.

Size: 20" x 18"
Bowl: 13½" x 9"



S7.

Basin overall: 18½" x 22½". Bowl: 11" x 16" x 6" deep, with two Tap Holes at 8" centres.



S8.


Top: 24" x 16". Bowl: 15" x 10".

TAPS ARE NOT INCLUDED.



S9.

Top: 24" x 18". Bowl: 15" x 10".
Height: 30½".



S10.

Size of Basin: 18½" x 22½"
Size of Bowl: 11" x 16"
Height from Floor to Rim: 31"



S11.

Size of Basin: 21½" x 26". Size of Bowl: 12½" x 16".
Height from Floor to Rim: 31½".



S12.


Top: 27½" x 22½". Bowl: 18" x 14".
Height: 31".

WHEN YOU THINK OF TILING, THINK OF DANKS


Earthenware Angle and Wall Basins



S13. Corner Basin, Round Front, Circular Bowl, with Screw Holes
Approximate Overall Measurements: 21" x 21".
Approximate Diameter Bowl: 14".



S14. The "Tweed" Corner Wall Basin
With One or Two Tap Holes
Approximate Overall Measurements: 20" x 18".
Approximate Bowl Measurements: 14½" x 10".




S15. Corner Basin, Round Front, with Screw Holes
With One or Two Tap Holes
Approximate Overall Measurements: 20" x 18".
Approximate Bowl Measurements: 14½" x 10".



S16. Flat Back, Square or Round Front Basin

Approximate Overall Measurements	Approximate Bowl Measurements	Approximate Overall Measurements	Approximate Bowl Measurements
27" x 19"	24" x 12"	22" x 16"	19½" x 9"
25" x 18"	22" x 11"	20" x 16"	17½" x 9"

(With or without screw holes)
Basins without screw holes have slots underneath roll for 12" centre pin brackets.



S17.

Elitex

Patent	Invisible Bracket.
27" x 19"	
25" x 18"	
22" x 16"	
20" x 16"	

WE STOCK A LARGE RANGE OF TILES IN COLOURS AND TYPES TO SUIT MODERN BATHROOM EQUIPMENT


Submit Your Tiling Problems to Us for a Satisfactory Solution

We Have the Knowledge and the Stocks




S18. Flat Back Basin, with Circular Bowl

Approximate Overall Measurements: 16" x 16"
Approximate Bowl Diameter: 12½".



S19. Corner Basin, Mitre Front

Approximate Overall Measurements	Approximate Bowl Measurements
27" x 20"	14" x 10½"
Without screw holes, soaps at corners:	15½" x 16"
With screw holes:	14½" x 10"
25" x 19"	
20" x 18"	



S20. Flat Back Basin, Shaped Front, with Screw Holes

Approximate Overall Measurements	Approximate Bowl Measurements
26" x 15½"	16" x 11"
22" x 12"	14" x 8"



S21. Flat Back, Square Front Basin, with Overflow at Front, with Screw Holes

Approximate Overall Measurements	Approximate Bowl Measurements
22" x 12½"	14" x 10"

As Illustrated, or with Bevelled Edges.

BASINS STOCKED FOR EVERY REQUIREMENT

Earthenware Pedestal Basins



S22. "BELLEVUE" OCTAGONAL BASIN ON PEDESTAL
Approximate Overall Measurements: 24" x 20"; 21½" x 18".
Approximate Bowl Measurements: 17½" x 13"; 16" x 12".



S23. PEDESTAL LAVATORY, WITH BACK SKIRTING
Overall: 25" x 18"; Bowl: 20" x 11". Overall: 22" x 16"; Bowl: 19½" x 10".

A large variety of Coloured Pedestal Basins are carried in stock, all matching perfectly with baths.

Also sizes to suit every bathroom.

Flat top basins are obtainable with centre tap hole to take Neo-Chrome combination basin set.

ALL
TILES
BATHS
and
BASINS
are
Stocked
in
Colours
Blending
Perfectly
Together

Write
for
Further
Particulars



S24. FLAT BACK BASIN, BEVELLED EDGES
Approximate Overall Measurements: 25" x 18"; 22" x 16".
Approximate Bowl Measurements: 21½" x 10½"; 19" x 9½"



S25. PEDESTAL LAVATORY, WITH FLAT TOP
Overall: 24" x 20"; Bowl: 18" x 12½". Overall: 20" x 18"; Bowl: 15" x 11".

OUR SELECTION OF TILES IS UNSURPASSED

Bath and Shower Screens




S26. Glass Screen Door and Panel. With Brass Frame heavily Nickelplated. Sizes: Height, 6 ft.; Total width, 3 ft. Can also be made in any size to order.



Frames for Glass Screens are made in $\frac{3}{4}$ in. round and square solid Brass tube, Nickelplated, and Glazed in wire Arctic Glass and wired Georgian Glass.


S27.

Plain Galvanized Iron Bath Screen. Glossy, smooth finish Enamel, easily cleaned and obtainable in White or Colours. Height, 4 ft.; Weight, 32 lbs Special.—Any model Bath or Shower Screen may be had in extra special Duco. Withstands Acids or Stains




S28. Light Pattern Glass Screen. With Brass Frame heavily Nickelplated. Size: 4 ft. 6 in. x 2 ft. 3 in.


BATHROOM ACCESSORIES - - - - - Well Worth Your Inspection



S29. SAFIX TOILET PAPER HOLDER
Delivers two sheets only at a time.



S35. Porcelain Splash Back with Chrome-plated Toothbrush and Tumbler Holders.
As above, but without Toothbrush and Tumbler Holders.




S30. SAFIX PAPER TOWEL CABINET

We Keep a Full Stock of Various Types of Toilet Paper including Refills for Safix Cabinets

SHOWER CURTAIN RINGS

- S36.—(Right)—For attaching to Shower Pipe.
S37.—(Left)—With Bracket for Wall Fixing



WE HAVE A STOCK OF IMPORTED SHOWER CURTAINS IN SPECIALLY TREATED SILK, AND ALSO IN FLEECE NAP RUBBER IN MANY PLEASING COLOURS.
STOCK SIZES: 72" x 72" AND 72" x 36".

DANKS FOR A COMPREHENSIVE RANGE OF BATHROOM FITTINGS

CHROMIUM PLATED BATHROOM FITTINGS

S38.




1. Round Pillar End Towel Rail.
- 2 and 3. Swing Towel Rails with 1, 2 or 3 arms.
4. Square Pillar End Towel Rail.

- 5 and 6. Screw to Wall Type Soap holders.
7. Tumbler Holder.
8. Tumbler and Toothbrush Holder.
9. Tumbler Holder.

10. Toothbrush Holder.
11. Toothbrush Holder.
12. Tumbler and Toothbrush Holder.
13. Plate Glass Shelf and Brackets.
14. Liquid Soap Dispenser.

15. Swivel Jointed Shower Rose
- 16, 17, 18. Toilet Paper Holders.
19. Towel Hook.
- 20 and 21. Robe Hooks.


RECESSED TYPE BATHROOM FITTINGS



TILED SHELIVING
S39.



TOILET PAPER HOLDER
S40.




TOWEL RAIL
S41.

THESE FITTINGS
ARE MADE TO
SUIT TILE SIZES
AND MAY BE HAD
TO MATCH
TILE COLOURS




WATER SPOUT
FOR BATH
S42.



SOAP HOLDER
S43.



OBLONG SOAP HOLDER
S44.



OBLONG SOAP HOLDER
WITH GRIP
S45.


BATHROOM CABINETS

In Wood and
White Enamelled
Steel

S46.


ALL MIRROR
FRONT
WOODEN
CABINET

Mirror Sizes
16" x 12"
20" x 14"



S47.

Corner Cabinet, fitted with
Bevelled Mirror. Sizes:
Small 11" x 7 1/2" x 15" high.
Large 12 3/4" x 8 3/4" x 18" high.




S48.

Square Cabinet, fitted with
Bevelled Mirror. Sizes:
Small 11" x 5 1/2" x 15" high.
Large 12 3/4" x 7" x 18" high.

WHEN IN TOWN, VISIT OUR SHOWROOMS

A Bath Heater for Every Home



The Little Hero

S49.

A popular fuel type Heater, the inside element of which can be renewed at very small cost. Suitable for either high or low water pressure.


The "Cash"

S50.

(At right)

An efficient and economical Gas Bath Heater of modern design. Nickel plated, copper finish or in Chrome Plate. Complete with bracket.

ALL GAS HEATERS
STOCKED ARE APPROVED
BY NATIONAL GAS
ASSOCIATION OF VICTORIA



"Carlyle"

S51.


A fuel type Heater, rapid in action. In aluminium sprayed Galvanized Iron or Nickel Plated Copper.

"Malley"

S52.

(Right)

Chip Heater. No installation required. Water runs direct into funnel at top. Very rapid, and ideal for home, farm or dairy.



"Cash" Fuel Heater

S53.

(Left)

Fitted with copper and cast aluminium inside water container. In Galvanized Iron, Aluminium, Sprayed or Nickel Plated Copper.

FUEL HEATERS
supplied with Tipping
Grate, operated by
handle in front of
Heater.



All Heaters
finished in
Aluminium
Sprayed
Galvanized Iron
or
Nickel Plated
Copper

MIRRORS

BEVELLED PLATE GLASS

Decorate your home in the modern manner . . . with mirrors. Our large selection includes many new and lovely designs. With clear glass or silver, gold, peach, blue or amber.



S58. (Above)
S59. (At Left)

Mirrors are the modern motif in enhancing a room, hall or staircase. We show two designs only from a very wide and varied range, but can supply you with practically any shape or size. Just tell us what you want.

Reflect Your
Good Taste
with Mirrors.

20th Century Heaters

(Right)

Can be fitted with shower. Galvanized Iron or Copper, aluminium sprayed or nickel plated copper

S54. 5 ft 4 ins.
high

S55. 4 ft 8 ins.


S56. 4 ft. 2 ins.



The "Lux" Heater

S57.


This fuel type Heater is noted for the extra heavy quality materials used. Large ash-pan eliminates need to empty after every bath. In Galvanized Iron, Aluminium sprayed or Nickel Copper.



Danks' Name Ensures Highest Quality

QUALITY IS OUR WATCHWORD

BATH HEATERS Cont.




**"Caulfield"
Gas
Heater
S60.**

Built on the coil principle, which will stand 180 pounds pressure per square inch.

Supplied in
CHROME
FINISH

Capacity
1 3/4 gallons per
minute


Stainless Steel Sinks and Draining Boards



**Cast Iron Sinks
S69.**

Size: 14" wide x 6" deep x 15", 18", 21", 24", 27", 30" long. Size: 12" wide x 6" deep x 15", 18" long. With and without overflow.

We also stock three sizes of stamped steel enamelled Sinks, as follows: 12" x 12", 18" x 12", 21" x 13"



Stainless or Standard, Porcelain Enamel Finishes.


Cast Iron Porcelain Enamel Sinks

S65.

Made with Sink Left or Right Hand, or in Centre (as illustrated). Overall Sizes: Length, Depth, 1' 6"; Sink, 1' 6" x 1' 2". Supplied Complete with Nickel plated Plug, Washer, Cap and Lining, and Fixing Strip. Cast-iron "T" Section Wall Brackets or Oanti-lever Brackets, extra.




COMBINATION SINK AND DRAINER



COMBINATION SINK AND DRAINER

S67.

Made with Sink Left Hand (as illustrated), Right Hand, or with Sink in Centre and Skirting at back only. Left Hand Sink has Left Hand Outlet; Right Hand has Right Hand Outlet; Centre Pattern has Outlet Right Hand. Sizes Overall: Length 4' 13"; Depth, 1' 6"; Sink, 1' 8" x 1'.



COMBINATION SINK AND DRAINER

S68.


Stainless Steel Sinks are now almost universally used and are giving ever-satisfaction. They will last a lifetime and retain their bright finish. Standard sizes and designs as Price List, but any size or design can be made to order.

White Enamel Porcelain C.I Wash Troughs

S70.

These Troughs are made in Single Sections only. Each Trough is complete with Plug, Washer, Cap and Lining, and two Brackets. Can be supplied with Plug at Right or Left end. (Left Hand Plug illustrated.)

Measurements: Length, 4' 3 1/2"; Width, 15 1/2"; Depth, 8". Suitable for Industrial Wash Houses, Schools, etc.



DANKS FOR MODERN KITCHEN EQUIPMENT

SANITARY DRINKING FOUNTAINS



S71.


Drinking Fountain, constructed of Cast Iron bowl, finished in Porcelain Enamel, White, and Pedestal obtainable in either White Porcelain or Black Iron finish, and fitted with Bubbling Faucet, with Self-closing Valve, as shown in illustration, and a Galvanised Waste Pipe to floor.



Sanitary Drinking Fountain
S72.

EDUCATION PATTERN

As used in the State schools; has 3" galvanised pipe standard, with C.I. galvanised flange for bolting to floor or ground, C.I. galvanised bowl, with Nickel-plated, Self-closing Valve and Metal Drinking Head. Can also be supplied with Side Discharge Head at extra cost.



Sanitary Drinking Fountain

S74.

WALL TYPE


Heavy White Porcelain Enamelled Cast Iron, with Oval Bowl fitted with Faucet with concealed Regulator and Slant Stream Head, with Guard and Dome Outlet Grating to Waste. Over-all size, 10½" x 16" projection.



Sanitary Drinking Faucet

S76.

Press Button, Right Angle Drinking Faucet. Nickel-plated Finish. Screwed for ¾" Gas Thread, and can also be supplied with Guard



"COO-EE" PRESSURE FILTERS


S77.

PRESSURE FILTER (Right). "Coo-ee," household size. Connects to tap by means of rubber connection or screw attachment. Made throughout of brass, and heavily nickel-plated. Nothing to rust. Few parts. Easily cleaned. Capacity, 15 gals. per hour approx., with water pressure of 68 lbs. When ordering, please give size of tap

S78.

RAPID PRESSURE FILTER (Left), larger size, for use in Clubs, Hotels, Restaurants, Public Buildings, Schools, etc. Capacity, 40 gals. per hour approx., at 68 lbs. water pressure.

Extra Candles may be obtained for both Household and Rapid Filters.



S75.


Constructed of Cast Iron with Pillar Painted Black and Bowl finished in Porcelain Enamel White. Fitted with our Faucet, with concealed Regulator and Slant Stream Head with Guard. Height, 30"; Size of Bowl, 16½" x 14½".

Pressure Filter Candles




S79.

S80.



FOR HIGHEST QUALITY PRODUCTS INSIST ON "DASPYL"

CEMENT WASH TROUGHS




S81.

Obtainable in M.M.B.W. Pattern with 2" Outlet, or Country Pattern, with 1½" Outlet, as follows:

- | | | | | | | | | | | |
|---|--------|------------|------|---|-----|------|---|-----|------|----------|
| 1 | Compt. | 24" | long | x | 21" | wide | x | 14" | deep | overall. |
| 2 | " | 46" or 48" | " | " | 21" | " | " | 14" | " | " |
| 3 | " | 72" | " | " | 21" | " | " | 14" | " | " |

With or Without Special Cement Pedestals.

WHITE FIRECLAY PEDESTAL SLOP HOPPER



S82.

With Flushing Rim, Back and Sides, and S. & P. Trap.


Fitted with top Cast Brass Grating, and Teak Wood Inset Pad

D.P.L. W.C. CISTERNS

Painted or Glass Lined

FULL BORE FLUSH

S.83



Ball Cock and Overflow are interchangeable. The Ball is suspended, and cannot strike the bottom of the Cistern.

Supplied also with Brackets if desired.


PEDESTAL PANS



S84.

All White Pedestal Pan

P. or S. Trap, Plain or Vented, Right or Left Hand Side. Also Right or Left Hand Side Outlet, Plain or Vented.



S85.

Ivory Pedestal Pan

P. or S. Trap. Plain or Vented. Right or Left Hand Side. Also Right or Left Hand Side Outlet, Not Vented.

W.C. Seats



S86.

Single Flap Double Flap

3" or 9" Backboard

In Oak, Kauri, Maple, White and Coloured Duco, White and Coloured Celluloid. Bi-bolted in Oak and Kauri



S87.

Single Flap Double Flap

3" or 9" Backboard

In Oak, Kauri, Maple, White and Coloured Duco, White and Coloured Celluloid. Bi-bolted in Oak and Kauri



S88.

Single and Double Flap

In Kauri, Maple, Mahogany, Church White, White and Coloured Duco, White and Coloured Celluloid; Black, White and Coloured Bakelite.



S89.

Single and Double Flap

OPEN FRONT

In Kauri, Maple, Mahogany, Church White, White and Coloured Duco, White and Coloured Celluloid; Black, White and Coloured Bakelite

URINAL STALLS


Particulars and Illustrations can be had on application.

DANKS FOR ALL PLUMBERS' REQUIREMENTS

Streamlined Beauty and Silent Efficiency


*for Modern Bathrooms
and Lavatories*

"HUSH"
The SILENT Flusher



S90. "HUSH"—Pattern No. 1


There are only two moving units in the "HUSH" FLUSHER, i.e., the lever and valve. The lever unit is definite in action, and the valve unit, which controls the volume of water passed at each flush, is strongly constructed and cannot get out of order. The valve moves only half an inch at each flush, and will operate an unlimited number of times without variation. The piston is loose fitting, and cannot be held up by small pieces of foreign matter, and the construction allows great volume of water to pass quickly, but water is cut off gradually at end of flush, thus allowing valve to seat quietly.



S91. "HUSH"—No. 2 Pattern

"HUSH" FLUSHER fitted with straight cock, concealed control, suitable for installing on division walls, obviating unsightly joint connections.


"HUSH" FLUSHERS are guaranteed against mechanical defects, due to any possible fault in construction, for a period of five years from date of purchase.



S92. "HUSH"—De Luxe Model

This Model is designed to meet the requirements of modern bathroom planning.

The appearance is all that can be desired, and the working parts are identical with our other types which have made the "HUSH" famous.




S93. PRESS BUTTON TYPE
For Flats, Public Buildings, etc.

OPERATES AGAINST ANY PRESSURE OVER 8ft. For Fuller Details, WRITE FOR LEAFLET

SINCE 1859 DANKS' SEWERAGE FITTINGS HAVE LED THE WAY

McCLARY



ELECTRIC RANGES

E1.

Model No. 1 supplied in the following finishes—C. and E.

Roasting Oven	16" x 20" x 14"
Cooking Top	20" x 23"
Height to Cooking Top	36"
Floor Space	28" x 40"
Surface Elements	1-9" 1,800 W
	1-9" 1,700 W
	2-7½" 1,250 W.
Oven Elements	Upper 1-1,800 W
	Lower 1-5,000 W.
Warming Closet	1,400 W

The Speediron Element is a tried and proved heating unit . . . famous for its uniform and consistent heating abilities . . . absolutely dependable performance . . . economy in operation . . . and, furthermore, is easily removable for minor or major adjustment.

The heavy cast-iron base is entirely eliminated. The four copper terminal blades on element engage easily, smoothly and flexibly. The fourth blade and jaw are permanently earthed to element base and range body respectively, thus ensuring absolute protection. All wiring and connections are clear of any contamination from boil-overs and grease. The element is faster, more rugged in construction, and will give longer and more satisfactory service.

INTRODUCED INTO AUSTRALIA BY JOHN DANKS & SON PTY. LTD. AS THE IDEAL ELECTRIC RANGE FOR AUSTRALIAN CONDITIONS.

Only McClary offers you these features . . .

The Oven is roomy, seamless and porcelain enamel lined. It will take the largest roasting pan. Four pie plates can be accommodated at one time. Joints are electric-welded before being porcelain enamelled, making seamless rounded corners that are easily cleaned. Two inches of special insulation material between the inside and outside walls retains all heat for hours. Racks and rack holders are removable. Elements plug in.

The Oven Springs are smooth acting, strong and invisible . . . give the oven door a silent, easy motion, and when closed hold it firmly against the oven frame. Not affected by heat of the oven elements, thus retaining their effectiveness indefinitely.

The Oven Heat Control, which is standard on higher-priced models, maintains oven heat automatically; can also be supplied on all Cabinet Models. Where Oven Heat Control is not supplied, a reliable Heat Indicator gives required degrees of heat.

All McClary Ranges have a beautiful porcelain enamelled finish, a finish that is smooth, glossy and readily cleaned. Colors are as indicated for the various models

Cooking Top is also porcelain enamelled, resists the action of boil-overs and acids, and is generously proportioned.

For ease in handling, fuses are arranged so that each is directly under the switch it controls.

McClary Electric Ranges are supplied in these finishes:

A Finish.—Black body, white enamelled panel, nickelled door.

B Finish.—Black body, white enamelled panel, grey enamelled top and front.

C Finish.—White enamelled front, sides, panel and door frames—grey top and blued covers.

GC Finish.—Grey enamelled front and door frames, white enamelled panel and sides, grey top and blued covers

D Finish.—Ivory and green full enamelled—green enamelled top with blued covers

E Finish.—Two-tone ivory.

K Finish.—Black enamelled front, ivory doors and panel—black enamelled top and blued covers.

CK Finish.—Black enamelled front, white enamelled sides, black enamelled top, blued covers.

DANKS FOR SUPREME ELECTRIC RANGES

SMART IN STYLE THOROUGHLY DEPENDABLE

What is it you desire most in your new Electric Range—speed, efficiency, cleanliness, economy, beauty or long life? Then the McClary will suit you best, for it has more than one or two of these features—it has them all.

Speed.—With the new “Max-Speed” element (Boiling plate) you have a powerful unit capable of fast cooking

Efficiency.—No detail has been neglected in producing a range that is EFFICIENT. The McClary is also RELIABLE—you can depend on it to give you finest baking and cooking results.

Cleanliness.—The McClary Range is porcelain enamelled throughout, both outside and in—this glossy, marble-like finish requires only the use of a damp cloth to keep it spic and shining.

Economy.—Could anything be more economical than the protected elements on the cooking surface and the insulated oven?

Beauty.—The design and beauty of the McClary Electric Range is distinctive—the pastel shades of Green and Ivory, Two-Tone

Ivory or the stronger colors of Grey and White are in perfect harmony and will enhance the appearance of any kitchen. The lines are smooth and unbroken by bolts, or unsightly hinges.

Long Life.—An outstanding feature of these carefully built stoves is that they are built to give long, reliable service. Our many friends can vouch for this. Thus, when you buy a McClary you are purchasing a product that will stand by you for a lifetime.


E2.

Model No. 2 supplied in the following finishes—C., D., E. and K

Roasting Oven	12 $\frac{1}{2}$ " x 15 $\frac{1}{2}$ " x 18 $\frac{1}{2}$ "
Cooking Top . . .	18 $\frac{1}{2}$ " x 22"
Height to Cooking Top	35"
Floor Space	25" x 39"
Surface Elements	1-9" 1,800 W
	2-7 $\frac{1}{2}$ " 1,250 W
Oven Elements	Upper 1-1,800 W
	Lower 1-1,500 W
Warming Oven	1-400 W.
Approx. Cu. Cap	24 cu. ft

The Modern McCLARY offers you these Outstanding Features

1. Dependable, quick-heating Elements.
2. Illuminated cooking surface and Minute Minder.
3. Seamless all porcelain enamelled top.
4. Stain resisting porcelain enamelled top.
5. Seamless porcelain enamelled oven interior.
6. Oven completely surrounded with insulating material.
7. Balanced door.
8. Efficient broiler with smokeless grid.
9. Utility Drawer with rubber mat.
10. Oven Heat Control . . . New Hydraulic Type.
11. New long life Switches with Bi-Rotary action.
12. Pull-out oven racks . . . new design.




E3.

E4.

Models No. 3 (Top) and No. 4 (Bottom) supplied in the following finishes—GC., C., D. and E.

	Model No. 3.	Model No. 4.
Roasting Oven	14" x 20 $\frac{1}{2}$ " x 14"	16" x 20 $\frac{1}{2}$ " x 14"
Cooking Top	21" x 23"	23 $\frac{1}{2}$ " x 23"
Height to Cooking Top	34"	34"
Floor Space	39" x 28"	44" x 28"
Surface Elements	1-9" 1,800 W.	1-9" 1,800 W.
	2-7 $\frac{1}{2}$ " 1,250 W.	1-9" 1,700 W.
		2-7 $\frac{1}{2}$ " 1,200 W.
Oven Elements	Upper 1,800 W.	Upper 1,800 W.
	Lower 1,200 W.	Lower 1,200 W.
Warming Closet	1-650 W.	1-650 W.

MCCLARY — A BRITISH EMPIRE PRODUCT




E5. (At right). E6.

McClary Model

Models No. 5 and 6 supplied in the following finishes—GC., C., D. and E.


Roasting Oven	16" x 15" x 14"
Cooking Top	20½" x 24½"
Height to Cooking Top	34"
Floor Space	24" x 25½"
Surface Elements	1-9" 1,800 W.
	2-7½" 1,250 W.
Oven Elements	1-1,500 W.
	1 1,200 W.



E7. (On left)

Model No. 7 supplied in the following finishes — C., GC., D. and E.

Roasting Oven:	15" x 12½" x 14"
Cooking Top:	24½" x 15½"
Height to Cooking Top:	36"
Floor Space:	25" x 19"
Surface Elements:	
1-9"	1,700 W.
1-7½"	1,250 W.
Oven Elements:	
Upper	1,300 W.
Lower	1,100 W.



E8.

Model No. 8 supplied in the following finish only—GC.


Roasting Oven	12½" x 12½" x 10"
Cooking Top	14½" x 18½"
Height to Cooking Top	23"
Floor Space	19½" x 17½"
Surface Elements	1-9" 1,800 W.
Oven Elements	Upper 1,000 W.
	Lower 600 W.

McCLARY ELECTRIC RANGES

On left, E9, and (lower) E10.

Models No. 9 (Top) and 10 (Bottom) supplied in the following finishes—GC., C. and D.

	Model No. 8.	Model No. 82
Roasting Oven	15" x 16" x 16"	15" x 16" x 16"
Cooking Top	20½" x 22"	20½" x 22"
Height to Cooking Top	34½"	34½"
Floor Space	42" x 22"	42" x 22"
Surface Elements	1-9" 1,800 W.	1-9" 1,800 W.
	2-7½" 1,250 W.	1-7½" 1,250 W.
Oven Elements	Upper 1,500 W.	Upper 1,500 W.
	Lower 1,200 W.	Lower 1,200 W.




A Pleasure to Operate
A Treasure to Own

E11.

Model No. 11 supplied in GC. and C.

Roasting Oven:	15" x 16" x 16"
Cooking Top:	20½" x 24½"
Height to Cooking Top:	34"
Floor Space:	25" x 22"
Surface Elements:	
1-9"	1,800 W.
2-7½"	1,250 W.
Oven Elements:	
Upper	1,500 W.
Lower	1,200 W.



Send for Illustrated Leaflet giving details
of other designs and types for all homes

DANKS FIRST IN THE FIELD FOR AN EFFICIENT RANGE (MCCLARY)



CLEAN - ECONOMICAL COOKING

MOFFAT ELECTRIC RANGES

E12 (at left). MOFFAT MODEL

A specially fine Moffat model, combining economical efficiency with smart appearance.

DIMENSIONS

	Width	Depth	Height
Bake Oven	14"	18½"	13"
Warming Oven or Utility Drawer	14"	19"	6"
Cooking Top to Floor	—	—	39"
Cooking Top	19"	20½"	—
Extreme Dimensions	39"	24"	37"

Elements on Top—1-1700W. or 1350W. Standard or 2000W. Cookquik.
1-1260W. Standard or 1800W. Red Spot.
1-750W. Standard or 750W. Red Spot.

Elements in Oven—Top, 1500W.; Bottom, 1260W.

With Utility Drawer, or Warming Oven with 500W. Element.

E13 (at right). MOFFAT MODEL

DIMENSIONS

	Width	Depth	Height		Width	Depth	Height
Oven	18"	15"	13"	Floor to Top	—	—	36"
Top	28"	21½"	—	Extreme Dimensions	29"	22"	40"


Elements on Top—1-700W. Standard or 2000W. Cookquik.

1-1350W. Standard or 1800W. Red Spot. 1-750W. Standard or 750W. Red Spot

Elements in Oven—Top 1500W., Bottom 1260W.



Illustrated
Leaflets
on
Moffat
Ranges
Gladly
Sent
on
Request



E14 (at left). MOFFAT MODEL

A Moffat model with an instant appeal to those who must consider space available.

DIMENSIONS

	Width	Depth	Height
Oven	14"	13"	13"
Hob or Cooking Top	22½"	16½"	—
Hob or Cooking Top to Floor	—	—	37"
Hot Cupboard	17½"	13½"	6½"
Extreme Dimensions	22½"	18½"	42½"

Elements on Top—1-7½ x 10½ Grill Boiler, 2000W.
1-6½" Red Spot, 900W

Elements in Oven—Top 1000W., Bottom 1000W.

"Good Cooking depends a lot on your Stove"

DANKS FOR MOFFAT RANGES — MADE IN AUSTRALIA

Gas-Electric Stoves

By METTERS, K.F.B.

For those who prefer a gas-burning hot-plate with an electric oven, these fine Stoves make an instant appeal. Obtainable in Blue, Green, Brown or Grey Mottled Enamels or Plain Green or All Cream.




E16 (above).

METTERS, MODEL

DIMENSIONS				
	Wide	Overall Height	Deep	Height W/out Plate Rack
Overall	51"	48"	24"	41½"
Overall as Table Model	50"	32"	22½"	26"
Inside Oven	14"	13"	18"	—

ELEMENTS—TOP 1500W., BOTTOM 1260W.

Hotplate—3 "Star" boiling burners, simmering burner, griller, pilot light. Enamelled Griller Dish and Crown Plate with gutter



E15 (above).

METTERS, MODEL, ELEVATED

DIMENSIONS				
	Overall Height	Wide	Deep	Height W/out Plate Rack
Overall	48"	55½"	22"	42"
Overall as Table Model	32½"	54"	22"	26½"
Oven	13"	18"	15"	—

ELEMENTS—TOP 1500W., BOTTOM 1260W.

Hotplate—3 "Star" boiling burners, simmering burner, griller, pilot light. Enamelled Griller Dish and Crown Plate with gutter.

SPEEDY - ECONOMICAL - DEPENDABLE
Combines, in one Stove, all the advantages of a gas-burning hot-plate and an electric oven.



E17 (at left).

METTERS, MODEL

DIMENSIONS			
	High	Wide	Deep
Overall	39"	27"	21"
Oven	13"	14"	13"

ELEMENTS—TWO-900W. EACH

Hotplate—3 "Star" boiling burners, simmering burner, griller, pilot light. Enamelled Griller Dish and Crown Plate with gutter


E18 (at right).

METTERS, MODEL

DIMENSIONS			
	High	Wide	Deep
Overall	39"	28"	21"
Oven	13"	18"	15"

ELEMENTS—TOP 1500W., BOTTOM 1260W.


Hotplate—3 "Star" boiling burners, simmering burner, griller, pilot light. Enamelled Griller Dish and Crown Plate with gutter.



DO NOT CUT CATALOGUE

GAS-ELECTRIC STOVES FOR ECONOMY — SEE DANKS

SERVEX Modern ELECTRIC APPLIANCES *reliable modern*



E19.—Chrome Plated Coffee Percolator

E20.—As above, heavily Silver Plated. Attractive colored handles.



E21.—Toaster. In Chrome and Black.

E22.—Chrome, colored feet, handles in Green, Blue, Red or Black.



E23.—Electric Jug. Plain Cream.


E24.—Mottled Finish. Blue, Green, Brown
E25.—Plain Blue or Green.



E26.—Griller. Solid made in Chrome Nickel Plate. Guaranteed 2 years.



E27.—De Luxe Iron. Large Sole Plate. Chrome and Black or Red or Green




E28.—Standard Iron. Dependable. Chrome and Blue.

Reading Lamps

To clamp, stand or hang. For bed-side, desk or table.

E29.

In attractive lacquer colours.



E30.

(At left): In Silver, Bronze or Satin Brass Finish



E31.

Chromium Plated.



Good Lamps deserve
Good Globes.
INSIST on "NOX"

All the above complete with 6 Feet of Flexible Cord and Plug

WELCOME WARMTH AT SMALL COST!



E36.—Chrome Reflector, colored frame. 13 in. x 15 in. x 5 in. Dependable, long life, strongly made.




E37.—Adjustable Chrome Reflector

12 in. x 10 in. x 6 in.
Very handsome in appearance and solidly made.



E38.—Styled for beauty as well as efficiency.

A modern Radiator, 15 in. x 13 in. x 5 in. Chrome Reflector.



E39.—Combining utility with appearance. Full 90 degrees heat distribution. Adjustable Chrome Reflector.

14 in. x 12 in. x 4½ in.

When ordering, quote number only. Do Not Cut Catalogue

DANKS FOR "SERVEX" APPLIANCES AND SATISFACTION



E40.

HECLA SUPERLINE IRON

With flared sole, fatigueless handle. All Chrome finish.



E41.

HEAT CONTROLLED IRON

Prevents heat rot and scorching. Flared sole. All Chrome finish.



E42.

SUPER IRON

With flared sole and trouble free flex connection. All Chrome finish.



E45.

KETTLES

Beautifully modelled and finished in Nickel Plate. Automatic cut-off

E45.—2-pint capacity.

E46.—3-pint capacity.

E47.—4-pint capacity.



E48.

IMMERSION HEATER

Sheathed type. Quicker, more reliable. Nickel Plate finish.



Clean, Cheap, Efficient.

COOKERS

E43 (at left).

FAMILY COOKER

E44 (at right).

ELECTRIC STOVETTE

HECLA


ELECTRIC APPLIANCES



E49.

BOILO-JUGS

Fastest, most economical way to boil water. In many beautiful colors.



E52.


TOASTERS

Electrically made toast is the most delicious!

E52.—In Black and Chrome.

E53.—All Chrome finish.

E54.—All Chrome on Brass.



E55.

3-HEAT GRILLER-COOKER

Grills, fries, boils, toasts. Two operations at once. Trouble free, dependable.



E50.

GRILLER

For quick results. Will grill, fry, boil, toast. Nickel Plated finish



E56.

COFFEE PERCOLATOR

For making coffee of fuller, richer flavor. Holds six large cups. Nickel Plated, Silvered interior.



E51.

PLATE WARMERS

E57.

Electric Cal-O-Font

For plentiful hot water in the kitchen or bathroom at low cost. Capacity, 1½ gallons.

**Auto. Safety Urn****Hot Water Urns.**

E58. 1 gallon capacity.

E59. 2 gallon capacity.

E60. 3 gallon capacity with 3 heat control.

E61. 4 gallon capacity with 3 heat control.



E58.

Leaflets on Request

HECLA ELECTRIC

COOKERS

E66 (at right).

Clean, economical cooking with a minimum of trouble. Dependable and smartly styled.




E67.

As above with short legs.




DANKS FOR "HECLA" PRODUCTS OF QUALITY

HECLA




E68. HECLA "FLUTA-ROD"
Size: 15" W. x 16½" H. x 5½" D. Elements: 10½" (two). Loading: 2,000 Watts. Finish: Wood Grain or Antique Brass.




E69. HECLA "FLUTA-ROD"
Size: 15" W. x 15" H. x 5½" D. Element: 10½". Loading: 1,000 Watts. Finish: Wood Grain or Antique Brass.



E70. HECLA "RAY-ROD"
Fitted with adjustable reflector. Size: 15½" W. x 11½" H. x 9½" D. Element: 10½". Loading: 1,000 Watts. Finish: Baked Enamel and Chrome. Wall mounting holes provided for Bathroom fixing if desired.



E71. HECLA "RAY-ROD PLUS"
Fitted with adjustable reflector. Size: 17" W. x 11½" H. x 9½" D. Element: 13½". Loading: 1,300 Watts. Finish: Baked Enamel and Chrome. Wall mounting holes provided for Bathroom fixing if desired.



E76. HECLA "MELBA-ROD"
Size: 17½" W. x 16½" H. x 7" D. Elements: 10½" (two). Loading: 2,000 Watts. Finish: Oxy-copper and Chrome.
Hospital Types.—"Melba" design, but fitted with porcelain bar elements (sun-bar type), same price

Electric "Coal-aglo" Fires (Regd.)



E73. THE "MANDEVILLE"
Loading: 2,600 Watts. Finish: Antique Brass. Overall Dimensions: 22½" W. x 25½" H. x 10½" D.
May also be had in two cheaper models of a similar design.

E74. THE "MALDON"
Loading: 1,000 Watts. Finish: Antique Brass. Overall Dimensions: 19½" W. x 18½" H. x 8½" D.

E75. THE "MACEDON"
Loading: 2,000 Watts. Finish: Antique Brass. Overall Dimensions: 19" W. x 22½" H. x 10½" D.



E72. HECLA "ADJUSTA-ROD"
Fitted with adjustable reflector. Size: 18½" W. x 18" H. x 11½" D. Finish: Oxy-copper and Chrome. Element: 13½" (one). Loading: 1,300 Watts. Elements: 13½" (two). Loading: 2,600 Watts.



WRITE FOR LEAFLETS

E77. HECLA "APEX"

Fitted with adjustable 9" reflector. Size: 9½" W. x 12" H. x 10½" D. Loading: 700 or 1,000 Watts. Finish: Chrome and Enamel.



E78. HECLA "MARLO"
Size: 15½" W. x 18" H. x 7½" D. Reflector: 12". Loading: 700 or 1,000 Watts. Finish: Oxy-copper and Chrome.

E79. HECLA "GEM"

Fitted with adjustable 9" reflector. Size: 10" W. x 16" H. x 10½" D. Loading: 700 or 1,000 Watts. Finish: Chrome and Enamel.



IN EXCLUSIVE DESIGNS OF ELECTRIC FIRES




**E80.
ENSIGN**

A neat, sturdy article complete with clip-on attachment, adjustable opaque shade, moulded Push Bar Holder and ferrule to match.

Colours available in: Mottled Pink, Mottled Green, Mottled Blue, Walnut.

CHARMING TABLE AND STANDARD LAMPS

Made in Duperite and Designed to
Meet Modern Requirements in Lighting



E84. BARON

This smart, modern Desk or Table Lamp has an adjustable Shade of charming design, weighted Base and Push Button Switch.

Obtainable in: Onyx Green, Onyx Pink, Onyx Blue, Onyx Amber, Onyx White, and Champagne.

**E85.
ROYAL**

An attractive Reading Lamp, with Push Bar Switch, clip-on attachment, weighted base and Chromium Swivel Joint.

Colours: Onyx White, Onyx Pink, Onyx Green, Onyx Amber, Onyx Blue and Champagne.



**E81.
CHIEF**

Specially designed Desk, Study, Display or Commercial Lamp, combining appearance with utility.

Heavily weighted moulded base, with wall clip, movable moulded arm, and reflector lined shade.

Obtainable in the following wood colours to match your Desk: Brown, Black, Mahogany, Walnut.

**E86.
MONARCH**

A Quality Lamp at an attractive price, with clip-on attachment, Push Bar Switch and Weighted base.

Available in: Onyx Green, Onyx Pink, Onyx Blue, Onyx Amber, Onyx White.




**E82.
COUNTESS**

A beautiful Lamp of unique design, complete with rubber covered Bed Clips. Chrome finish.

Obtainable in: Onyx Green, Onyx Pink, Onyx Blue, Onyx Amber, Onyx White, Champagne.

**E87.
THE EMPEROR FLOOR
STANDARD**

A graceful Standard. Obtainable with an attractive Black fluted base, Chromium stem, White moulded centrepiece and Buckram shades in Natural (off White), Primrose and Buff. Each unit is equipped with 4 yards silk covered flex and B.C. Adaptor.



**E83.
THE EMPRESS
MANTEL LAMP**

An exquisite lighting unit for the mantel or occasional table.

The fluted column is available in White only, but the base can be supplied in either Black or White, complete with Buckram shade in either Natural, Primrose or Buff, and equipped with 3 yards silk flex and B.C. Adaptor.

For maximum efficiency, 75-watt frosted globes are recommended.



**E88.
THE PRINCE
TABLE STANDARD**

A delightful Table Lamp, complete with 18" Buckram shade. Black base, Chrome and Natural trimmings.

Equipment details are the same as for the standard type.

For maximum efficiency, 100-watt frosted globes are recommended for the Prince and Emperor Lamps.

ALL AUSTRALIAN PRODUCTS OF DISTINCTION

Distinctive Lighting Fixtures

Space does not permit the showing of more than a few of the more popular designs from our range of fittings, of which there are literally hundreds in stock.

The newest designs, lovely in line and exquisite in colour, are always available and are being constantly added to as fresh shipments arrive.


If the particular design you require is not shown, ask us for it, we are certain to have it or can secure it for you.



Commercial Lighting Units suitable for Offices and Public Buildings.
E89. Fittings in Oxidized Copper and Florentine Bronze.



E92. SEMI-INDIRECT LIGHTING BOWL
Diam., 14".
Modern Design.



E93. OPAL ENCLOSED UNITS
10", 12", 14" and 16" Diam.



E95. CAST GLASS BOWL
"Prismatic"
Diam., 14".



E96. SEMI-INDIRECT LIGHTING BOWL
Diam., 15".




E90. SEMI-INDIRECT LIGHTING BOWL
Diam., 12" and 14".
Fitted with Gravity Hooks,
Chains and Canopy.




E91. OPAL ENCLOSED UNIT
10", 12", 14" and 16" Diam.

Good Fittings Deserve Good Globes
... Insist on NOX Electric LAMPS



E94. DOMESTIC BOWLS
Diam., 14".
Are available in a Wide Range of Colours and Decorative Treatment.



E97. BATHROOM UNIT
With Tiled Effect.
Diam., 9". Fitter, 4".



E98. ACORN FITTING
Diam., 8".

A FULL DISPLAY OF THE ABOVE FITTINGS TO BE SEEN IN OUR SHOWROOM

NEW VOGUE IN MODERN LIGHTING



Modern
Units
Featuring
Prismatic
Glass
Removable
Caps



E99.
CRYSTAL BASE UNIT

Diam., 10".
Length, 12 $\frac{1}{2}$ ".
Fitter, 4".
Lamp Size,
100 to 150 Watt




E100.
CRYSTAL BASE UNIT

Diam., 14".
Length, 13
Fitter, 6"
Lamp Size,
150 to 200 Watt



E101.
CRYSTAL BASE UNIT

Diam., 12".
Length, 14".
Fitter, 4".
Lamp Size,
150 to 200 Watt



E102.
ACORN FITTING

Diam., 8"
Fitter, 4"



E103.

TABLE LAMP
Chrome Plated

Height, 8 $\frac{1}{2}$ "
Diam. of Base, 9 $\frac{1}{2}$ "
Diam. of Ball, 8".

Also made with 6" Ball

E104.
ALL GLASS BRACKET
Projection, 8 $\frac{1}{2}$ ". Width, 5 $\frac{1}{2}$ ".



E105.

This Unit is specially suited for lighting Offices and Public Buildings.
Supplied with Oxidized Copper or Florentina Bronze Fittings.
Size: 14" and 16" Diam



E106. ACORN FITTING Diam., 10". Fitter, 6".



E107.
FLAMBEAU SHADE
Diam., 5". Fitter, 3".



E108.
WALL BRACKET, CHROME PLATED
Length, 10 $\frac{1}{2}$ ". Projection, 10 $\frac{1}{2}$ ". Max. Diam., 6".

WE SPECIALIZE IN INDUSTRIAL AND DOMESTIC


**KEMPTHORNE
EXTERIOR LIGHTING
EQUIPMENT**



E109. WINTON
16 $\frac{3}{4}$ " High.
8" Projection.



E110. WALTON
Height, 12". Projection, 5 $\frac{1}{4}$ ". Standard Finish, Black.



E111. BEVERLY
Height Overall, 23".
Projection, 10".
Standard Finish,
Black with White
Opal Glass.



E112. IRIS (Exclusive)
Height, 12 $\frac{1}{2}$ ". Projection, 8". Glass, Amber
or Flashed Opal. Standard Finish, Black.

LIGHTED
WITH
NOX LAMPS
OF COURSE!



E113. YORK
Height, 10 $\frac{1}{2}$ ".
Projection, 6 $\frac{1}{2}$ ".
Glass,
Amber Cathedral.
Finish,
Armour Bright.



E114. LINCOLN
Height, 13". Projection, 8". Glass, Amber
Crackle. Finish, Armour Bright.




E115. PETER PAN
Height, 25". Projection, 12 $\frac{1}{2}$ ".
Standard Finish, Black.



E116. DURHAM
Height, 13 $\frac{1}{2}$ ". Projection, 8 $\frac{1}{2}$ ".
Standard Finish, Black.

ALSO EXTERIOR LIGHTING -- WRITE TO US FOR DESIGNS

STARLYTE BOX FITTINGS



**E117.
VENUS CEILING FITTING**

Sizes: 15½" diameter with two fins.


All Box Fittings may be had in the following finishes:
Polished Chromium, Iridescent Gold and Silver Lacquer.

Glass: White or Amber Flashed Opal, White or Amber Sandblasted.



E118. DELPHIC

Overall Height: 28". Diameter: 17".
Glass: Amber. Finish: Ivory and Chrome.



**E119.
TUDOR 5-LIGHT**


Overall Height: 28". Spread: 21".
Glass: Amber Crackle. Finish: Armour Bright.



E120. STARLYTE

Overall Height: 28". Diameter: 16".
Glass: Amber or Peach. Finish: Ivory or Bronze.

DANKS FOR DISTINCTIVE LIGHTING



E121.

Height, $46\frac{11}{16}$ ins. Width, $23\frac{1}{16}$ ins. Depth, $21\frac{1}{4}$ ins. Approx. food storage capacity, 3.0 cu. ft. Shelf area, 5.0 sq. ft. Two single depth trays make 30 ice cubes per freezing. SPECIAL FEATURES include Cold Chest with meat grid; Cooling Chamber Door; Balloon-type Door Gaskets; "Economiser" Cold Control.

**CHOOSE
ELECTRICE . . .**
the only refrigerator with
Economic . . .
Cold . . .
Control

DESIGNED AND BUILT BY CRAFTSMEN TO MAKE
THEM THE MOST BEAUTIFUL AND EFFICIENT
REFRIGERATORS YOU EVER SAW.



E124.

Height, $55\frac{11}{16}$ ins. Width, $29\frac{1}{16}$ ins. Depth, $24\frac{1}{4}$ ins. Approx. food storage capacity, 6.3 cu. ft. Shelf area, 14.2 sq. ft. One single depth and one double depth tray make 84 ice cubes per freezing. SPECIAL FEATURES include Recessed "Quickshelf" Door; "Economiser" Freezing Speed Control; Automatic Interior Light; Removable Ice Tray Shelf; Cold Chest with meat grid; Cooling Chamber Door; Flexo Cube Tray Insert.

Silent . . .

FITTED WITH INTERIOR LIGHT —
AUTOMATICALLY LIGHTING WHEN
DOOR IS OPENED.

BUILT FOR AUSTRALIAN
CONDITIONS.

DANKS
for
Everything Electrical


Streamlined . . .
Dependability . . .
and real Economy . . that's
ElectrICE!

E122.

Height, $49\frac{13}{16}$ ins. Width, $24\frac{9}{16}$ ins. Depth, $21\frac{1}{4}$ ins. Approx. food storage capacity, 4.0 cu. ft. Shelf area, 8.8 sq. ft. Two single depth trays make 30 ice cubes per freezing. SPECIAL FEATURES include Recessed "Quickshelf" Door; "Economiser" Cold Control; Automatic Interior Light; Cold Chest with meat grid; Cooling Chamber Door; Balloon-type Door Gaskets.

E123.

Height, $52\frac{11}{16}$ ins. Width, $26\frac{9}{16}$ ins. Depth, $24\frac{1}{4}$ ins. Approx. food storage capacity, 5.1 cu. ft. Shelf area, 11.9 sq. ft. Two single depth trays make 56 ice cubes per freezing. SPECIAL FEATURES include Recessed "Quickshelf" Door; "Economiser" Freezing Speed Control; Automatic Interior Light; Cold Chest with meat grid; Cooling Chamber Door; Removable Ice Tray Shelf; Flexo Cube Tray Insert.




E125.

Height, $57\frac{9}{16}$ ins. Width, $34\frac{9}{16}$ ins. Depth, $24\frac{1}{4}$ ins. Approx. food storage capacity, 8.5 cu. ft. Shelf area, 18.4 sq. ft. Two single depth and one double depth tray make 112 ice cubes per freezing. SPECIAL FEATURES include Recessed "Quickshelf" Door; "Economiser" Freezing Speed Control; Automatic Interior Light; Cold Chest with meat grid; Cooling Chamber Door; Flexo Cube Tray Insert. Folding Tray Shelf.

"ELECTRICE" REFRIGERATORS A SUMMER NECESSITY. 100% AUSTRALIAN MADE

BREVILLE RADIOS


ELECTRIC - - BATTERY - - VIBRATOR - - HOME LIGHTING



VICTORY CONSOLE
34½" high, 31½" wide, 14" deep.



LYRIC CONSOLE
34" high, 27½" wide, 13" deep.



CAMEO MANTEL
11½" high, 18½" wide, 9½" deep

ZIP BUTTON TUNING

Just press button — your station is automatically tuned in. This feature equipped on Models E129, E130, E131, E133, E146, E147

Breville gives you everything you demand—finer tonal qualities, superb workmanship, and modern style at the price you want to pay. Engineered by experts, Breville's outstanding performance is acclaimed faultless. Models are listed below and offer you a wide choice of receiver, both Broadcast (Australian stations) and Dual Wave (Australian and Overseas reception), in Electric, Battery, Vibrator or Home Lighting Plant types. And the model you choose can be supplied in any of the lovely Consoles shown here (for minor exceptions, see list below). This is a convenience exclusive to Breville.

One day you'll probably own a Breville—why not make it to-day?

ELECTRIC RECEIVERS

E126.—4 Valve A.C. Broadcast. E127.—5 Valve A.C. Broadcast. E128.—5 Valve A.C. Dual Wave. E132.—6 Valve A.C./D.C. Dual Wave. (All available in Cameo Mantel and Liberty, Lyric and Victory Consoles.) E129.—5 Valve A.C. Dual de Luxe. E130.—6 Valve A.C. Dual de Luxe. E131.—8 Valve A.C. Dual de Luxe. (Available in Lyric, Liberty or Victory Consoles.) E133.—4 Valve A.C. Broadcast. E134.—5 Valve A.C. Broadcast. (Both in Pick-Me-Up model with built-in loop.)

BATTERY RECEIVERS

(Using Dry "A" and "B" batteries. E135.—4 Valve Broadcast. E136.—5 Valve Broadcast. E137.—5 Valve Dual Wave. (These three available in Cameo, Lyric, Liberty or Victory.) E138.—7 Valve Dual Wave in Lyric, Liberty or Victory Consoles.

PORTABLE MODELS


E139.—4 Valve, Battery operated. E140.—5 Valve, Battery. E141.—5 Valve, Battery or A.C. Electric. E142.—6 Valve, Battery or A.C. Electric. (All Broadcast types, in handsome portable case.)

VIBRATOR

(Using 6 Volt Accumulator—no "B" Batteries.) E143.—4 Valve Broadcast. E144.—5 Valve Broadcast. E145.—5 Valve Dual. (All available in Cameo, Lyric, Liberty or Victory.) E146.—7 Valve Dual Wave in Lyric, Liberty or Victory.

HOME LIGHTING PLANT RADIOS

(All Electric — just plug in to your Home Lighting Plant.) E147.—5 Valve Dual Wave in Lyric, Liberty or Victory.




LIBERTY CONSOLE
34½" high, 29½" wide, 13½" deep.


HOME LIGHTING PLANT RADIOS

If you maintain your own home lighting plant, you'll be interested in Model E147, a 5 Valve Dual Wave Receiver specially designed to work off your home lighting plant. Adjustable to various voltages and available in Lyric, Liberty or Victory Consoles - - Write for fuller details.

FOR RADIO BATTERIES
SEE PAGE 75



PICK-ME-UP
8" high, 11" wide, 7½" deep.



PORTABLE
13½" wide, 9½" high, 5½" deep.

DANKS FOR BREVILLE RECEIVERS "EVENTUALLY" — WHY NOT NOW?

NON-OSCILLATING



AND OSCILLATING

STANDARD ELECTRIC FANS


As Supplied to the Commonwealth Government

Non-Oscillating
Induction Motors


WALL OR
DESK TYPE

Oscillating
Induction Motors

Standard Finishes: All Brown, Green, with Brass Blades and Guard.
Special Finishes Extra



E148.



E149.


EXHAUST FANS



E150.

**Port-hole Exhaust Fans
For Light Duty Work**


Standard Finish:
Black Stove Enamel with Blades in Red.
With the exception of P.H. and P.N. Types, all Port-hole Fans are fitted with grease packed ball bearings
VENTILATED COMMUTATING MOTORS.



E151.

For Heavy Duty Work

Standard Finish:
Black Stove Enamel with Specially Formed Blades in Red.
All Elcon Heavy Duty Exhaust Fans are fitted with grease packed ball bearings.
VENTILATED COMMUTATING MOTORS.



E152.

**TABLE TYPE
GYRATIC FANS**
Induction Motors

Standard Finishes:
Black and Chrome.
Ivory and Chrome.
Pastel Green and Chrome.
Special Finishes Extra.

CEILING FANS



E153.

ENCLOSED INDUCTION MOTORS

Standard Finish:
Black with Three Polished Aluminium Blades.
Standard Suspension Rods: 24" and 36".
Elcon Ceiling Fans are supplied with a combination Ceiling and Three Plate Connector for direct mounting to Wood or Concrete.
Fitted with grease packed ball bearings.

E154.


Revolving Ceiling Fans

Standard Finish:
Black, Brass Blades and Guard.

Special Finishes Extra
Angle of Fan, 45°. Totally Enc. Gears. Sleeve Bearings with Wick Lubrication for 12" Type only.

Standard Suspension Rods: 36" and 48". Special Lengths can be supplied.

Ceiling Plate as with 3 Blade Ceiling Fan.



GYRATIC CEILING FAN.
VENTILATED COMMUTATING MOTORS.
NEW MODEL.

**D
A
N
K
S**

STOCKED BY MELBOURNE
AND SYDNEY

"ELCON" FANS FOR ALL PURPOSES -- WHOLLY AUSTRALIAN MANUFACTURE

Heralding the World's Light

HAMMOND ELECTRIC CLOCKS Correct Time



E155. Parkway
Height: 6 7/8".
Depth: 2 1/4".
Colours: Ivory, Green, Red.



E156. Stewardess
Height: 5 1/2".
Width: 6 1/2".
Depth: 2".
Colours: Ivory, Green, Red, Black.

**From
Your
Power-
Point
For
All
Time**

**DOMESTIC
OR
INDUSTRIAL
TYPES**



E157. Picardy
Height: 5 1/2".
Width: 5 1/2".
Depth: 2".
Colours: Ivory, Green, Red, Black, Chrome.



E158. Cathay
Height: 4 1/2".
Width: 3 7/8".
Depth: 2 1/4".
Colour: Ivory.

The "EXPRESS" ELECTRIC VACUUM CLEANER DE-LUXE

E159. PATENTED

Prolongs the life of Carpets and Rugs —
DISINFECTS as it cleans.

Complete home cleaner. Accessories all lock together. Designed to give maximum cleaning with minimum of labour; and is designed to enable it to work under **BEDS and LOW FURNITURE** with equal efficiency.

**NO STRAINING TO
MOVE HEAVY
ARTICLES.**

**NO
OILING**



E160.
**THE "EXPRESS"
STANDARD MODEL**
is fitted with Steel Skids instead of Roller Undercarriage.


NOX ELECTRIC LAMPS

**GASFILLED
CLEAR LAMPS**

15 to 500 Watts

PEARL

15 to 150 Watts



ALSO

STANDARD VACUUM LAMPS

15 and 25 Watts

A clear white light equal to daylight.

DAYLIGHT GASFILLED LAMPS

40 to 200 Watts

HEAVY DUTY VACUUM

Traction Filament Lamps
40 to 60 Watts

ALL LAMPS AVAILABLE IN B.C. OR EDISON SCREW CAPS.

We are Sole Agents in Australia for NOX Lamps.

MADE IN ENGLAND

ALWAYS THINK "DANKS" FOR ELECTRICAL APPLIANCES

STAN-MOR DRY BATTERIES



E165.
Heavy Duty and Triple Radio "B" Batteries
45 and 65 Volt, Upright Type



E166.
3 Volt Junior
2 Cell
Round Battery



E167.
1.5 Volt Intermediate
Torch Battery




E168.
1.5 Volt Standard
Round Battery



E169.
4.5 Volt Flat
Torch Battery



E170.
Radio "C" Batteries
Heavy Duty 4.5 V., Upright
Light Duty 15-9 V., Upright



E171.
1.5 Volt Standard
Dry Cell

V.I.R. WIRES AND CABLES

We are distributors of:-



J. & P. C.M.A. WIRES AND CABLES

Made by **JOHNSON & PHILLIPS**
CHARLTON, LONDON



Callender C.M.A. (Regd.) CABLES

Made and Tested in England in accordance with the Standards and Formula of the Cable Makers' Association.

Olympic

WIRES

SINGLE CORE
TAPED AND BRAIDED
250 V. GRADE

Manufactured in Australia according to British
Engineering Standard Specification and approved
by State Electricity Commission of Victoria.

INSULATED AND BARE CABLES -- ALL SIZES AVAILABLE AT DANKS

"RING-GRIP" CONDUIT FITTINGS, ETC.



E172.
ELBOWS
Fixed Reversible
Rings.
1 1/2, 2, 3, 4, 6, 8, 10, 12, 14, 16, 18, 20, 24, 30, 36, 42, 48, 54, 60, 72, 84, 96, 108, 120, 144, 168, 192, 216, 240, 270, 300, 324, 360, 420, 480, 540, 600, 660, 720, 780, 840, 900, 960, 1020, 1080, 1140, 1200, 1260, 1320, 1380, 1440, 1500, 1560, 1620, 1680, 1740, 1800, 1860, 1920, 1980, 2040, 2100, 2160, 2220, 2280, 2340, 2400, 2460, 2520, 2580, 2640, 2700, 2760, 2820, 2880, 2940, 3000, 3060, 3120, 3180, 3240, 3300, 3360, 3420, 3480, 3540, 3600, 3660, 3720, 3780, 3840, 3900, 3960, 4020, 4080, 4140, 4200, 4260, 4320, 4380, 4440, 4500, 4560, 4620, 4680, 4740, 4800, 4860, 4920, 4980, 5040, 5100, 5160, 5220, 5280, 5340, 5400, 5460, 5520, 5580, 5640, 5700, 5760, 5820, 5880, 5940, 6000, 6060, 6120, 6180, 6240, 6300, 6360, 6420, 6480, 6540, 6600, 6660, 6720, 6780, 6840, 6900, 6960, 7020, 7080, 7140, 7200, 7260, 7320, 7380, 7440, 7500, 7560, 7620, 7680, 7740, 7800, 7860, 7920, 7980, 8040, 8100, 8160, 8220, 8280, 8340, 8400, 8460, 8520, 8580, 8640, 8700, 8760, 8820, 8880, 8940, 9000, 9060, 9120, 9180, 9240, 9300, 9360, 9420, 9480, 9540, 9600, 9660, 9720, 9780, 9840, 9900, 9960, 10000


"RING-GRIP"
SADDLES, CLIPS, BUSHES





"RING-GRIP"

E198.
CEILING ROSES
Fitted with a very effective Cord Grip. Designed to take Cab Tyre Flex.



"RING-GRIP"

E199.
CEILING ROSES
FLUSH TYPE
2-Plate, 3-Plate, 4-Plate.

"RING-GRIP" QUALITY SWITCHES



"RING-GRIP"
E200.

5 AMP. SURFACE
SWITCHES
Roller and Rocket Types.



"RING-GRIP"
E201.



"RING-GRIP"
E202.

10 AMP. S.P. 1-WAY
SURFACE TYPE
SWITCHES



"RING-GRIP"

E203.
5 AMP. SEMI-
RECESSED
SWITCH



"RING-GRIP"

E204.
5 AMP. S.P.
INDUSTRIAL SWITCH
Roller Type.



"RING-GRIP"

E205.
5 AMP. S.P.
CEILING SWITCHES
Also in 2-Way.




"RING-GRIP"
E206.

10 AMP. DOUBLE
POLE SWITCH



"RING-GRIP"
E207.
10 AND 15 AMP. S.P.
SURFACE SWITCHES



"RING-GRIP"

E208.
LINKED SWITCHES
Coupled for Double Pole.



"RING-GRIP"
E209.
RECESSED FLUSH
PLATES
For Round Dolly
Flush Switches
4 1/16" x 2 3/4".



"RING-GRIP"
E210.
FLUSH
RECEPTACLES
4 1/16" x 2 3/4".

MINIATURE
ARCHITRAVE
FLUSH SWITCHES
E211.

3 AMP.
SINGLE
POLE



"RING-GRIP"




Side View
of Switch.

A LARGE RANGE OF FLUSH PLATES
AND SWITCHES AVAILABLE

Made in Brown
and White.

MODERNISTIC FLUSH SWITCH PLATES




"RING-GRIP"
E212.

WALNUT, 6 1/4" x 4 1/2".
WHITE, 6 1/4" x 4 1/2".



"RING-GRIP"
E213.


WALNUT, 4 1/2" x 2 3/4".
WHITE, 4 1/2" x 2 3/4".



"RING-GRIP"
E214.

WALNUT, 4 1/2" x 4 1/2".
WHITE, 4 1/2" x 4 1/2".

WALL PLUG AND SWITCH COMBINATION PLATES



"RING-GRIP"


E215.

WALNUT, 6 1/4" x 4 1/2".
WHITE, 6 1/4" x 4 1/2".



"RING-GRIP"

E216.
WALNUT, 4 1/2" x 2 3/4".
WHITE, 4 1/2" x 2 3/4".




"RING-GRIP"
E217.

WALNUT, 4 1/2" x 4 1/2".
WHITE, 4 1/2" x 4 1/2".

DANKS CAN SUPPLY THEM ALL

CLIPSAL

EFFICIENT ELECTRICAL FITTINGS



E220. FLUSH RECEPTACLES
10 Amp., 3 Flat Pins.
In Brown and White.



E221.
PONY FLUSH SWITCH
5 Amp., Single Pole.
Complete with Flush Plate.
In Walnut and White.



"CLIPSAL"
E222.
PONY FLUSH PLUG
5 Amp., 2 Flat Pins.
In Walnut and White.



CLIPSAL
E223.
AMERICAN TYPE FLUSH RECEPTACLES
2 Flat Pins.
In Brown and White



"CLIPSAL"
E224. FLUSH RECEPTACLES
10 Amp., 2 Flat Pins.
In Brown and White.



CLIPSAL
E225.
FLUSH SWITCHES
Mount directly into a
Round Hole.
In Brown and White.



"CLIPSAL"
E226.
POWER OUTLETS
10 Amp., 2 Flat Pins.
In Brown and White.



"CLIPSAL"
E227.
POWER OUTLETS
10 Amp., 3 Flat Pins.
In Brown and White.




CLIPSAL
E228.
AMERICAN TYPE FLUSH RECEPTACLES
3 Flat Pins.
In Brown and White



"CLIPSAL"
E229.
BELL MOUTHS
Screwed Type.
Sizes: 1/2", 3/4", 1".



"CLIPSAL"
E230.
METAL BOXES
For Flush Switches
and Plugs.
Single and Two Gang.
1/2" Single Conduit
Entry.




"CLIPSAL"
E231. OBLONG JUNCTION BOXES
Sizes: 1/2" and 3/4".
1, 2, 3 and 4 Ways.



CLIPSAL
E232.
BELL MOUTHS
Grip Type.
Sizes: 1/2", 3/4".
Straight and Elbow.



E233.
GRIP REDUCERS
Sizes: 1/2"-3/4", 3/4"-1",
1"-1 1/4", 1 1/4"-1 1/2",
1 1/2"-1 3/4", 2"-1 3/4".



E234.
ROUND JUNCTION BOXES
Sizes: 1/2", 3/4".
1, 2, 3 and 4 Ways.



"CLIPSAL"
E235.
GRIP COUPLINGS
Sizes: 1/2", 3/4", 1",
1 1/4", 1 1/2", 2".




E236. GRIP TEES
Sizes: 1/2", 3/4", 1",
1 1/4", 1 1/2", 2".




E237. GRIP ELBOWS
Sizes: 1/2", 3/4", 1", 1 1/4", 1 1/2", 2".
Also REVERSE ELBOWS
(Inspection Type.) Size: 1/2".

F.G.S. FITTINGS

ONLY STOCKED BY OUR
SYDNEY HOUSE



E238.
EARTH CLIPS
Sizes:
From
1/2" to 2".



E239.
CABLE LUGS F.G.S. TINNED
Sizes: 15, 30, 60, 100, 150, 200 Amps.

WRITE TO US STATING YOUR REQUIREMENTS FOR SWITCH GEAR

BIG SIX


MAKES A SINGLE WIRE — PLAIN OR BARBED —

Positively Stockproof

AND IS ACTUALLY SAFER THAN AN ORDINARY FENCE

• EXCLUSIVE FEATURES

- Absolutely harmless to Animals or human beings.
- One "Big Six" Charger controls up to 25 miles of fencing.
- Adjustable for three different strengths of sting — Dry, Normal or Wet Weather.
- The new and improved BIG SIX excels every other type of Electric Fence Charger—because of its Compact efficiency and dependability.
- No farm too small, no station too large, to benefit from this gigantic boon!
- BIG SIX, the last word in economical efficiency.



E240.

Vesta has designed a special battery—type 6FC5—expressly made for use with the "BIG SIX" Electric Fencer. Just the right size and capacity to give absolute satisfaction and years of good service to this popular "fence charger."

There is no better battery for the job—nothing more economical . . . in first and operating costs.

Vesta type 6FC5 has super-thick poro-hard plates to offset self-discharge losses and a specially mixed low gravity electrolyte to minimize sulphation.

This battery will only need recharging every eight weeks, and should give four or more years' highly satisfactory service.


No electrical or mechanical experience is necessary. Simply connect the wires to the battery terminals, one to an earth pipe; the other, as shown, is the fence wire.



E241.

VESTA "ELECTRIC"
FENCER BATTERY

This simple plan illustrates how easily any or all sections of a farm can be made stockproof with an electric fence without gates, all operated from the same charger. It is advised: One low wire for pigs; one high wire for cattle and horses; two wires for sheep.



To Save Fencing Costs, Install a "Big Six" ————— We are Sole Distributing Agents for Victoria

"WHITE ROSE"*Domestic Boilers***USEFUL INFORMATION**

RECOGNITION of the necessity of an adequate Hot Water Service has become more and more evident during recent times, and whether a building be one for investment purposes or a private residence, the comfort and low cost of upkeep of a slow-combustion "White Rose" boiler system ensures a well-worth-while return in service and satisfaction.

"White Rose" Domestic Boilers have been designed especially for hot water services and for burning coke or wood on the slow-combustion principle. They require little attention, and in addition to new installations, can be connected to existing systems, replacing units where heat has been supplied by gas or electricity. They also have been frequently installed to replace the old-fashioned boot or range system.

Efficiency.—"White Rose" Domestic Boilers are provided with complete draught control, which enables the fire to be burned fast or slow as desired. The water is contained in a jacket completely surrounding the fire, which ensures high efficiency.

Economy.—When the cost of gas, electricity, briquettes and oil are compared with the cost of coke burned on the slow-combustion principle, it will be realized why a more abundant supply of hot water at lower maintenance cost can be provided by the "White Rose" Boiler, than from a system heated by gas or electricity.


Cleaning.—The boilers are provided with access for cleaning. Openings over the waterways enable all internal surfaces to be cleaned. Openings on the bottom of the water jacket permit removal of any sediment. If water containing a large proportion of lime is used, as is necessary in some districts, the boiler should be cleaned out periodically. The interval can be determined by the extent of lime deposit occurring in the first few months after the service is put into use.

Soft Water Districts.—In most cases throughout this country the water is of a soft nature, or contains vegetable or mineral acids which it is advisable to guard against by the use of the rustless cast iron boiler.

"White Rose" Rustless Domestic Boilers.—In most parts of the State the water used contains quantities of foreign matter which cause rust or corrosion. The effect of this is that the water is discoloured, and is unsatisfactory for domestic purposes. This trouble has been totally obviated by the introduction of the "Bower Barffed" or Rustless "White Rose" Boiler.

These treated "White Rose" Boilers have been proved superior to any copper boilers, as the life of a copper boiler is affected by the sulphur fumes given off by burning coke. A chemical action is set up by the sulphur fumes coming into contact with the copper, and the thickest copper will decompose in a comparatively short time.

Automatic Regulation.—In a number of cases the automatic regulation of draught is considered an advantage. It serves to maintain a uniform temperature and also prevents overheating or boiling of the water in the system. The fitting of the automatic regulator enables the water in the system to be maintained at a pre-arranged temperature, usually about 160 degrees. The automatic regulator also has the advantage of limiting the fuel consumption of the boiler.



Operation.—The operation of "White Rose" Boilers does not require any special skill, and having full provision for regulation of draught, considerably less attention is necessary than the ordinary kitchen fuel stove. An instruction card is sent out with the boilers.

Chimney Flues.—In selection of a suitable chimney in a new or an existing building, a brick chimney is to be preferred to a pipe chimney on account of appearance and efficiency. Brick flues should, however, not be less than 8 inches internal diameter. A flue which is round or square in section is to be preferred, but if not so the difference between the greater width and lesser width should not be more than three or four inches.

If a pipe chimney of cast iron or steel is selected, less resistance to the passage of flue gases is offered, as the internal surfaces are smoother than the ordinary brick chimney, but the cooling effect of the metal is greater. It has been found advisable with metal chimneys to use pipe having a diameter of not less than six inches.

If fuel other than coke is to be used, it is advisable to increase the dimensions given above by up to 33 per cent., on account of the greater liability of soot being deposited.

All angles or bends as well as horizontal or inclined flues should have provision for cleaning internally.

THE CHEER OF A WARM WELCOME—THE CONVENIENCE AND LUXURY OF STEAMING HOT WATER AT A TURN OF A TAP — ALL AT AN AMAZINGLY LOW UPKEEP COST MAKE "WHITE ROSE" BOILERS A WORTH-WHILE INVESTMENT.

WRITE TO US ABOUT YOUR HOT WATER PROBLEMS

WHITE * ROSE

Cast Iron

Domestic and Sectional

BOILERS

for Hot Water Service & Central Heating


Made by HARTLEY & SUGDEN, Halifax, England

IMPORTANT! When Ordering or Inquiring:

The information we usually require to assist us in selecting the most suitable size and type of boiler is as follows:—

1. District in which boiler is to be installed.
2. Class of fuel (wood, coal, or coke)
3. Class of building (accommodation house, private residence, schools, hospitals, etc.).
4. Number of baths, basins, sinks, or other facilities for using hot water.
5. If for hotel purposes, the maximum number of guests the building will accommodate. Private residence, number of baths required. School or hospital, the maximum number of baths required for a given bathing period.

AUTOMATIC DRAUGHT REGULATOR for Hot Water Boilers H10.



Directions for Fixing and Adjustment.—The bulb of the Regulator must be immersed in hot water at the top of the Boiler. Any method of fixing, which enables this to be done, and avoids air pockets, will be satisfactory.

Screw the Regulator into the 2" tapping provided, and connect chain to the air door attached to the ashes door, or fixed on side of base.

Adjustment.—The chain between the lever and the ashpit air door should have its length adjusted by means of the sliding scale, so that when the lever rod is at rest the air door is sufficiently open to secure the desired water temperature.

To reduce the maximum air inlet through the draught door, lengthen the chain, and thus consequently lowers the temperature.

To increase the temperature, shorten the chain, which will increase the draught.

Any desired degree between the temperature range of the Regulator can be easily maintained by adjusting the sliding scale.

If the Regulator does not operate correctly when installed, it must not be taken apart or tampered with.



THERMOMETERS

Screwed

1" Gas Thread

H11.

Straight and Right Angle

White


Enamel

Scale


Reading.

60° 200° Fah.

Minimum Attention for
Maximum Satisfaction.



BOILER C.D.O
H12.





BOILERS C.D.1-3 of
this Type.
H13.

JOHN DANKS & SON
PTY. LTD.

Melbourne and Sydney,
are SOLE AGENTS for
"WHITE ROSE" Boilers

"WHITE ROSE" CAST IRON INDEPENDENT DOMESTIC BOILERS



DIMENSIONS

Cat. No.	A	B	C	D	E	F	G	H	J	K	L	M	Flow and Return Tappings
H12 C.D.O.	15"	17 1/2"	21 1/2"	4"	2 1/2"	20"	17"	2"	—	3 1/2"	4 1/2"	13 1/2"	1 1/2"
H13 C.D.1	19"	22"	32 1/2"	4 1/2"	7 1/2"	24 1/2"	23"	2 1/2"	5 1/2"	7 1/2"	7"	14 1/2"	1 1/2"
H14 C.D.2	19"	22"	40 1/2"	4 1/2"	7 1/2"	32 1/2"	31"	2 1/2"	5 1/2"	7 1/2"	7"	22 1/2"	1 1/2"
H15 C.D.3	22 1/2"	25 1/2"	46 1/2"	5"	9"	36 1/2"	35"	3"	7 1/2"	9"	9"	24"	2"

*Stoking Tools and Draw-off Cocks supplied unless instructed otherwise.
Ash-pit door can be arranged for automatic draught control when desired.

RATINGS

No.	Heating Surface	Water Content	Fuel Capacity	B.T.U. per hour	Hot Water Supply		Central Heating only	
					Gallons per hour		B.T.U. per hour	Direct Radiation
					50-100° F	50-150° F		
C.D.O.	3.	3.8	0.51	30,000	60	30	15,000	100
C.D.1	4.6	9.0	0.8	50,000	100	50	19,600	136
C.D.2	6.4	12.5	1.2	70,000	140	70	28,500	200
C.D.3	9.1	17.5	2.0	100,000	200	100	35,200	244


Suppliers of All Kinds of Appliances for Heating
... and Hot Water Services and Plumbing Needs ...

DANKS CAN SUPPLY A BOILER FOR EVERY REQUIREMENT

Plain or Rustless
**"White Rose" Cast Iron
Sectional Boilers**

NEW SERIES H.

**"White Rose" Cast-Iron
Sectional Boiler**



HEATING CAPACITIES

H5.

Boiler Heating Cat. No.	Surface sq. ft.	Heating Power 4" Pipes lin. ft.	Heating Power Direct Radiation sq. ft.	Gallons Per Hr. 50-150° F.	Length over Sections in.	Grate Area sq. ft.	Fuel Capacity cub. ft.	Water Content galls.
H4	21.5	510	660	230	24½	2.05	2.4	24½
H5	27	645	825	290	31	2.75	3.2	29½
H6	32.5	775	995	350	37½	3.45	4.0	34½
H7	38	905	1,169	410	43½	4.15	4.8	39½
H8	43.5	1,035	1,330	470	49½	4.85	5.6	44½
H9	49	1,165	1,495	540	56	5.55	6.4	49½

PLASTIC ASBESTOS

For Covering Boilers and Tanks.


"Danks" Plastic Asbestos can be applied either to a warm or cold surface, although a warm surface is preferable. In covering the surface with this material, it should not be applied in a single coat; whilst there is very little shrinkage, there might be some cracking in the drying-up, which can easily be prevented by putting on a thin spotting coat first; after this is well set and very nearly all the moisture evaporated, a second coat should be put on, leaving a rough surface; then a third coat can be used for finishing off. This can be trowelled down smooth. If these instructions are followed, especially where cold surfaces are covered, there will be no cracking of the covering. It is advisable to reinforce with wire-netting for cylinders, and this is usually put on after the first coat.

Supplied in 50 and 100 lb. bags.

The following quantities of Plastic Asbestos are required to cover 1½" thick of the various sizes of "White Rose" Domestic Boilers and Cylinders.

No. of Boiler	C.D.O	CD1	C.D.2	C.D.3
Lbs	25	25	40	50

There is a **"WHITE ROSE" BOILER** for
Every Heating and Hot Water Requirement



A typical design showing a villa installation using a **"WHITE ROSE" BOILER** (Made in England)

WE WILL PREPARE A SPECIFICATION FOR YOUR HOT WATER AND HEATING INSTALLATION

CRANE RADIATORS

MADE IN ENGLAND



H16.—Pall Mall 4-Column Radiator, for Water or Steam. Made in the following heights: 18", 24", 30", 36".




H17.—Pall Mall 6-Column Radiator, for Water or Steam. Made in the following heights: 18", 24", 30", 36".

BOILERS
AND
RADIATORS
AS
INSTALLED
IN
CITY
BUILDINGS,
INSTITUTIONS
AND
PRIVATE
RESIDENCES

WHITE ROSE BOILERS

MADE IN ENGLAND




CAST-IRON SECTIONAL BOILER

H21.—SERIES A1

Catalogue No.	Type and No. of Boiler	Dimensions over Sections			Heating Capacity B.T.U. per hour
		Length	Width	Height	
		ins.	ins.	ins.	
H20	613-A1	107½	46½	68	1,324,400
H21	612-A1	99½	46½	68	1,218,800
H22	611-A1	90½	46½	68	1,113,200
H23	610-A1	82½	46½	68	1,007,600
H24	609-A1	74	46½	68	902,000
H25	608-A1	65½	46½	68	796,400
H26	607-A1	57½	46½	68	690,800
H27	606-A1	49½	46½	68	585,200



H18.—Pall Mall 2-Column Radiators, for Water or Steam. Made in the following heights: 18", 24", 30".



H19.—Pall Mall 2-Column Radiators, for Water or Steam. Made in the following heights: 18", 24", 30".

FOR FULL PARTICULARS WRITE TO OUR HEATING DEPARTMENT

INSTALL CRANE RADIATORS ON YOUR NEXT HEATING JOB


The Dual Purpose Boiler and Open Fire

THE Dork
"WHITE ROSE"
BOGGER

In most modern small buildings, cellars and boiler houses are not provided, and Boilers are installed in the Hall, Room, Kitchen or other position where, exposed to view, the design of Boiler embodying plain external surfaces on neat modern lines, in addition to the variety of attractive enamelled finishes, ensures the source of warmth harmonizing with the general scheme of design and decoration. The illustrations show that the boiler may possess a closed waterway front with doors for fuelling and fire cleaning, or an open front with suitable doors and front fire grate, which latter is very popular in the kitchen to provide the cosy open fire for the maid and for drying clothes and similar purposes.

"YORK" White Rose BOILER

DIMENSIONS



With Closed Fire without Jacket

H29.

Pipe Connections are screwed up to and including 2" diameter. Returns can be on both sides $2\frac{1}{2}$ " from floor to centre on front and back sections. $5\frac{1}{2}$ " on intermediate sections. A return can be provided on back face $2\frac{1}{2}$ " to centre. Flows on any section except front. Usual small tapings on front section for mountings.

Smoke Pipe Connection (Y8 = 6", all others 5") is universal type, with socket end for horizontal or vertical connection, provided with cleaning door, check draught, and sliding damper. Supplied vertical unless ordered otherwise.

With Open Fire and Insulating Jacket

H34.



DATA

Cat. No.	Boiler No.	Heating Capacity		External Surface B.T.U. per Hr.	Boiler Heating Surface
		B.T.U. per Hour	Direct Radia- tion		
H28.	Y 3 - -	32,600	sq. ft. 225	2,940	sq. ft. 7 41
H29.	Y 4 - -	43,500	300	3,410	8 31
H30.	Y 5 - -	54,200	375	3,880	12 31
H31.	Y 6 - -	65,000	450	4,350	14 76
H32.	Y 7 - -	76,000	525	4,820	17 31
H33.	Y 8 -	87,000	600	5,290	19 66

Boiler No.	Grate Area	Fuel Capacity	Water Content	Length "A"
	sq. ft.	cu. ft.	galls.	ins
Y 3	.535	.671	6.1	11
Y 4	.815	1.013	7.4	14 1/2
Y 5	1.095	1.365	8.7	18 1/2
Y 6	1.375	1.712	10.0	22 1/2
Y 7	1.655	2.059	11.3	26
Y 8	1.935	2.406	12.6	29 3/4

COPPER STORAGE CYLINDERS AND CALORIFIERS

When ordering it is advisable to state the pressure under which the cylinder will be working, or the height from the cold water supply tank to the cylinder; also the size of connection bosses required.

Unless otherwise ordered, stock sizes and positions will be supplied
If any special positions are required, a rough sketch showing same should
be sent with the order.


Copper Hot Water Storage Cylinders

Tested to 30 lbs. per square inch.

Capacity	Dimensions in Inches	Capacity	Dimensions in Inches
20 gallons	42" x 14"	70 gallons	54" x 21"
25 "	45" x 14"	80 "	54" x 23"
30 "	48" x 15"	100 "	54" x 25"
35 "	51" x 15"	120 "	54" x 29"
40 "	54" x 16"	130 "	54" x 30"
50 "	54" x 18"	150 "	78" x 27"
60 "	54" x 20"		

Note.—When ordering Cylinders, please give position and size of pipe connections, and if for copper or iron pipe.

Prices for Copper Calorifiers and Cylinders of special size on application.



H.35.—Copper Cylinder

H36.—Calorifier

We Cordially Invite Architects, Builders, Consulting Engineers and Home Owners to call at Our Heating Showrooms, and Inspect
OUR WIDE RANGE OF HEATING EQUIPMENT

DANKS FOR COPPER CYLINDERS AND COPPER STORAGE TANKS

"Good Cooking depends on your Stove"

LUX FUEL STOVES

ALL "LUX" STOVES are SUPPLIED COMPLETE with 6 feet of Piping, Flue Brush, Rake, Poker, Plate Lifter, etc.




THE "LUX" STOVE

D1.

With Plate Warmer.

Dimensions:—
Width, 3' 6"; Height, Bare, 20"; With Plate Warmer, 28"; Depth, 19".
Oven (left), 19" x 15" x 14"
Oven (right), 19" x 15" x 12".




THE "LUX" STOVE

D2.

Oven and Fountain Model, with Extended Front.

Dimensions:—
Height, Bare, 20"; With Plate Warmer, 28";
With Extended Front, 28".
Oven, 19" x 15" x 14".
Capacity of Fountain, 1 gal.




THE "LUX" STOVE

D3.

Single Oven Model, with Feet.

Dimensions:—
Width, 30"; Height (with Plate Warmer), 28"; Height (without Plate Warmer), 20";
Depth, 19".
Oven, 19" x 15" x 14".




"LUX" All Cast Stove

D5. — A 24" Top Fire Stove, incorporating New Features: Open Fire Hot Plate; Convertible Fire Box for Burning Wood, Coal or Briquettes; Centre Flue with Cast Flue Box, fitted with Cleaning Door.

Bare—24" Wide, 25" High, 19" Deep
(As illustrated):

With Feet 34" High
With Extended Front 31" High
With Plate Warmer 33" High
Oven Capacity: 19" Wide, 12" High,
13 1/2" Deep.



THE "LUX" STOVE

D6.

A 30" Top Fire Stove to burn wood 24" in length

A Modern Stove—wholly of Cast Iron.

With large oven capacity. All parts renewable.

May also be had with Feet, with Extended Front, or with Plate Warmer, as desired.

Dimensions:—Width, 30"; Height (with Plate Warmer), 31 1/2";
Height (without Plate Warmer), 23 1/2"; Depth, 18".

Oven, 24" Wide; 10" High; 14 1/2" Deep.

Supplied with 6' of Piping, Flue Brush, Rake, Poker, Plate Lifter, etc.

Obtainable also in ATTRACTIVE
COLORED ENAMEL FINISHES
.. to Blend with your Kitchen ..


When ordering quote the number of the item only. Do not cut Catalogue. This is unnecessary and will destroy much of its further value to you.

FOR GAS AND ELECTRIC STOVES, PLEASE TURN TO PAGES 58-62

WE SPECIALIZE IN HOTEL RANGES

"ECLIPSE" STOVES

THE "ECLIPSE" TOP FIRE STOVE



D7.

The big feature of this Stove is that the front part of the Hot Plate can be completely removed, thus converting it into an open fireplace for heating the room. Made with Cast Iron Back. Ventilating Side Dampers. Fitted with Ash Pan and Swing Oven Doors. May be had with either fall or double swing Fire Doors.

D8.

Dimensions:—
2' long x 18" deep x 2' 3" high.
Oven, 18" long x 14½" deep x 11½" high.

Burns 18" wood.

D9.

2' 6" x 18" x 2' 3".
Oven, 2' x 15" x 11½".

Burns 24" wood.

D10.

3' x 18" x 2' 3".
Oven, 2' 6" x 15" x 11½".

Burns 30" wood.

THE "DUX" STOVE FOR COAL OR WOOD


D11.

The Fire Box of the "Dux" is fitted with Double Sliding Doors, and by a simple adjustment wood or coal can be used as desired. The proper regulation around the Oven has been well considered. The Oven Door is of the Swing Type. Body of Stove is of heavy sheet steel, with strong cast iron Hot Plate, Grate, Ashpan, Doors, etc. The Hot Plate is provided with three Boiling Holes.

Damper regulation is from the front of end of Stove.

Outside Measurement:

Size	Width	Depth	Height
24"	17"	24"	



THE "ECLIPSE" MODEL "C" STOVE


D12.

The "Eclipse" Model "C", is of Cast Iron throughout and is one of the very few 24" All-cast Stoves that is fitted with an Ash Pan. It has a Single Swing Oven Door and two Sliding Doors to the Fire Box, and has a Central Flue. The Fire Box is easily adjustable for burning Wood or Coal.

Outside Measurement:—

Size	Width	Depth	Height
24"	16½"	22"	

Can also be had with Legs at extra cost



JOHN DANKS & SON, PTY. LTD., are
Specially Equipped to do All Kinds of Repairs
... to Stoves and Ranges ...

"BOBS" STOVE

D13.


Sizes:

No. 1—24" wide x 27" high x 18" deep.

No. 2—30" wide x 27" high x 18" deep

No. 3—36" wide x 27" high x 18" deep.

Also 48" wide.




THE "COO-EE" COOKING STOVE

D14.

A simple and economical (and Fire) Stove. Fitted with Double Oven Doors and Long Fall Fire Door for burning long lengths of wood, and is easy to manage. Has an indicator to show which way to move Sliding Damper, for lighting fire or for heating Oven. It is strong and well made, of first-class finish, and cooks thoroughly and quickly. There are four lengths of piping, lifter and rake for cleaning Stove, given with Stove.

Dimensions:—

Nos.	Length	Depth	Height
D14	24"	18"	27"
D15	30"	18"	27"
D16	36"	18"	27"



ANDREW'S "NONPAREIL" STOVE (No. 1A)

D17.

Without
Hot Chamber

This Stove is a splendid cooker, and has become immensely popular, especially so for small villa use. It has two very roomy ovens.

Latches, Hinges, Knobs, and other Furnishings are nickel plated. 36" wide; 20" deep; 18" high without Hot Chamber. 27" High with Hot Chamber.


Andrews' "Nonpareil" Stoves can be supplied with or without Hot Chamber, or, alternative, with Stand and Legs. Either can be fitted with High Pressure Copper Coil Generator for Hot Water Service.



WHEN ORDERING—ORDER BY NUMBER
ONLY DO NOT CUT CATALOGUE

HOT WATER INSTALLATION CAN BE FITTED

THE "DOVER" STOVES FOR EITHER WOOD OR COAL



The "Dover" is the latest of its type in Fuel Stove Construction, and is a most reliable Stove. It has a simple, direct flue down end of Stove, which is brought up at the back of the Oven. This considerably helps the draught and gives extra heating surface to the Oven.

This Stove has Iron Linings, Drop-down Front Bars, and Extended Fire Box. The back lining is movable, for reducing size of Fire Box to suit coal or coke.

Sent complete with Cup Lifter, Scraper, Poker, and 6 feet of Stove Pipe.

The Elevated "Dover" D18.


Complete with Plate Rack and Splash Back
Width 29" Depth 19"

Width, including Extension Hob, 36".
Height to Hot Plate, 32½".
Height to Plate Rack, 46½".

The "Dover" D19.

Width 29" Height 25" Depth 19"

Width, including Extension Hob, 36".



Note.—Short and Elevated Legs are not interchangeable.

THE "PLANET" STOVES



The "Planet" Fuel Stove SIDE TYPE ON LEGS D22.

A reliable Stove made of Cast Iron throughout, which can be supplied with Legs as illustrated, with Plate Warmer in place of Legs, or Bare.

Dimensions:
Height: Bare, 19½"; with Plate Warmer, 25½"; On Legs, 28"; Width, 30"; Depth, 18½".

Oven Measurements: 17½" wide; 17½" deep; 14" high.

The "Planet" Fuel Stove

TOP FIRE TYPE BARE
Made in Two Sizes

D23.

Dimensions:

Height 24" Width 24" Depth 17"


Oven Measurements: 9" high; 18½" wide; 13½" deep.

D24.

Dimensions:

Height 26½" Width 30" Depth 18"

Oven Measurements: 11" high; 24" wide; 13½" deep.




The "Planet" No. 1 Open Top Fall Door Fire ALSO IN ENCLOSED TYPE D25.

Size Over All: 20" wide x 17" deep x 24" high.
Oven Measurements: 14½" wide x 13½" deep x 9" high.

The "A.N.A." Fuel Stove

With Plate Warmer
and Hot Water
Fountain

The A.N.A. Fuel Stove has been designed to give efficiency with Strict Economy. It is well made throughout from First Quality Materials, and is fitted with a Fire Box, adjustable for either Wood or Coal.



Made in two sizes.

	Width	Depth	Height		Width	Depth	Height
D20. . . .	24"	18"	22"	S.43A . . .	13"	15"	19½"
D21. . . .	30"	18"	22"	S.43B . . .	17½"	15"	19½"

NOTE.—The above measurements are for the Bare Stove. If with Plate Warmer, add 7" to the heights given. If with Fountain, add 6" to the widths given.

We Can also Supply the Larger
FUEL KITCHEN RANGES
and
COOKING APPARATUS
Suitable for Hotels, Guest Houses,
Mansions, and Public Institutions

TO ANY OF THE ABOVE STOVES

"IXL" Fuel Stoves



THE "I.X.L." SINGLE OVEN FUEL STOVE

D26.

Width, 24"; Depth, 19";
Height, 25½".

D27.


Width, 27"; Depth, 19½";
Height, 27½".

D28.

Width, 30"; Depth, 19½";
Height, 28½".

"I.X.L." PATENT FUEL STOVES


"I.X.L." Stoves are noted for their Simplicity, Economy, and Durability. They are made from Steel Plates specially procured for the purpose. A patent Direct back Draught does away with the Smoky Chimney nuisance and draws up the fire quickly. All "I.X.L." Stoves are sent out complete with Flue Brush, Lifter, Raker, Baking Tin, and 6 ft. Flue Pipe. "I.X.L." Stoves can be supplied to take the longer wood at extra cost. Made also with Side Boiler. This adds six inches to width of Stove. The Depth and Height are as in ordinary pattern.



Sizes of I.X.L. Double Oven Stoves, with usual Fire Box for Coal and Town Lengths of Firewood, and with Plate Warmer:

	Width	Depth	Height		Width	Depth	Height
D29	36"	19½"	25"	S 25	42"	23"	29"
D30	36"	23"	25"	S 26	48"	26"	31"
D31	39"	19½"	26½"	S 27	54"	31"	34"
D32	39"	23"	26½"				

If without Warmer, the height will be 8" less.



THE "I.X.L." SINGLE OVEN FUEL STOVE

CAST IRON
THROUGHOUT
WITH LEGS
D33.

Dimensions:—
24" Wide; 19" Deep; standing
on 10" Legs, which make the
Stove 27½" High.

Can also be supplied with
Plate Warmer instead of with
Legs. The dimensions being
the same in both models

When you think of
Stoves think FIRST of John Danks

THE "TRIUMPH" FUEL STOVE


The "Triumph" is a good
type of Top Fire Stove, manu-
factured by the makers of
"I.X.L." Stoves, and is equal
in quality to the "I.X.L."
pattern

It can be used either closed
in at the top or with the
centre raised to give an open
fire.

D34.

Width, 24"; Depth, 19";
Height, 27½".

D35.

Width, 30"; Depth, 19";
Height, 27½".

THE "FEDERAL" COOKING STOVE


D36.

The "Federal" has an im-
proved Fire Door, which is
the full length of Stove. The
Fire Box is constructed on
an entirely new principle, and
insures perfect Distribution of
Heat

The Bottom Plate under oven
is of Cast Iron, and the Outer
Sheet Iron Casing is protected
with Strong Cast Iron Plates
to prevent it burning through.
The whole of the top is a
perfect Hot Plate, and Uten-
sils can be kept boiling over
the whole surface. It is fitted
with a neat Ash Pan.

Outside Measurements:—
Width Depth Height

D36	24"	18"	27"
D37	30"	18"	27"
D38	36"	20"	30"





"UNIQUE" STOVE

D39.

No. 1—24" wide x 27" high x
18" deep.No. 2—30" wide x 27" high x
18" deep.No. 3—36" wide x 27" high x
18" deep.

Also 48" wide.



METTERS' "ACE" FUEL STOVE ALL CAST

D40.

No. 1—24"

No. 2—30"

WITH OR WITHOUT
FEET.

DANKS FOR STOVE PARTS AND REPAIRS



Old Style Colonial Oven
D41.

Made of Sheet Steel and supplied in the following sizes and gauges:

Width	Depth	Height
24"	18"	10"

D42.—Top in 10 gauge; Bottom, Shelf, Bar and Hob, 16 gauge.

Width	Depth	Height
24"	18"	12"

D43.—In 10 gauge Iron throughout.

Width	Depth	Height
24"	18"	12"

D44.—In 3/16" Iron throughout.

Width	Depth	Height
24"	18"	12"

Top in 3/4"; Iron Bottom, Shelf, Bar and Hob in 5/16".

The "Coo-ee"

Slow-Combustion Stove

For Heating Public Halls, Schools,
Workshops, etc.

D45.

The "Coo-ee" Slow Combustion Stove is a very efficient heater with low Fuel Cost, and it can be regulated to meet the heating requirements of the day. The "Coo-ee" is made of heavy gauge Steel with Cast Iron Stand, Base, Top, Furnace Doors, etc., and has a substantial lining throughout of Fire Brick

Height Over all, 31 1/2".

Width, 13 1/2"; Depth, 18 1/2".

Fire Brick Lining, 2" thick.

Flue Pipe Extra.

Smaller Size, D49.

Height, 22"; Width, 11"; Depth, 14".



WARM FRIENDS!

SLOW COMBUSTION HEATING STOVES
that will solve the Fuel Problem!



The Modernized
"KOSI"
HEATING STOVE

D46.

A very popular and economical type of slow combustion heating Stove in a new and modernized design. Will burn continuously at a fuel cost of about 2/6 a week and uses coke or briquettes—the cheapest form of fuel. Gives a steady glow of heat and burns slowly and evenly. The firebox is sealed.

In Fawn, Ruby, Green or Walnut Enamelled finishes.

NO SMOKE . . . NO FUMES . . . NO DIRT
but a Clean, Even, Glowing Heat all the time!

The "Excelsee" (Stocked by Sydney only)
D47.

Internal Flues.—Encircling Stove. Heat does not escape direct to chimney.

Front Grate.—Curved Fork to open up Fire Protecting Mica Windows.

Hopper Plate.—Protects Front and Directs Burning Fuel to Centre.

Back Draft Damper.—Controlling Draft under all conditions in fireplace or otherwise.

Shaking Grate.—Avoiding All Dust Nuisance.

Continuous Burning.—Obtainable 8 to 9 hours to Bucket of Coke.



The "REGAL"

D48.

Burns coke, coal or briquettes, and gives a steady heat at all times. No soot, dust or ashes. 30 in. high by 26 in. wide, and 16 1/2 in. from back to front.

In several enamelled finishes.

SEE NEXT PAGE FOR FURTHER TYPES OF THESE STOVES

**THE MOST BEAUTIFUL
HEATING STOVE,**


as well as the most Efficient!

D51.

In Mottled Beige Enamel Finish



One size only. Height 2'6", width 1'5 1/2", depth 1'1 1/2"; height to top of flue outlet 1'9 3/4"; diameter of flue 4 1/2". Attractively styled . . . as beautiful as a piece of lovely furniture, and just as great an attraction in any room.



No Soot - No Fumes - No Ash
A Steady, Even, Cheerful,
Glowing Fire.

"The
Loveliest
Stove
ever
designed!"

- Burns any kind of Fuel, Coke, Coal, Wood, Briquettes.
- Closed or Open Fire as you like.

- Cheap to run and a Stove you'll always be proud of!

Slow Combustion

- EASY TO INSTAL.

Obtainable in

Teapot Brown . . .

Moss Green . . .


French Grey . . .

Royal Blue . . .


"ESSE" Coke Stoves

D52.—"The ARTESSE" (shown on right)

Economical heat from coke fuel. Clean: no soot, dust or ash can enter the room. Requires little or no attention. The solution to the problem of internal heating.



INTERIOR GRATES



D53.

INTERIOR GRATES

Size 21" wide, 30" high, 18" fire.

Can be had in the following finishes:—Fine Cast with Oxidized Copper or Brass movable canopies, also Armour Bright, Oxidized Copper, Coin Bronze and Oxidized Silver.

D54.

ROUND

PATTERN

Solid Firebrick

Two sizes only:

18" and 21"

Armour Bright

Ox. Brass


Ox. Copper



PERFECT SLOW COMBUSTION

Order by Number - - Do Not Cut Catalogue

"DANKS" FOR ALL KINDS OF HEATING APPLIANCES



GAS STOVES

D55.


"KEMBLA" GAS RANGE

(On left.)

With thermostatically-controlled, heavily insulated Oven, rust-proof porcelain enamelled inside and out. Convenient Hot-plate with three boiling burners and a large grill unit with grill pan and grid.

All-porcelain enamelled finish in ALL CREAM, or GREEN, BLUE, GREY or BROWN mottled enamel with cream panels. All corners rounded and flush fitting oven door for easy cleaning. Square finish to base and legs to line up with modern kitchen fittings.

	High	Deep	Wide
Oven Dimensions:	15 in.	14 in.	15 in.



D56.

THE "NEW STATE" GAS STOVE

(FULLY PACKED)

DESCRIPTION: A modern Stove of good cooking capacity, with up-to-date Top Bars, "Star" Burners. Can be fitted with Automatic Oven Heat Control (extra).
Width Depth Height
Inside size of Oven: 14½ in. 13 in. 17 in.

D57.

"OBAN" GAS COOKER

(On left.)


Is Australia's latest and most modern approved gas cooker.

D60.

"SWIFT" GAS RANGE


(Lower right corner.)

Beautifully modern in appearance and with its unusually wide oven, the new approved "Swift" is an ideal family gas range, saving time, labour and money. It has all the outstanding features of the "Swift" cooker, whilst the arrangement in this case makes it ideal for easy working.



D58. RANGES ON SHORT LEGS

All Ranges can be fitted with short legs.




D59.

THE "ACME" LION

Frame constructed like a Motor Car.
Made of the Strongest Pressed Steel.
Thoroughly Rust-proofed.
Stove-Baked Enamel.
Improved Reversible Handle.
Improved Rubber-lined Clamps.
The "Acme" drains into either Trough.

Guaranteed 10 Years.



WRITE TO US FOR FULL PARTICULARS OF GAS STOVES


COPPERS AND COPPER FRAMES



**Regal
Copper Frame**
D61.

Made in the following sizes:—
10, 12 gals.

The Regal Copper Frame burns wood, coal or coke. Is easily moved about to suit the convenience of the user.



COPPERS

For building in Brickwork or use with Cast Iron Copper Frames. We strongly recommend the one-piece Seamless Copper as the most durable and satisfactory. These can be supplied in the following sizes:—

- D65.—Spun—10, 12, 14, 16, 18
20 gallons (light weight).
D66.—Spun—10, 12, 14, 16, 18
20 gallons (medium weight).
D67.—Special Heavy Quality
Spuners—10, 12, 14, 16, 18, 20 gallon.

Cast Iron Copper

D68.

Suitable for Boiling Down, or for any purpose where it is necessary to use Cast Iron in place of the ordinary Copper.

Can be obtained in any size, from 10 to 100 gallons.



**The "Family" Cast
Iron Copper Frame**
D69.

The "Family" is substantial and of good appearance. Finished Aluminium. Fire Box is lined with Cast Iron Cheeks, protecting the Frame from Fire. It has a circular Flue, which distributes the heat around sides and bottom of Copper.
Fitted with Sliding Fire Doors, Ash Pan, and 4 ft. Flue Pipe and Hood.
Draw-off Tap extra.



"ECLIPSE"
Cast Iron Copper Frame
D70.

This Copper Frame is our latest production in this line, and incorporates every modern improvement. It is made in sections, as are all our frames, and is of particularly handsome appearance. It has a totally enclosed ashpan, which prevents sparks flying. It is also fitted with a special flue of our own design, which absolutely prevents the annoying choking of the flue, and also gives a perfect draught. This flue has been highly praised by experts.

"UNIQUE"

Copper Cast Iron Boiler
Frames

D71.

	Inside Top
10 Gallons	18 1/2"
12 Gallons	19 1/2"
14 Gallons	20 1/2"
16 Gallons	22"
18 Gallons	22 1/2"
20 Gallons	24"
25 Gallons	25"
30 Gallons	26"

With each is supplied a 3 feet length of Galvanised Iron Chimney.

Extra Lengths, 3/- each.



COKE GRATES FOR USE IN OPEN FIREPLACES



Box Pattern
D72.


Supplied either with or without Trivet

Sizes: 12", 14", 16", 18"

Basket Pattern
D73.

Supplied either with or without Trivet

Sizes: 14", 16", 18" wide



FOR ILLUSTRATION OF "ACME" WRINGER TURN TO PAGE 91




Furnace or Copper Doors and Grates

D74.

Can be had singly or in pairs in the following sizes: 6" x 8", 7" x 9", 8" x 10", 10" x 12", 12" x 14".


We will make Grates to fit any size Stove. When ordering, please give measurement over all.



Grates Made to Fit Any Size Stove

D75. —Dampers may be had as follows, complete—Sizes: No. 1, No. 2 No. 3

We can supply extra Flue Pipe for Coppers and Stoves, in either Galvanised or Black Iron.
We recommend Black Iron for Stoves and Galvanized for Coppers.



**Simpson's Portable
Magnecrete Boiler
Stands
D76.**

Simpson's Portable Magnecrete Boiler Stands are CONSTRUCTED OF REINFORCED MAGNECRETE IN TWO SECTIONS.

Sections for Chimney are in 1 foot and in 1 ft. 6 in. lengths.

These stands are a great aid to economy. The cost of a Magnecrete is saved in first year by remarkable saving of fuel because of the perfectly set boiler and low thermal conductivity lessening radiation.

Sizes 10 to 40 gallons supplied at short notice.


Foundation Slabs for Wooden Floors and Flue Pipes extra




**The "Rose"
Copper Frame
D77.**

Made of Cast Iron throughout, and sent out with 4 ft. Galvanised Flue Pipe, with Cowl.

Made in 10 and 12 gallon sizes.



DANKS FOR VALUE



**Enamelled Copper
D78.**

Made of Heavy Gauge Iron and mounted on Strong Cast Iron Legs. Inside of Copper is heavily lined. Supplied with Enamelled Top and Cover and Gas Main Cock to connect to Gas Supply.

Capacity of Stock Sizes: 10, 12, 14 gals. Larger sizes made to order. All Coppers are fitted with 1/2" Draw-off Tap and with Sliding Door to regulate Air Supply. Galvanised Iron Flue Pipe, with Cowl, extra



**Black Sheet Steel
Portable Copper Frames
D79.**

We can supply from stock these Black Sheet Iron Frames, complete with Flue Pipe and Cowl and Cast Iron Grating

In 10, 12, 14, 16, 18 and 20 gallon sizes. Larger sizes, up to 100 gallons, to order.

**ORDER BY NUMBER ONLY—
Do Not Cut Catalogue.**

D80. Oven for Use with Kerosene Stoves (At left)


This Oven is very strongly constructed. It is reinforced in all vital parts, and is a really good, sturdy oven that will last. The body is made of heavy gauge steel. There are full tin linings at ends and back and top, which deflect the heat evenly, and a further lining of asbestos to make doubly certain that the heat is retained inside the Oven. This ensures a saving in fuel and better baking results.

A Heavy Sheet Iron Deflector spreads the heat from the flame evenly to all sides of the Oven. It has a strong Iron Door with Glass Panels, is smart in appearance, and each Oven is fitted with Strong Wire Racks.

Stocked in one and two Burner sizes

For FUEL STOVES, See Page 85.

High Quality Gas Rings



**Gas Burning
Rings
D81.**

Size: 4 1/2", 5", 6"


Note.—The 6" size has air regulator.

**Coke Grate for
Open
Fireplace
Drop Front
D82.**

Sizes: 14", 16", 18" wide.



WRITE FOR PARTICULARS OF GAS STOVES AS ILLUSTRATED ON PAGE 91



D83.
**TEA OR COFFEE
 URNS**

Suitable for Hotel, Cafe, or
 Factory use.


These are good strong Copper
 Urns in heavy gauge metal. They
 are made with One Tap only,
 for Tea or Coffee; or with two
 Taps and division for Tea and
 Coffee. Finished in polished
 copper or heavily nickel-plated.
 These Urns can also be had in
 Polished Tin, with all details as
 in Copper.

Sizes: 2, 3, 4, 6, 8, 10 gallons.

D84.
**HOT
 WATER
 FOUNTAIN**

Made of heavy Copper,
 tinned inside; brass
 tap; for use on top of
 stove.

Sizes, 2, 3, 4, 6, 8,
 10 gallons.




OIL STOVE

D85.

This new stove is just the right size
 for the average family. It is fitted
 with three powerful burners, with
 asbestos wicks—Safety, Cool Kitchen,
 Fast Cooking, Economy, Beauty,
 Simplicity and Rockweave Trouble-
 proof Burners.

Made also with two burners.



S I L E X

ALL STEEL ICE REFRIGERATORS

D86.

This medium priced but very
 attractive model has baked
 enamel finish and has the capa-
 city to meet the needs of most
 large families

Air conditioned by the use of
 the exclusive "Silex" system of
 air circulation by means of
 pressed directional vanes, in
 conjunction with insulated air
 circulation control tray.


Overall sizes, excluding hard-
 ware 45 in x 22½ in x 17½ in.

Capacity of Food Compart-
 ment, 2.9 cub. ft.

Number of Shelves, 3

Area of Shelf Space, 4½ sq. ft

Door Opening of Ice Compart-
 ment, 17 in. x 10 in.



TILLEY LAMPS

are

BRITISH MADE

Introducing the
**NEW ALL - PURPOSE
 LAMP AND LANTERN**

D87.

This is the most popular of all Tilley
 Lamps. It can be used as a storm
 lantern or hanging lamp by sliding on
 reflector as illustrated, or as a table
 lamp by removing the reflector and
 handle. Made of brass and fitted
 with English Pyrex Globes and solid
 brass internal pump. The single silk
 mantle is supported top and bottom,
 and is extremely strong, and will not
 shake off.



TALL TABLE LAMP

D88.


A really fine Lamp beautifully fin-
 ished in lacquered brass. Has a fine
 fluted column and stands 24" high,
 throwing a steady light over a large
 area. This Lamp develops 300 candle
 power, and as it is simple and easy
 to operate, is indispensable for the
 lounge or dining-room. Fitted with
 white Resistopal Shade, or, if pre-
 ferred, parchment of various colours.



**TILLEY
 LAMPS**

Burn Kerosene
 and are
 Perfectly Safe

WE STOCK ALL GRADES OF ICE CHESTS



FREE SAMPLES

Free samples are gladly forwarded on request. When writing, mention the approximate price per roll you wish to pay and the type of room or rooms to be decorated. Prices range from 8d. to 20/- per roll, and borders to harmonize with every pattern are available at from 1d. per yard up to 1/6. The table on next page will show you how many rolls you require, which may help you in deciding what quality paper you will use.

STANDARD SIZES

A standard size roll of wallpaper is 12 yards long and 21 inches wide. This will cover about 60 square feet. (See also table on next page.) Canadian and American papers of the better qualities are obtainable in rolls 15 yards long and 30 inches wide. These cover nearly twice the area of a standard size roll.

*The Magic Influence
of Color through*

WALLPAPER

*the Modern Motif for
Interior Decoration*

Nothing contributes more to the effect your home has on you and your friends than the treatment of the walls.

Nothing brings so much life, light and colour to your surroundings than carefully selected wall-papers.

Wallpapers are economical, too! No other wall treatment offers you the same wide variety of designs, textures or colourings, and the many exquisitely lovely patterns now available give you unlimited scope to exercise your good taste

To brighten a room, or to bring a new joy of living into your home, decorate with wallpapers . . . the modern motif in interior decoration.

It has been found impracticable to show even a fraction of the many designs and qualities of wallpapers in our showrooms. The range is so wide and new patterns are constantly arriving, so that no selection restricted to a few samples would do justice to our stocks.

You should write for our free samples, when we will gladly send you cuttings of our current range, including the newest designs from our latest shipments.

DANKS' FOR THE LATEST IN WALLPAPERS

CONSULT US ABOUT YOUR WALLPAPER PROBLEMS



"STIX" COLD WATER PASTE for Wallpapers

"STIX" PASTE is highly recommended for Hanging Wallpapers, and 1 lb. is sufficient to hang approximately 8 to 10 rolls of medium quality wallpaper. May be obtained in ½ and 1 lb. Cartons or Linen Bags, and various sized packages up to 28 lbs.

CALL AND INSPECT OUR BUILDING SPECIALITIES

OIL BAIZE AND FABREX CLOTH

Used Extensively for Kitchen and Bathroom Walls. Our Stock comprises a wide selection of designs from all Makers. Every Pattern a popular seller, 45", 48" and 50" wide.

Also a complete range of attractive designs in SHELVING BAIZES, 11" wide.

WALL BOARDS

For Lining Rooms, Ceilings, Window Backgrounds, Partitions, etc.

- * Nelson Board: ¾" thick, plain cream surface, comes in sheets 6' x 3' and 6' x 4', up to 12' x 3' and 4'
- * Upon Processed Board: ¾" thick, stippled cream surface, 6' x 3' and 6' x 4'. Sheets upward to 12' x 3' and 4'
- * Essex Board: ¾" thick, plain in same size sheets as above.
- * Gretex Board: ¾" thick, plain in same size sheets as above.
- * Ankarboard: Hardboard—glazed surface
- * Ankarboard: Heat and cold insulating and sound absorbing, in sheets 6' x 3' up to 6' x 12', ¾" thick
- * Tilux Asbestos Cement Wall Lining: In Colours
- * Duratite Asbestos Cement, Plain.
- * Fibro Asbestos, Sheets for exterior and interior use
- * Cane-ite: ½", ¾", 1" thick in plain and very finish
- * Masonite.
- * Preswood: ¾", 1", 1½" thick
- * Temptex Preswood: ¾", 1", 1½" thick
- * Temptex: ¾", 1", 1½" thick
- * Quarterboard De Luxe: ¾" thick

* Lines marked thus stocked by Sydney House only

Other Lines handled by this Department:

HESSIAN

6 ft. Wide, for Paper Hanging. 14 oz Calcutta; 18 oz. Calcutta; 16 oz. Dundee. (Guaranteed free from oil)

VITRAUPHANIE

Window Transfers, Imitation Leadlight Effects Modern Designs Also in Plain Colours: Red, Green, Blue and Amber; all 18" wide.



Helpful Hints for Home Decorators

WALLPAPERS AND LIGHT

When selecting wallpapers, it is often useful to know what effect the colour of the paper has on light, as householders frequently pay too much for gas or electric lighting simply because the wall coverings absorb a large percentage of the light rays. The table below shows the percentage of light absorbed by various colours, from which it is obvious that the lower the percentage of light absorbed, the brighter will be your room.

Colour	% of Light Absorbed	Colour	% of Light Absorbed
White	30	Emerald Green . . .	82
Chrome Yellow . . .	38	Dark Brown	87
Orange	50	Blue-Green	88
Yellow	60	Cobalt Blue	88
Light Pink	64	Chocolate	96

GUIDE TO QUANTITY OF ROLLS REQUIRED TO PAPER A ROOM

(Standard Rolls, 12 yds. x 21 ins.)

Measure round Walls, including Doors and Windows.

Measurement Round Room	Height in Feet from Skirting to Cornice						
	7 ft.	8 ft.	9 ft.	10 ft.	11 ft.	12 ft.	
32 feet	4	5	5	5	6	6	Number of Standard Size Rolls Required.
36 "	5	5	6	6	7	7	
40 "	5	6	6	7	7	8	
44 "	6	6	7	8	8	8	
52 "	7	7	8	9	9	10	
56 "	7	8	9	10	10	10	
60 "	8	8	9	10	11	11	
64 "	8	9	10	11	11	12	
68 "	9	9	10	12	12	13	
76 "	9	10	12	13	13	14	
80 "	10	11	12	14	14	15	
84 "	10	12	13	14	15	16	
92 "	11	13	14	16	16	17	
96 "	12	13	15	16	17	18	
100 "	12	14	15	17	18	18	

RE-DECORATION CALLS FOR "MODERN WALLPAPERS"


"B.P." Berger's Paint (Prepared)

For the inside and outside painting of homes and buildings. You get enduring beauty and absolute protection with "B.P."—Australia's foremost house paint. "B.P." quality is guaranteed on the can. "B.P." Undercoats are heavy in body so that they may be reduced for use as Primers or Undercoats to suit the type of surface on which they are to be applied. Supplied in: Dark Green, Cream, Light Brown, Green, Stone, Grey, Pink.

Synthetic "B.P." is designed especially for Trimming Work. The colours dry with an enamel-like gloss and withstand the elements for longer than any other similar paint. "B.P." is obtainable in 5-gallon drums, 1-gallon, $\frac{1}{2}$ -gallon, $\frac{1}{4}$ -gallon, pint and $\frac{1}{2}$ -pint tins.



160 IVORY



120 LT. APPLE GREEN




* 142 MAIL RED




101 LIGHT BUFF




* 121 NAVY GREEN




140 PURPLE BROWN



161 CREAM




* 122 LIGHT GREEN




126 FRENCH GREY



102 LIGHT STONE



* 143 VENETIAN GREEN



127 SMOKE GREY




104 STRAW



* 157 DEEP GREEN




169 DARK TAN




103 MID. STONE




4536 CHOCOLATE




130 PALE BLUE



168 DEEP STONE



117 RICH BROWN



164 DEEP BLUE

Shades marked thus * are higher in price.

COMPLETE COLOUR CARD AVAILABLE ON REQUEST

**LET BERGER'S STAND
BETWEEN YOUR HOME
AND THE WEATHER!**



No part of a house wears so quickly as the outside. That is where the ravages of time are most severely felt—and only White Lead Paint is strong enough to protect it. "B.P." BERGER'S PAINT (Prepared) is made of Genuine White Lead and Zinc Oxide in correct proportions! "B.P." will place an impenetrable coat of armour between your home and the weather to keep it safe from decay—and repair bills. Paint and save with BERGER'S—the Genuine White Lead and Zinc paint.



Berger's **"KEEPS ON KEEPING ON!"**

DANK'S FOR BERGER'S PAINTS AND VARNISHES

BERGER'S HOME PAINTING GUIDE

ALL FINISHES QUOTED BELOW WILL BE FOUND UNDER THE BERGER LABEL.



SURFACE	TO PAINT Use product named below	TO ENAMEL Use product named below	TO STAIN Use product named below	TO VARNISH Use product named below
BRICK WALLS (Exterior)	Prime with "Dusseal," Finish with "B.P." or Cement and Waterproof Paint	Prime with "Dusseal," undercoat and finish with Kem Super Finish		Weatherite (Clear, Waterproofing) Cannot be painted over Or 2 coats of Brick Glaze
CONCRETE WALLS CEMENT SHEETS (Exterior)	Prime with "Dusseal," Finish with Cement and Waterproof Paint or "B.P."	Prime with "Dusseal," undercoat and finish with Kem Super Finish		
CEMENT SHEETS (Interior)	Prime with "Dusseal," Finish with Matone "B.P.," "F.O.B." Cold Water Paint or Kalsomine	Prime with "Dusseal," Finish with Matone or Synthelac Satin Finish or Full Gloss or Kem Super Finish		
CEMENT FLOORS	Pave-ol Paving Paint		Lime-Proof Colours mixed with Cement	
EXTERIOR WOOD SURFACES	"B.P." Berger's Paint (Prepared)	Kem Super Finish or Enamelac (White)	Flat Stain and Varnish or Arboreum Wood Preservative—Brown	M.P. Copal, Fine Outside Oak or Synthelac Clear
EXTERIOR METAL SURFACES	Promeum Primer followed by "B.P.," Silverglo, Anti- Corrosive Paint, Ebo- nite or Hemacote	Promeum Primer followed by Kem Super Finish or Palladium		
FLOORS (Interior Wood)	Pave-ol Paving Paint		Flat Stain, "Quick" Stain or Homecraft Varnish Stain	"Quick" Clear or Special Floor Varnish
GALVANISED IRON SURFACES	New Iron, Prime Galvan- ised Iron Primer, Finish Structural and Roof or Hemacote	Prime with Galvanised Iron Primer or "pickle," follow with Kem Under- coats and Kem Super Finish		
INTERIOR WALLS AND CEILINGS	Matone-Flat Oil Wall Paint, "F.O.B." Cold Water Paint or Kalsomine	Enamelac (White), Synthelac— Full Gloss or Satin Finish or Kem Super Finish		
INTERIOR WOOD TRIM	"B.P." Berger's Paint (Prepared)	Kem, Synthelac Full Gloss or Satin Finish or "Quick"	Flat Stain, "Quick" Stain or Homecraft Varnish Stain	Fine Inside Oak, Nevamar, Synthelac Clear or Eggshell Flat
PORCH FLOORS	Pave-ol Paving Paint		Flat Stain	Special Floor Varnish or "Quick" Clear
RADIATORS AND PIPES	Silverglo or Matone	Engine Enamel or Synthelac		Nevamar Varnish
ROOFS (Metal)	Structural and Roof Paint, Anti-Corrosive Paint, Sil- verglo or Hemacote			
ROOFS (Wood Shingle)			Arboreum Wood Preservative—Brown	
STACKS AND HOT SURFACES	Silverglo or Smoke Stack Black	Engine Enamel		
STRUCTURAL STEEL	Prime Ledquid (Liquid Red Lead) or Promeum. Finish Structural and Roof, Anti-Corrosive Paint, Hemacote or Silverglo	Prime with Promeum. Finish with Kem Super Finish or Synthelac Full Gloss Finish		
TO DAMP-PROOF FOUNDATIONS	Asphaltum Black or Ebonite			
TO DAMP-PROOF WALLS	Damp Resister or "Dusseal"			
WOOD PRESERVATIVE			Arboreum Wood Preservative—Brown	Weatherboard Oil

Colour Cards free on request

DANK'S FOR BERGER'S PAINTS, VARNISHES & ENAMELS

APPROXIMATE COVERING CAPACITIES OF BERGER'S PRODUCTS

NAME OF PRODUCT.	SQUARE FEET PER GALLON (ONE COAT).
"B.P." Berger's Paint (Prepared)	850 to 1000 sq. ft. (on wood).
Cement and Waterproof Paint	800 sq. ft. over "Dusseal."
"Dusseal" (Cement Sealer)	300 to 320 sq. ft. on cement; 500 to 600 sq. ft. on plaster.
Facite (Facsimile Stone Finish)	30 to 33 sq. yds. per gall. (depends on thickness of application).
Factory White	1050 sq. ft. per gallon.
Flat Stain	500 to 600 sq. ft.
"F.O.B." Cold Water Paint	800 to 850 sq. yds. per cwt.
Galvanised Iron Primer	900 to 1000 sq. ft.
Hemacote	1200 sq. ft. reduced as instructed.
Homecraft Varnish Stain	500 to 600 sq. ft.
Kalsomine	350 to 500 sq. ft. per 5-lb. packet.
Kem Super Finish	650 to 675 sq. ft.
Master Painters' White	According to reduction.
Matone—"Wet-Edge" (Washable Wall Paint)	880 sq. ft. on rough surface; 1150 sq. ft. on smooth plaster when reduced 5 per cent. with Turpentine.
Pave-ol Paving Paint	600 sq. ft. on wood; 450 sq. ft. on cement.
Promeum Primer	925 sq. ft. when brushed.
"Quick" Enamel—Four-Hour Finish	650 to 675 sq. ft.
"Quick" Stain—Gloss Finish	500 to 600 sq. ft.
Rockgloss (Leadless) House Paint	700 to 750 sq. ft.
Rose Brand Ready Mixed Paint (sold by weight)	245 sq. ft. per 7-lb. tin.
Silverglo—Heat-resisting and Standard	850 to 1000 sq. ft. on any surface.
Stiff White Lead	According to reduction.
Structural and Roof Paint	900 to 1000 sq. ft.
Surtint (Strong Liquid Stainer)	For staining any white base.
Synthelac Full Gloss Finish	650 to 675 sq. ft.
Synthelac Pastel Tints (Full Gloss and Satin Finish)	650 to 675 sq. ft.
Tex (Texture Wall Finish)	1½ to 2-lb. per sq. yd., reduced 14-lbs. Tex to one gallon water.
Timonic White	According to reduction.
Varnishes	550 to 600 sq. ft. (average).
White Lead Paint	According to reduction.




Berger's ROCKGLOSS

(Leadless) HOUSE PAINT

"ROCKGLOSS" HOUSE PAINT is a ready-to-use leadless paint for either interior or exterior use, possessing splendid body and great oblitative power. It works easily and flows out well under the brush, drying hard with a glossy surface in from 10 to 15 hours, depending on weather conditions. Other shades not included below:—Venetian Red, Royal Blue, Middle Blue, Bungalow Brown, Pale Blue, Bright Blue and Platinum Grey. Obtainable in 1-gallon, $\frac{1}{2}$ -gallon, $\frac{1}{4}$ -gallon, pint and $\frac{1}{2}$ -pint tins.



CREAM




APPLE GREEN




PINK




LIGHT STONE




SHAMROCK GREEN



DARK IVY GREEN




MID. STONE



HOLLY GREEN



DARK CHOCOLATE




TERRA COTTA



WARATAH RED




DARK TAN




DEEP STONE




LIGHT TAN




PRIMROSE




BUFF




FRENCH GREY




SUEDE GREY



ROOF RED



CHOCOLATE



SALMON PINK



KEM

SUPER FINISH

"KEM" Super Finish is the ideal finish for cars, trucks, farm machinery and for house decoration. "KEM" dries with a gloss like glass and the finish is so flexible that it will not crack, chip nor peel. "KEM," because of its toughness and durability, greatly reduces costs for upkeep. A "KEM" finish is practically scratch and mar proof. In no other finish is there such enduring, glass-like finish. Available in 54 colours, and 10 tints from Quarts to 1/4-pints.



SYNTHELAC

FOR
CEILING

SYNTHELAC Full Gloss is preferred to the usual matt finish. With Satin Finish on the walls, an excellent contrast may be obtained by using SYNTHELAC Full Gloss tints of a similar hue for the woodwork. Ease of brushing and perfect drying without the slightest blemish or brush-mark characterise these SYNTHELAC Finishes and maintain their leadership for interior decoration.

Supplied in 54 vibrant, full gloss colours, the pastel tints of which are available in Satin Finish. Colour cards free on request. Obtainable in tins from Quarts to 1/4-pints.



FULL GLOSS AND SATIN FINISH

"QUICK" ENAMEL AND STAIN



It's wonderful what a little "QUICK" Enamel can do to brighten up home life! You simply brush it on for a lasting glossy surface that can be kept clean with just a whisk over with a damp cloth. "QUICK" dries in four hours and will not crack, chip nor peel. The complete range comprises 33 delightful colours, some of which are displayed below. Supplied in tins from Quarts to ½-pints.

More often than not stained floors and carpet surrounds wear very quickly near open doorways. You can easily restore the full glossy colour when this happens if you use "QUICK" Varnish Stain. "QUICK" Varnish Stain produces a handsome stained and varnished effect in one operation. It is for use on floors and woodwork, and is made in 9 natural wood shades. Supplied in tins from Quarts to ½-pints.

LIGHT IVORY

LILAC BLUE

JADE

IVORY

SPRING GREEN

CINNAMON BROWN

CREAM

CH BLUE

NILE GREEN

LETTUCE

YELLOW

POWDER BLUE

CHAMPAGNE

FOREST GREEN

CARMINE

LIGHT OAK

MAPLE

ROSEWOOD

DARK OAK

WALNUT

JACOBEEAN

COMPLETE COLOUR CARD AVAILABLE ON REQUEST

OTHER BERGER FINISHES

FOR HOUSEHOLD DECORATION

PAVE-OL PAVING PAINT



PAVE-OL is a hard-wearing paint made especially for the purpose of beautifying and protecting all types of concrete paths and floors, wood verandah floors and worn linoleums! PAVE-OL does not show heel marks and is **MADE TO BE WALKED ON!** Made in 13 lasting colours, Black and White, and a special Clear for Linos.

Supplied in tins from Gallons to $\frac{1}{2}$ -pints.

"F.O.B." COLD WATER PAINT



"F.O.B." is an oil-bound paste paint that only requires cold water for thinning, and may be obtained in 12 delicate colours and white. It is inexpensive, clean, hygienic and a perfect light reflector.

Supplied in tins from 56-lbs. to 2-lbs.

STRUCTURAL & ROOF PAINT



Give the roof of your home a saving coat of Berger's ROOF PAINT and rest assured that it is safe from decay and unnecessary repairs. One coat gives a solid covering that withstands sun, wind and rain. Made in seven colours, Black and White.

Supplied in tins from Gallons to Pints.

"WET-EDGE" MATONE

Berger's "Wet-Edge" MATONE provides a beautiful enduring finish for interior walls and ceilings. Its matt surface is pleasing and restful to the eyes, as it does not reflect light with a glare. Furthermore, each one of the 28 shades is washable and fadeless.



Supplied in tins from Gallons to Pints.

DUSSEAL—CEMENT SEALER

An efficient sealer for cement surfaces, protecting succeeding coats of paint from adverse action of cement alkali. Whilst closing pores of cement, also acts as a primer, thus dispensing with one coat of paint.



Supplied in tins from Gallons to $\frac{1}{2}$ -pints.

BERGER'S VARNISHES

NEVAMAR—Water-resisting, interior varnish for furniture and woodwork.

SPECIAL OAK—An interior varnish for use where an inexpensive finish is required.

SPECIAL FLOOR VARNISH—Recommended for new hard-wood floors. Will not show heel marks and is readily washable.



Berger's


PAINTS & VARNISHES

"Keep on Keeping on!"

FOUNDED IN LONDON—1760

DANK'S FOR PAINTS, VARNISHES AND PAINTERS' NEEDS

BERGER'S SILVERGLO (ALUMINIUM PAINT)



Water-proof.
Heat-proof.
Rust-proof.

For use on
Water Pipes,
Gas Stoves,
Coppers,
Wire Gates,
Iron Work,
Bath Heaters,
Meat Safes,
Motor Engines.

Sizes:
1, $\frac{1}{2}$, $\frac{3}{4}$, $\frac{1}{2}$ galls.
 $\frac{1}{10}$, $\frac{1}{32}$, $\frac{1}{64}$ galls.

ALUMINIUM
ALUM POWDERED
ACID OXALIC

PAINTERS' BRUSHWARE



VARNISH OR ENAMEL

SPECIAL

Sizes: 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 3 $\frac{1}{2}$ ", 4".
Pure Bristle. Medium length.
A Brush for the Amateur.

No. 15

Sizes: 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 3 $\frac{1}{2}$ ", 4".
Pure Bristle. Long length.
Suitable for Tradesman's use.

"PEERLESS"

Sizes: 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 3 $\frac{1}{2}$ ", 4".
Pure, extra long Bristle.
High-grade Tradesman's Brush.

"M"

Sizes: 1", 1 $\frac{1}{2}$ ", 2".
A cheap, short, pure Bristle Brush.

* "PETER"

Sizes: $\frac{1}{2}$ ", 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 3 $\frac{1}{2}$ ", 4".
Pure Bristle. Medium length.
Suitable for Amateur or Tradesman's use.

PAINTERS' BRUSHWARE (Continued)

VARNISH OR ENAMEL

* DANKS "A"

Sizes: 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 3 $\frac{1}{2}$ ", 4".
Pure, extra long Bristle.
A Craftsman's Brush.

* BONDZA


Sizes: 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 3 $\frac{1}{2}$ ", 4".
Pure Bristle. Similar to Danks "A."

* STREAMLINE

Sizes: 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 3 $\frac{1}{2}$ ", 4".
Pure, long Bristles.
Set in seamless, stamped Copper Ferrule.
Without nails.

* SHUTTER

Sizes: 1", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 3 $\frac{1}{2}$ ", 4".
Pure Bristle. Thin.
Made especially for Louvres.
Medium Sizes.



WALL OR PAINT BRUSHES

"PEERLESS"

Sizes: 3", 3 $\frac{1}{2}$ ", 4".
Pure, extra long Bristles.
A high-class Tradesman's Brush.

EXTRA

Sizes: 3", 3 $\frac{1}{2}$ ", 4", 4 $\frac{1}{2}$ ", 5".
A pure Bristle Brush. Medium length.
Suitable for Tradesman or Amateur.

No. 24

Sizes: 3", 3 $\frac{1}{2}$ ", 4", 4 $\frac{1}{2}$ ", 5".
Medium length.
Pure Bristle Brush for Amateur.

* WARATAH EXTRA BLACK

Sizes: 3", 3 $\frac{1}{2}$ ", 4", 4 $\frac{1}{2}$ ", 5".
Pure, extra long Bristle.
Very full bodied.

* "WAVERLEY"

Sizes: 3", 3 $\frac{1}{2}$ ", 4", 4 $\frac{1}{2}$ ", 5".
Pure, long Bristle. Similar to Waratah.

PAINTERS' BRUSHWARE (Continued)
WALL OR PAINT BRUSHES
*** BLACK BEVELLED WALL**

Sizes: 3", 3½", 4", 4½", 5".

Pure Bristle.

Shorter than Waratah or Waverley.

Bevelled at tip, making it ready for instant use.

*** GREY WEATHERBOARD**


Sizes: 3", 3½", 4", 4½", 5".

Pure, long Grey Bristle.

Very flexible.

Set in narrow Metal Ferrule.

Wears exceptionally well.


KALSOMINE BRUSHES
No. 18

6" wide. Pure Bristle.

Good quality. Medium price.

No. 18 A

6" wide. Pure Bristle.

Better quality than No. 18.

No. 93

6" wide. Extra long Black Bristles.

High-grade Tradesman's Brush.

No. 7

5" and 6" wide.

Good value.

*** STANPIL BLACK**

6" wide. Pure, long Black Bristle.

Set in special Vulcanite that will withstand action of minerals contained in Water Paints.

*** STANPIL GREY**

Pure, long Grey Bristles.

6" and 7" wide.

Similar to Stanpil Black.

KALSOMINE BRUSHES (Continued)
*** BONDZA BLACK**

6", 7" and 8" wide.

Long Black Bristle.

*** BONDZA GREY**

6", 7" and 8" wide.

Long Grey Bristle.

*** NERO**

6" and 7" wide.

Pure Black, medium length Bristle.

Suitable for Amateur or Tradesman.

A good Brush for light work.

*** DISTEMPER BLACK**

Pure Black, medium length Bristle.

A little lighter in weight than Stanpil Black and cheaper in price.


No. 47

Sizes: 3½", 4", 4½", 5", 6".

A short Black, pure Bristle Brush.

Designed especially for Amateur work.

Cheap in price.


FIBRE WHITEWASH BRUSHES

2 Tie

No. 6

No. 8

No. 10

3 Tie

No. 6

No. 8

No. 10

Flat: 4", 5", 6".

We also carry full stocks—

 Painters' Dusters, Stencil Brushes,
 Cutting-in Brushes,

Round and Flat Hog Hair Fitches.

Artists' Brushes.

In fact, all Painters' Brush Requirements.

LINES MARKED THUS * STOCKED BY SYDNEY HOUSE ONLY

BRIKO

* ANTI-DAMP SOLUTION



A Colourless
Preparation
that will
Waterproof
BRICK, STONE
and
CONCRETE
WALLS.

Sizes:
4 and 1 gall. Tins.
Covering Capacity:
15 to 20 sq. yds.
to the gall.
(2 coats.)



BOTANITE

A cheap Black Bituminous Enamel.
Suitable for Tanks, Sheep Troughs, etc.
Sizes: 4 gall., 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall., $\frac{1}{8}$ gall. Tins.

BLUESTONE BRUSH CLEANER

Quickstryp. Small Packets. Powder.
Lightning. Small Tins. Liquid.

BRONZES

Aluminium, Pale Gold, Deep Gold,
Copper, Antique.

CAR POLISH

Berger's Opex Liquid.
Berger's Opex Wax.
Adzon.
Johnson's "Carnu."

CEMENT

Portland or White.

CHALK

Lump, Powdered or Stick.

COLAS

4 gall, or 1 gall. Tins.

COPPERAS

Green and White.

CREOSOTE

Clear and Crude.
4 gall., 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall. Tins.

DRIERS PATENT

Sizes: 28 lb., 14 lb., 7 lb., 2 lb., 1 lb. Tins.

DRY COLOURS

BLACKS

Vegetable, Lamp,
Carbon, Ivory Drop.

BLUES

Ultramarine, Prussian,
Celestial, Cement.

BROWNS

Purple Brown, Raw Umber, Burnt Umber,
Raw Sienna, Burnt Sienna, Spanish,
Vandyke Brown Powder,
Vandyke Brown Crystals.

GREENS

Cement, Light, Middle and Deep Brunswick.
Light, Middle and Deep Bronze,
Paris, Oxide of Chromium.

REDS

Spanish Oxide, English Venetian,
Australian Venetian, Australian Red Oxide,
Indian, Pyrites, Permanent Mail.

YELLOWS

Oxford Ochre, Australian Yellow Ochre,
Lemon, Middle and Orange Chrome,
Cement Yellow.

WHITES

Flake White,
White Lead, Dry.
Zinc White.

ENAMELS

BERGER'S FAMOUS "QUICK" ENAMEL

S
E
E
T
I
N
T
C
A
R
D
P
A
G
E



I
N
L
A
T
E
S
T
S
H
A
D
E
S

YOU
can use "Quick" Enamel
— it's so easy!

VII.

PAINT
SECTION.

FOR KITCHEN, BATHROOM
FURNITURE OR WALLS



**BERGER'S
BATH
ENAMEL**

WHITE
AND
COLOURS

Sizes:

$\frac{1}{4}$ galls., $\frac{1}{2}$ galls.,
 $\frac{1}{16}$ galls., $\frac{1}{32}$ galls.

Also:

Undercoating
for above.
Same Sizes.

ENAMEL—PARKER'S

GOLD, ALUMINIUM, ANTIQUE, SILVER, COPPER.

Sizes: Midget, Small, Medium and Large Boxes.



BERGER'S "SYNTHELAC" ENAMEL

Made in Full Gloss and Satin Finish.

The Decorator's choice for Kitchen and Bathroom.
In Beautiful Pastel Tones.



Sizes:
 $\frac{1}{4}$ gall.
 $\frac{1}{2}$ gall.
 $\frac{1}{16}$ gall.
 $\frac{1}{32}$ gall.
Tins.

Write
Us
for
a
Tint
Card.

* **"FISHOILENE"**

Prevents Rust and Corrosion on Metal.
Sizes: 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall., $\frac{1}{8}$ gall. Tins.

FIREPLACE RED (BERGER'S)

$\frac{1}{2}$ pint Tins.

FURNITURE POLISH

Johnson's and Superglow.

GLASS PAPER

Oakey's English and Australian.
Grades: 00, 0, 1, $1\frac{1}{2}$, F2, M2, S2, $2\frac{1}{2}$, 3.

GLUES

Powdered, Sheet and Pearl.
Davis Liquid, Davis Gripit.
"Nuglu," Casco Waterproof, Varline.

GLYCERINE

Any quantity.

GOLD LEAF

Imported and Australian.
Books, 25 leaves each.
Plain and Transferred.

"HANSLICK"

For cleaning Paint, Baths, Sinks, Hands, etc.
Sizes: 1 lb., 5 lb. Tins.


KEROSENE

"Laurel."
Sizes: 4 gall., 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall. Tins.
13 oz., 26 oz. Bottles.

KALSOMINE
* **BERGER'S HYGIENIC**

5 lb.

P
A
C
K
E
T
S



A HIGH-GRADE
KALSOMINE
FOR WALLS
AND CEILINGS.
ATTRACTIVE
SHADES.

WE RECOMMEND IT.
WRITE FOR TINT CARD.

LACQUER

"Rogers" Brushing.
Full range smart Pastel Shades.
Sizes: $\frac{1}{4}$ gall., $\frac{1}{2}$ gall., $\frac{1}{16}$ gall., $\frac{1}{32}$ gall., $\frac{1}{64}$ gall. Tins.
Write for Tint Card.


LIME

Rock and Garden.

LIMIL

Bags, 50 lb. each.

LINES MARKED THUS * STOCKED BY SYDNEY HOUSE ONLY



PAINTERS' AND BUILDERS' STEPS

(Strongly made for hard usage.)

Each tread is screwed as well as nailed.

Styles: $3\frac{1}{4}$ in. x 1 in. (Finished size), selected Oregon.

Treads: $4\frac{1}{2}$ in. x 1 in. (Finished size), selected Pine.

Sizes: 4 feet to 10 feet.

PATENT SAFETY LADDERS

TWO SECTIONS




7 ft.	closed, extends to	12 ft.
8 ft.	"	14 ft.
9 ft.	"	16 ft.
10 ft.	"	18 ft.
11 ft.	"	20 ft.
12 ft.	"	22 ft.
13 ft.	"	24 ft.
14 ft.	"	26 ft.
15 ft.	"	28 ft.
16 ft.	"	30 ft.
17 ft.	"	31 ft.
18 ft.	"	32 ft.
20 ft.	"	35 ft.
22 ft.	"	40 ft.
23 ft.	"	42 ft.
24 ft.	"	44 ft.
25 ft.	"	46 ft.

GUARANTEED TO SUPPORT 30 STONE. LONGER LENGTHS ON APPLICATION.

May be fitted to extension ladder for electrical work.

BUILDERS' AND BRICKLAYERS' RUNG LADDERS



Made from selected Oregon with Spotted Gum Rungs and fitted with Tie Rods, ensuring rigidity.

Ordinary Rung Ladders

Suitable for Builder, Painter or Plumber.
10 in. centres.

Bricklayers' Rung Ladders

$8\frac{1}{2}$ in. centres.

Made in Sizes from 8 feet to 50 feet.

* LINO. AND FLOOR LACQUER (CLEAR)

Berger's. For reviving old Linoleums.

Sizes: $\frac{1}{4}$ galls., $\frac{1}{2}$ galls., $\frac{1}{16}$ galls., $\frac{1}{32}$ galls.



LEAD, WHITE, IN OIL (GENUINE)

Brands: Berger's, Balm, and Champion's.

Sizes: 1 cwt., 56 lbs., 28 lbs., 14 lbs., 7 lbs., 1 lb. Tins.

LEAD, RED

Sizes: 1 cwt., 56 lbs., 28 lbs., 14 lbs., 7 lbs.

* "MURDIRAT"

Rat Poison. 1 oz., 4 oz. Bottles.

METHYLATED SPIRITS

Sizes: 40 gall. Cylinders.

4 gall., 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall. Tins.

13 oz., 26 oz. Bottles.

BERGER'S "WET-EDGE" MATONE

F
L
A
T

O
I
L

P
A
I
N
T



S
I
Z
E
S

1 gall.

$\frac{1}{2}$ gall.

$\frac{1}{4}$ gall.

$\frac{1}{8}$ gall.

The Perfect Wall Finish.

Made in Lovely Pastel Tints and Warm

Neutral Shades.

Does Not Leave Any Brush Marks.

SEND FOR TINT CARD



Also Made in Various Shades.

Sizes: 56 lb., 28 lb., 14 lb., 7 lb., 4 lb., 2 lb. Tins.

BERGER'S FLAT OIL BOUND

Water Paint.
Suitable for Walls and Ceilings.
Sizes: 56 lb., 28 lb., 14 lb., 7 lb., 4 lb., 2 lb. Tins.

OIL, LINSEED

Raw, Boiled, Pale Boiled.
Brands: B.O.C., Blundel and Spence's, Halmeg, Meggitt's.
Sizes: 40 gall. Cylinders, 5 gall. Drums.
1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall. Tins.
13 oz., 26 oz. Bottles.

OIL, HARDWOOD AND WEATHERBOARD (BERGER'S)

A High Gloss, Hard Wearing Oil.
Suitable for Hardwood and Jarrah Surfaces.
Sizes: 5 gall., 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall. Tins.

OIL, GLASSARD

Similar to above.
Sizes: 4 gall., 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall., $\frac{1}{8}$ gall. Tins.


OIL, NEATSFOOT

Sizes: 4 gall., 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall., $\frac{1}{8}$ gall. Tins.

OIL, CASTOR

Crude.
Sizes: 4 gall., 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall. Tins.

"MERCURY" PAINT



Manufactured by Berger's.
Has Exceptional Obliterating Power and is
very Easy to Apply.

A Medium Priced Paint.

Sizes: 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall., $\frac{1}{8}$ gall. Tins.
 $\frac{1}{2}$ pint, $\frac{1}{4}$ pint Tins.

TINT CARD ON PAGE V.
PAINT SECTION.

TYRE PAINT (BERGER'S)

Black and White.
Sizes: $\frac{1}{2}$ gall., $\frac{1}{4}$ gall., $\frac{1}{16}$ gall. Tins.

ZONE PAINT (BERGER'S)

White, Yellow, Orange.
Sizes: $\frac{1}{2}$ gall., $\frac{1}{4}$ gall., $\frac{1}{16}$ gall. Tins.

SCHOOLBOARD PAINT (BERGER'S)

Black and Dark Green.
Sizes: $\frac{1}{2}$ gall., $\frac{1}{16}$ gall.

PAINT POTS

PROPERTY PAINT

V
A
L
U
E

F
O
R

M
O
N
E
Y



Sizes.
1 gall.
 $\frac{1}{2}$ gall.
 $\frac{1}{4}$ gall.
 $\frac{1}{8}$ gall.
 $\frac{1}{16}$ gall.

A Good Cheap Paint.
Covers Well. Ready for Use.

DANKS FOR ALL PAINTING REQUIREMENTS

PAINTS (Continued)

SEE
BERGER'S
TINT
CARD



G
U
A
R
A
N
T
E
E
D

P
U
R
E

does
prevent decay!

PAGE I. IN PAINT SECTION.

CHROMIUM GREEN HOUSE PAINT


Berger's

This Green is guaranteed not to Fade or Discolour. The Pigment, Oxide of Chromium, is the most Permanent Green known. Is unaffected by Fumes and Salt Air. Suitable for Roofs. Does not affect Drinking Water.

Sizes: 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall., $\frac{1}{8}$ gall., $\frac{1}{16}$ gall.

ROOF PAINT

Berger's Structural and Roof Paint



Lt. Slate
Brown
Red
Black
Green

Dk. Slate
White
Dk. Red
Tile Red

A Durable, Full-bodied Metal Protective Paint with Great Covering Capacity.

Sizes: 5 gall. Drums, 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall., $\frac{1}{8}$ gall. Tins.



Gives lasting Colour to Cement Paths, Worn Linoleum, Porch Floors, Verandahs and Floors.
All the Latest Shades.

Sizes: 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall., $\frac{1}{8}$ gall., $\frac{1}{16}$ gall. Tins.

**Berger's
HEMACOTE
FOR
METAL PROTECTION**

Composed of Non-Poisonous Pigments,
and is Anti-corrosive.

If applied according to instructions, will not Powder,
Scale nor Fade.

Sizes: 5 gall. Drums, 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall. Tins.

ELASTIC CARBON PAINT

Roylo Brand.

Suitable for Tanks, Sheep and Cattle Troughs.

Sizes: 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall., $\frac{1}{8}$ gall. Tins.

PAINT AND VARNISH REMOVER

Berger's, Solvit, Payntoff.


Sizes: 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall., $\frac{1}{8}$ gall., $\frac{1}{10}$ gall., $\frac{1}{20}$ gall.

PUMICE

Lump and Powdered.

WHEN YOU THINK OF PAINTS, THINK OF DANKS

BERGER'S HEAVY BODIED MASTER PAINTER'S WHITE



TWO gallons for ONE. Here's the reason why. 1 gallon "M.P.W." = 32 lbs. plus 1 gallon Raw Linseed Oil = 9 lbs. Total weight = 41 lbs. This gives two gallons of the Best Quality Paint for Interior or Exterior use. Weighing 20½ lbs. per gallons. Made in White only, but may be stained to any shade with "Surtint."

Sizes: 4 gall. Drums, 1 gall., ½ gall., ¼ gall. Tins.

CEMENT AND WATERPROOF PAINT

Especially made for Cement and Concrete surfaces, Stucco, Brick and Terra Cotta.

Manufactured by Berger's.

Sizes: 1 gall., ½ gall., ¼ gall., ⅛ gall. Tins.

PLASTERS

Victor, Ordinary, Bags, 1 cwt.

Victor, Hard, Victor, Cement.

Victor, Dental, Victor, Sanded.

Victor, Patching, 1½ lb. Pkts.

Wesco, Patching, 1½ lb. Pkts.

PUTTY

Best Linseed Oil.

Sizes: 1 cwt., 84 lb., 56 lb., 28 lb.

14 lb., 7 lb., 1 lb.

PUTTY WATER

Agnew's C.P. sets like a rock.

Can be Planed and Stained. Sets like Wood.

Sizes: 8 oz., 16 oz. Tins.

PITCH

7 lb., 4 lb., 2 lb., 1 lb. Boxes.

PHENYLE

Sizes: 4 gall., 1 gall., ½ gall. Tins.

PAPER, WET OR DRY GARNET

Grades: 2/0, 3/0, 4/0, 5/0, 6/0, 7/0, 8/0.

PUDLO

For Waterproofing Cement or Concrete.

Quantity, 3 lbs. to 100 lbs. of Mixture.

PLASTIC WOOD

Sizes: Tubes 2 oz., 4 oz., 8 oz., 16 oz. Tins.

RESIN

Any quantity.

* RAWL PLUG

Plastic Wood.

Durofix.

Liquid Porcelain.

* RESPIRATOR

"Utilite." Adapted specially for Paint Spraying, Harvesting, Fertilizers, Dry Colours, Cement, and other dusty operations.

SHELLAC

Flake, Orange, Button,

Ground White, Lump White.

SULPHUR

Powdered.

LINES MARKED THUS * STOCKED BY SYDNEY HOUSE ONLY

QUICK

VARNISH STAIN AND SILVER



Stains and Varnishes in one operation.
Suitable for Floors and Woodwork.
Also made in Clear.

Sizes: $\frac{1}{4}$ gall., $\frac{1}{2}$ gall., $\frac{1}{16}$ gall., $\frac{1}{32}$ gall. Tins.

SIZE, WALL

Wesco. See also Glues.

SOFT SOAP

1 lb., 2 lb., 28 lb. Tins.

SPORTS WHITE, "SEAGULL"

Suitable for marking Tennis Courts, Traffic Lines.
Sizes: 4 lb., 2 lb. Tins.

STAINS, CREOSOTE, "ELTREMACE"

Shades: Lt. Brown, Mid. Brown, Dk. Brown.
Lt. Mid. and Dk. Moss Green.
Clear and Crude.
Sizes: 4 gall., 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall.

SODA, CAUSTIC

Sizes: 1 cwt., 56 lb., 28 lb., 14 lb.,
7 lb., 2 lb., 1 lb., $\frac{1}{2}$ lb. Tins.

SATIN STOVE BLACK (BERGER'S)

For Stoves, Grates, Fenders, etc.
Sizes: pints, $\frac{1}{2}$ pints, $\frac{1}{4}$ pints.

D
R
I
E
S

I
N

F
O
U
R

H
O
U
R
S

STAINS, FLAT OIL (BERGER'S)

Gives a perfectly Flat Finish.
Shades: Lt. Oak, Dk. Oak, Mission Walnut,
Mahogany, Ebony, Moss Green, Jacobean,
Maple, Rosewood.
Sizes: 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall., $\frac{1}{8}$ gall., $\frac{1}{16}$ gall. Tins.

SPONGES

"Wescopal" Stippling Sponge.
* "Spontex" Viscose Sponge.
Washing Down Sponges.



Makes Old Floors
Like New.
Easy to Apply.

SHADES:

Lt. Oak, Dk. Oak, Walnut,
Maple, Mahogany, Cedar,
Rosewood, Jacobean, Ebony.

Sizes:

1 gall., $\frac{1}{2}$ gall.,
 $\frac{1}{4}$ gall., $\frac{1}{8}$ gall.,
 $\frac{1}{16}$ gall., $\frac{1}{32}$ gall.

GENUINE STAINERS IN OIL

COLOURS:

Reds, Browns, Yellows, Greens, Blues, Blacks.

Sizes:

28 lb Kegs.
14 lb. Tins
7 lb. Tins
2 lb. Tins
1 lb. Tins.
 $\frac{1}{2}$ lb Tins



SURTINT

STRONG LIQUID STAINER

Shades: Pale Chrome, Black, Burnt Sienna, Burnt Umber, Ochre, Mid. Green, Deep Chrome, Red Oxide, Prussian Blue, Sunproof Red, Brilliant Blue.

Sizes: 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall., $\frac{1}{8}$ gall., $\frac{1}{16}$ gall., $\frac{1}{32}$ gall.

TURPENTINE

Genuine. Leading Brands.

Sizes: 40 gall. Cylinders.

4 gall., 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall. Tins.

26 oz., 13 oz. Bottles.

"Mineral." (Substitute.)

Sizes: 40 gall. Cylinders.

4 gall. Tins, 1 gall. Tins, $\frac{1}{2}$ gall. Tins, $\frac{1}{4}$ gall. Tins.

26 oz., 13 oz. Bottles.

TAR, COAL

Sizes: 4 gall., 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall. Tins.

TAR, GENUINE STOCKHOLM

Sizes: 1 gall., Reputed Quarts, Reputed Pints.

TARZAN'S GRIP

For Mending and Fixing Wood, Iron, Marble, Leather, Auto. Parts, Tanks, Furniture, Radiators, Canvas, Fabrics.

TEX (TEXTURE)

"Berger's."

A High-grade Texture.

For converting Old Walls into Modern Ones.

TOXEMENT

For Waterproofing Cement. Per lb.



Full Stocks of all Types carried in Stock.

A Varnish for Every Job.

Oaks, Copals, Carriage, Body, Floor, Eggshell, Gloss and Flat, Gold Size, Terebine, Knotting, Black Japan, French Polish, Waggon.

Sizes: 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall., $\frac{1}{8}$ gall., $\frac{1}{16}$ gall., $\frac{1}{32}$ gall.

WHITING

Gostling's (English) and Australia.

WOOL, STEEL

Grades: 00, 0, 1, 2, 3. 1 lb. Rolls.

WOOD, PLASTIC

Tubes: $\frac{1}{2}$ lb., $\frac{1}{4}$ lb., 1 lb.

WAXES

Beeswax, Paraffin.

WAX, POLISHES

Glocoat, Nufloor, Wundawax.

1 gall., 1 lb.

Johnson's.

1 gall., 16 oz., 8 oz., 4 oz. Tins.

WAX, PALAIS

For Dance Floors.

8 oz. Pkts., 16 oz. Pkts.

WEATHERTITE

"Berger's."

For Waterproofing Brick Walls.

* WILL KILL

Ant Destroyer.

1 oz., 2 $\frac{1}{2}$ oz.

* WEAVERS, BORER, EXTERMINATOR

Sizes: 1 gall., $\frac{1}{2}$ gall., $\frac{1}{4}$ gall., pints, $\frac{1}{2}$ pints.

"WYANDOTTE"

For Cleaning Paint Brushes.

For Cleaning All Kinds of Surfaces before Painting.

ROOFING and FLOOR COVERINGS



Ormonoid Asphalt Roll Roofing

Made from high-grade materials, and very suitable for covering the roofs of Factories, Warehouses, and all types of buildings. Made in One, Two, Three, and Five-Ply, and supplied in rolls 72' long x 36" wide, complete with clouts and cement for fixing.

Sturdyoid Asphalt Roll Roofing

A very reliable roofing with a smooth grey surface, put up in rolls 72' long x 36" wide, sufficient to cover 200 sq. feet, allowing for laps. Supplied in One, Two, and Three-Ply, complete with nails and cement.

Permanoid Special Asphalt Roll Roofing

A very serviceable line for use on Barns, Fowl Houses, Out Buildings, etc., supplied in rolls 72' and 36' long x 36" wide.

"ORMONOID" ROOFING

Made from the highest grade rag felts and specially refined asphalts. Recommended for roofing, lining and insulating factory and all types of buildings. Being fume, acid and chemical proof, and impervious to salt air, makes cool, silent and rustless roofs. Does not affect drinking water. Best quality. Grey surface, in rolls 36" x 72'; 216 sq. ft. (covers 200 sq. ft., allowing for 2" laps). Complete with Clouts and Cement for fixing.

- 1 Ply, Light, for temporary work, with fixings.
- 2 Ply, Med., for ordinary conditions, with fixings.
- 3 Ply, Heavy, for permanent service, with fixings.
- 5 Ply, Extra Heavy, mica finish, with fixings.

or without Fixings.
Less 2/- per roll without fixings.

"ORMONOID" RED BITUMEN PAINT

1 pint, 1 quart, $\frac{1}{2}$ gall., 1 gall., 4 galls.

"ORMONOID" SHINGLES.

Made from Medium and Extra Heavy roofing. For waterproofing and decorative effect on window bays, balconies and door and window overhangs.

Size, 12" x 9".

RED, Medium and Extra Heavy.
GREEN, Medium and Extra Heavy.

Size, 12" x 9". Per bundle of 50.

Ormonoid 3-Ply Dampcourse

A very reliable Dampcourse, supplied in rolls 72' long x 4 $\frac{1}{2}$ ", 9", 13 $\frac{1}{2}$ ", 18", 22 $\frac{1}{2}$ ", 27", and 36" wide.

OUR LAYING DEPARTMENT will gladly give competitive quotations for ORMONOID laid complete to any specification to roofs and floors.

Daspyl Lead-Core Dampcourse

A superior Dampcourse made of pure Bitumen, with a lead centre. It is approved of by all Government Departments. Rolls are in random length, but the prices given are based on rolls 20' in length. With 1 lb and 2 lbs. lead centre. Widths: 4 $\frac{1}{2}$ ", 9", 14", 18", 22 $\frac{1}{2}$ ", 27", 31 $\frac{1}{2}$ ", 36".

Ormonoid Bitumen Paint

For Painting Ormonoid and similar Roofings and Floorings, Steel, Concrete, Bricks, Wood, Galvanised Iron, etc. Does not affect drinking water. Colours: Red and Black.

Asbeskote Paint

A tough elastic paint of asbestos fibres and bitumen, having exceptional weather resisting properties. For protection, repair and preservation of corrugated iron and all types of bitumen roofs. Easily applied with a brush. In tins ready for use. Does not affect drinking water.

Lastoleum Floor Covering

Specially suited for hard wear on wood, concrete, or damp commercial and industrial floors. Splendid for Hotel Bars and around Billiard Tables. Made in 3-ply standard finish; 5-ply Extra Heavy Smooth Surface Mica Finish. Also in Medium and Extra Heavy Red Polishing Surface. Supplied in rolls 72' long x 36" wide. Full particulars on application.

Tensite Building Paper

Asphalt-saturated for many uses where tough lightweight insulating or linings are required. Specially suited for lining fruit drying trays. Best quality, No. 7, 3' x 33 $\frac{1}{2}$ ' 4"; contains 1,000 sq. feet.

Oral Asphalt Saturated Felt

Made from selected high-grade rag felts and best quality refined asphalts. Specially recommended for underlayers to roofings, refrigeration and other insulating, and linings of walls, ceilings, floors, etc. Suitable for mulching tobacco and other plants. No. 12, Medium, 3' x 166' 8"; contains 500 sq. feet. No. 15, Heavy, 3' x 108'; contains 324 sq. feet.

"Duraseal" Plastic

Colours Red and Black. Bitumen Asbestos Compound for stopping leaks, plugging cracks and holes and waterproofing lead flashings. For caulking boats, troughs, etc. Stops leaks everywhere. In tins ready for use.

Quotes Gladly Given for Roofing, etc., Laid complete to any Specifications. JUST ASK US!

DANKS' BITUMINOUS ROOFING PAINT CEMENT AND ROOF DRESSING (Black)

This material is excellent for prolonging the life of bituminous and iron roofs, guttering, etc. Can also be used for sticking down bituminous roofing material and flooring. A very effective Damp-proof coating for concrete, iron, wood, etc. 1 pint, 1 quart, $\frac{1}{2}$ gall., 1 gall., 4 galls.



"ORAL" SARKING FELT

Extra heavy, asphalt saturated Felt for insulating and sound-proofing. Anti-squeak and packing for bridges, wharves and other steel and timber constructions.

- No. 37, Extra Heavy, 3' x 66' 8"; 200 sq. ft.
- No. 27, Heavy Weight, 3' x 66' 8"; 200 sq. ft.
- No. 17, Medium Weight, 3' x 66' 8"; 200 sq. ft.

FOR HIGHEST QUALITY INSIST ON "ORMONOID" ROOFING

Roofing and Flooring *(continued)*

"STURDYOID" ROOFING

1 Ply, 2 Ply, and 3 Ply.
Rolls, 72' x 3', with Fixings.
Less 2/- per roll if without fixings.

DANKS' PLASTIC CEMENT (Black)

Bitumen Asbestos Compound, for stopping leaks, plugging cracks and holes and waterproofing lead flashings, chimneys, parapet walls, concrete paths, tiles and galvanised iron roofs and brickwork. For caulking boats, troughs, etc. Stops leaks everywhere. In Tins, ready for use:
1 lb., 5 lb., 10 lb.

"ORMONOID" RED PLASTIC CEMENT

1 pint, 1 quart, $\frac{1}{2}$ gall., 1 gall., 4 galls.

"GIVANTAKE" ASPHALT EXPANSION JOINTING

For concrete roads. Manufactured from best materials, having cork filler and saturated felt on both sides. Supplied to, and in conformity with, the specification of the Main Roads Board. Made to any size and specification.
 $\frac{3}{8}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", $1\frac{1}{2}$ " thick—Prices on application.

"ORMONOID" PLY DAMPCOURSE

Thoroughly reliable dampcourse, made from heavy ply. In rolls 72' long:

3 PLY— $4\frac{1}{2}$ ", 9", $13\frac{1}{2}$ ", 18", $22\frac{1}{2}$ ", 27", 36" wide.
2 PLY— $4\frac{1}{2}$ ", 9".
5 PLY—18".

LED CORE DAMPCOURSE

Special high grade and permanently waterproof. Unaffected by mortar acids, and will not corrode or squeeze. Lead centre, best quality asphalt mastic on both sides. Approved by Department of Public Health. In rolls 20' long.

$4\frac{1}{2}$ ", 9", $13\frac{1}{2}$ ", 18", $22\frac{1}{2}$ ", 27", $31\frac{1}{2}$ " wide.
1 lb. lead centre, 2 lb. lead centre, 3 lb. lead centre.
Prices on application, owing to fluctuating Lead Price.

"DASPYL" LEAD DAMPCOURSE

$4\frac{1}{2}$ ", 9", 14", 18" wide.
In 2 lb., 3 lb. and 4 lb. lead; 20' and 30' rolls.
Prices on application, owing to fluctuations in lead prices.

"ORAL" ASPHALT SATURATED FELT

Made from selected high-grade rag felts and best quality refined asphalts. Specially recommended for underlays to roofings, refrigeration and other insulating and linings of walls, ceilings, floors, etc. Suitable for mulching pineapple, tobacco and other plants. Best quality.

No. 12, Medium, 3' x 166' 8"; contains 500 sq. ft.
No. 15, Heavy, 3' x 108'; contains 324 sq. ft.

"LASTOLEUM" FLOORING AND ROOFING

Specially suited for hard wear on wood, concrete or damp commercial and industrial floors. Best quality and waterproof. Rolls 36" x 72'; covers 24 sq. yds. Without fixings.

3 Ply, Heavy, standard finish.
5 Ply, Extra Heavy, mica finish, smooth surface.
RED, Extra Heavy, rich red polishing surface.
RED, Medium, rich red polishing surface.
GREEN, Extra Heavy and Medium.

The wearing surface on "LASTOLEUM" is an integral part, being a thick deposit applied during manufacture, which, unlike painted surfaces, will not crack or peel off.

"ORAL" NATURAL ASPHALT DAMPCOURSE

Made from asphalts specially selected for waterproofing properties, and will not squeeze. Approved by Department of Public Health in accordance with Local Government Ordinances. Excellent value. Rolls 30' long.

$4\frac{1}{2}$ ", 9", $13\frac{1}{2}$ ", 18", 22", $26\frac{1}{2}$ ", $35\frac{1}{4}$ " wide.
30' rolls.


"DAMPAX" No. 90 HESSIAN CENTRE DAMPCOURSE AND WATERPROOF SHEETING

Specially made to conform to Main Roads Board specification No. 164. Recommended for vertical and horizontal permanent waterproofing in Bridges, Viaducts and Basements. Rolls 24' long.

$4\frac{1}{2}$ ", 9", $13\frac{1}{2}$ ", 18", 36" wide.
24' rolls.


LET US QUOTE YOU FOR PAINTING YOUR "ORMONOID" FLAT ROOFING

DOOR LATCHES & LOCKS




C1.
"ETAS" RIM NIGHT LATCH
Black Japanned Finish, Brass Bolt and Knob.
Three Keys.

A complete stock of
all makes carried




C2.
**"ETAS" PATENT MORTICE CYLINDER
NIGHT LATCH**
Three Keys. To work outside with Key and from
inside with Knob. Size: $3\frac{3}{8}$ " x $2\frac{1}{8}$ " x $\frac{1}{2}$ ".



C3.
NIGHT LATCH
Strong, serviceable Latch with two Flat Keys.




C4. CYLINDER NIGHT LATCH
(Pressed Steel Case.) Bronze Finish with Walnut
Bakelite Knob. Brass Rose and Three Keys.
Size: $3\frac{3}{8}$ " x $2\frac{1}{8}$ " x $9/16$ ". Also Chromium Finish
W/Black Knob.



C5.
DOUBLE HANDED RIM LOCKS
Brass Bolts, 6" Steel Case
Complete with Milled Edge Brass Knobs.



C6.
R.M. LOCKS
Vaughan's 6" Rim Locks. Complete with Milled
Edge Furniture, either right or left hand.



C7.

FRONT DOOR CYLINDER LATCH SETS

Complete with Florentine
on Brass Front Plate,
Door Handle and Knocker
combined. May also be
had in Deadlocking

C8.
UPRIGHT 4" RIM LOCK
With Snib. Complete. With
Oxidized or Bakelite Handles.





KEY CUTTING

We have a Quick Service for Cutting Keys.
If the original Key is received by the
morning mail, new Keys will be despatched
the same day.

C9.

**BRASS HOOK BOLT
MORTICE LOCK**
For Cupboard Doors
1 and 2 Lever.
Sizes: $2\frac{1}{2}$ ", 3".
Faceplate.





C10.

**MORTICE
SLIDING
DOOR
LOCKS**
For Full Size
Doors.

C11.

**MORTICE
SLIDING
DOOR
LOCKS**



C12.

PANIC LOCKS

As approved by Board of Health for Public Halls,
Picture Theatre Doors opening out. Steel Case.
Size: 6".




C13.
**INDICATING
BOLT**

Bolt Case: $2\frac{1}{2}$ " x $1\frac{1}{2}$ "
Indicator Case: $2-13/32$ " x $1\frac{1}{8}$ ".


C14.

MORTICE LATCH
Brass Bolt, Face Plate
and Striking Plate.
Size: $3\frac{3}{8}$ " x $2\frac{1}{8}$ " x $\frac{1}{2}$ ".




C15.

RIM LOCK STAPLES
For 6" Rim Lock.
When ordering, state hand
required.
Illustration right hand.




C16.
RIM LOCK FURNITURE
Brass Knobs, Milled Edge
Also Ant.que Finish on Steel Knobs.

DRAWER AND CUPBOARD LOCKS



C17.

DRAWER OR CUPBOARD LOCK
With Cylinder. Is locked by simply pressing on
front rim of cylinder. Solid Brass. Two Keys.



C18.

**STRONG BRASS
DRAWER OR
CUPBOARD LATCH**
Steel Cap.
Size: 2" x $1\frac{1}{8}$ ".


C19.

**BRASS WARDROBE
LOCKS**

Complete with Striking
Plate and One Key.
Right or left hand.
Left hand illustrated.
State which hand when
ordering.



DRAWER AND CUPBOARD LOCKS



C20.



DRAWER LOCKS

Brass: 1½", 2", 2½", 3".
 Best English 2 Lever
 2", 2½", 3".

C21.

BOX OR CHEST LOCKS

Iron: 3", 4".
 Brass: 1½", 2", 2½", 3".
 Brass with Best
 English 2 Lever
 Sizes: 1½", 2", 2½"



C22.

BRASS SHOW CASE LOCK


With strong Bolt to
 shoot out at back of
 Lock. 2 Lever
 Sizes 2½", 3"

C23.

CUPBOARD LOCKS

Double Handed.

Iron: 2½".
 Brass: 2", 2½", 3".
 Brass: 1½", 2", 2½", 3".
 Brass, Best English Lever
 1½", 2", 2½", 3"



C24.

LOCKER LOCKS

Size of Case overall:
 1½" x 2½" x 9/16".
 6 Lever.



C25.

STEEL CUPBOARD CATCHES

Finished in Antique Copper
 or Nickel.
 Sizes: 2" x 1½", 2½" x 1-7/16".



C26.


SCARBOROUGH TRUNK LOCKS



C27.

WIRE DOOR LATCHES

Bronze Finish.
 For Doors opening In or Out.
 State which you require.




C28.


WIRE DOOR LATCHES

Bronze Finish
 For Doors opening
 In or Out.
 State which you
 require.

Mortice Lock Sets



C29.



C30.



C31.



C32.

MORTICE LOCK SETS. Complete with 2 Lever Lock. Finish, Florentine Bronze.

Plate: 7½" x 2½".
 Knob: 2½" x 1½".

Plate: 7½" x 2½".
 Knob: 2½" across Flats.

Plate: 7" x 2½".
 Knob: 2½" x 1½".

Plate: 7" x 2½".
 Knob: 2" dia

LOCK SETS MAY BE HAD IN ANY FINISH AT SLIGHT EXTRA COST



C33.

Plate: 6½" x 1½".
 Knob: 2½" x 1½".




C34.

Plate: 5½" x 1½".
 Knob: 2½" x 1½".



C35.

Plate: 8" x 2½".
 Knob: 2½" across Flats.



C36.

Plate: 6" x 1½".
 Lever: 3½" long



C37.

Finish, Bakelite,
 Walnut or Ivory
 Plate: 7" x 2½".
 Knob: 2½" dia.



C38.

BALL LATCHES
 Stamped Brass with
 Steel Ball, ½".

Heavier Type with
 Cast Brass Cases
 Sizes with Plate:
 5" x 1½" and 7" x 2".



C39.

Finish, Black Bakelite
 and Chromium



C41.

REVERSIBLE REBATED LOCK

These Locks can be
 fitted in place of
 ordinary Locks to sets
 shown on this page.

DOUBLE BALL CUPBOARD CATCH

Brass with Steel Balls,
 adjustable tension.
 Sizes: 1-11/16", 1 15/16", 2½".

Finish, Florentine Bronze.
 Rose: 2½" x 2½".
 Lever: 3½" long.
 Escutcheon: 1-11/16" x 1".


WE SPECIALIZE IN ALL HOME REQUIREMENTS




C47.
LATCH KNOCKER
PLATE
Florentine Bronze
Finish on Brass.
To take Yale Latch
Cylinder.
Size: 3" x 2 1/2".



C48.
DOOR GRIP
Finish, Antique
Copper on
Steel.
5" overall



C49.
"BRITON" HYDRAULIC DOOR CLOSER
AND CHECK
Strongly built and gives positive control all
the way. A—for Light Doors, B—for
Medium Doors, C—for Heavy Doors.



C52.
"DUX" HYDRAULIC DOOR CLOSER
AND CHECK
Closes the door quietly and firmly. Can be
had for doors opening out. Also with device
for holding door open at 30° and 90°.
A—for Light Doors, B—for Medium Doors.
C—for Heavy Doors.



C53.
SPRAL DOOR SPRINGS
Japanned: 8", 9", 10", 11", 12".
Nickel Plated: 9", 10".



C58.
DOOR SILENCERS
For slamming doors.



C57.
AUTOMATIC DOOR
HOLDER



C59.
RUBBER DOOR
STOPS
1 1/2" diam.
Screw to floor
Colours: Red,
Black, Blue,
Green, Brown.



C55.
PRESSED OR
CAST STEEL
HANDLE
Finish,
Florentine.
Sizes: 4 1/2", 6".



C54.
PRESSED
STEEL PULL
HANDLE
Finish,
Japanned,
Florentine
Nickel Plated
Size: 4".




C56.
SCREEN DOOR SPRINGS
Japanned: 16" long.


DANKS for BUILDERS HARDWARE



C60.
LETTER PLATE
Horizontal or Vertical, Plain or Lettered
as illustrated.
Finish, Florentine Bronze, Chrome Plated.



C61.
DOUBLE ACTING SURFACE FLOOR HINGES
Have positive, smooth compression spring
action. Tension easily adjusted and simple
to fit by setting square plate into floor and
sawing out rectangular piece at bottom
corner of door.
To suit 1 1/2" to 1 3/4" Doors with Antique
Finish Side Plates.



C62.
DOOR CHAINS
Allows doors to open
few inches only. Black
Japanned and Antique
Finish




C63.
DOOR CHAINS
Plain design, Finish,
Florentine on Brass.



C64.
DOOR STOPS
To hold doors open; simply
kick with the foot to release.



C65.
DOOR BELL
To turn; may
also be had to
push.




C66.
SCREEN DOOR CLOSER
A splendid device for automatically closing and
preventing Screen Doors from banging.
Finished in Bronze or Colours.


LET US QUOTE YOU FOR YOUR BUILDING NEEDS




C67.
STEEL BACK FLAPS
Sizes: 1", 1½", 1¾", 1⅞", 2", 2½", 3".



C71.
LOOSE PIN BUTT HINGES
Very useful on Wire Doors.
Sizes: 2", 2½", 3", 3½", 4".




C76.
BALL KNOB BUTT HINGES
Florentine on Steel Loose Pins, Plain and Ball Bearings. 3" x 3", 3½" x 3½", 4" x 4".
Also Broad Butts. Bright Steel Fixed Pins: 3" x 3", 3½" x 3½", 4" x 4". Bright Steel Loose Pins, 3" x 3", 3½" x 3½", 4" x 4".
The above can be finished Florentine Bronze.



C78.
HEAVY SCOTCH TEE HINGES
Sizes: 8", 10", 12", 14", 16", 18", 20", 22", 24".



C79.
STEEL TEE HINGES
Sizes: 3", 4", 6", 8", 10", 12", 14", 16", 18".




C72.
SURFACE SPRING HINGES
For Wire Doors.
Pressed Steel.
Finish, Japanned.
Antique Coppered.



C75.
BRASS BUTT HINGES
Sizes: 1", 1½", 1¾", 1⅞", 2", 2½", 3", 3½", 4".
Antique Butt Hinges (On Steel.)
Sizes: 1", 1½", 2", 2½", 3", 3½", 4".



C77.
STEEL BUTT HINGES
Sizes: 1", 1½", 1¾", 1⅞", 2", 2½", 3", 3½", 4", 5".



C85.
AMERICAN GATE HINGES
Self Closing.



C86.
STEEL PARLIAMENT HINGES
Sizes: 2½", 3", 3½", 4", 5", 6", 7".

HINGES




C68.
DOUBLE STRAP HINGES
Sizes: 3", 4", 6", 8", 10", 12".




C73.
ICE CHEST HINGES
Finish, Nickel Plated.




C69.
BRASS COUNTER HINGES
Sizes: 4" x 1½", 4½" x 2".




C74.
KITCHEN CABINET HINGE
Nickel Plated.




C70.
DOUBLE ACTING SPRING HINGES
For Doors to Swing Both Ways.
Japanned Finish



C81.
DOUBLE ACTION SPRING HINGES
For Doors to Swing Both Ways.
Finish, Florentine Bronze and Black Japanned.
Sizes: 3", 4", 5", 6", 7".



C82.
HALF SURFACE SPRING HINGES
Fits face of door and inside of frames where ordinary hinge will not suit.
Japanned Finish.



C83.
FANCY BACK FLAP HINGES
Finish, Antique Copper or Nickel Plated. Width overall, 2½" flush, and with ⅝" offset.



C87.
BUTTERFLY HINGES
Antique or Nickel Plated Finish.



C84.
FANCY BACK FLAP HINGES
Antique Copper or Nickel Plated.
Width overall: 1½".



C88.
HOOK AND EYE HINGES
Welded Eye Drive, Bolt or Screw.
Sizes: 12", 14", 16", 18", 20".




C89.
TRESTLE HINGES
Finish, Dull Black. Sizes: 8", 10", 12".

MARBLE AND TERAZZO LAVATORY DOOR FITTINGS

NICKEL OR CHROMIUM PLATED FINISH

C80.



This Set supplied complete with Fixing Bolts.
When ordering, specify whether to hold open or to close.

If the articles you require are not illustrated on these pages, please write to us stating your needs.

A LARGE ASSORTMENT OF THE LATEST FITTINGS CAN BE SEEN IN OUR SHOWROOM

PADLOCKS



C95.

"CRUSADER" PADLOCKS

Solid Brass Automatic Cylinder Lock with Nickel plated Steel Shackle. 2 Paracentric Keys.
Sizes: 1 1/2", 1 3/4", 2", 2 1/2".



C96.

GENUINE YALE PADLOCK

Solid Bronze. 2 Keys.
Sizes: 1", 1 1/4", 1 1/2", 1 3/4", 2", 2 1/2", 3".



C97.

CADMIUM PLATED 2 LEVER PADLOCKS

2 Keys. Sizes: 2", 2 1/4", 2 1/2".



C98.

RUSTLESS PADLOCKS

All working parts are rustless and specially suited to withstand sea air. 6 Levers and 2 specially hardened Keys.



C99.

"GREYHOUND" PADLOCKS

Sizes: 1 1/4", 1 1/2", 1 3/4".



C100. **"TIRELOCK" PADLOCKS**

Laminated Steel Case. 3" High Carbon Steel Shackle. 2 Levers. Size: 1 1/2".

Also "Bicycle Lock," with 7" Shackle.



C101.

LAMINATED STEEL PADLOCK


Sizes: 1-3/16", 1 1/4", 1 1/2".



C102.

LAMINATED STEEL PADLOCK


2 Keys. Size: 1-3/16".



C103.


YALE JUNIOR PADLOCK

One Piece Hammered Forged Steel Case. Cadmium plated Case. Hardened Shackle. 2 Keys. 1 1/4", 1 1/2" wide.



C104.


SLIDING SHACKLE PADLOCK
Galvanized Padlock, fitted with Hardened Steel Self closing Shackle. 2 Lever Keys. Sizes: 2", 2 1/4", 3".



C105.

SIX LEVER PADLOCK


Heavy Galvanized Steel Case. 2". 2 Keys.



C106.

YALE SEAMLESS AND RIVETLESS STEEL PADLOCKS

Sizes: 1 1/4", 2 1/4".



C107.

GATE CHAINS


Galvanized. 24", 30" long.



C110.

BRASS HASP AND STAPLE

Sizes: 5" x 2".



C111.

STEEL HASPS AND STAPLES

Galvanized and Black Japanned. Sizes: 8", 9".



C108.

GALVANIZED PAD BOLTS


To take Padlocks with Bolts.
8" x 4", 6", 1 1/2" x 6", 8", 10", 12", 8" x 8", 10", 12".



C112.

STEEL SAFETY HASPS

Wrought Straps, Screws or Bolts. Cannot be drawn out or cut when locked. Measurement of flaps: 3 1/2", 4 1/2", 6".



HASPS AND STAPLES - PAD. BOLTS ETC.



C109.

OVAL PLATE PAD BOLTS
Galvanized with 4" Bolt.



C113.

HASPS AND STAPLES

Japanned: 2 1/2", 3 1/2", 4", 5", 6".

Galvanized: 5", 6", 7".

Brass Hasps and Staples: 1 1/2", 2", 2 1/2".

ASK FOR ANY LINES NOT ILLUSTRATED

FASTENERS, BOLTS, ETC.




C118.

GOthic GATE LATCH
Dull Black Finish with Square Spindle
to go through Gate. Size: 8".



C121.

SURFACE GATE LATCHES



C124.

COLONIAL "D" LATCHES
Finish, Japanned and Galvanised.



C128.

IMPROVED "D" LATCHES
Stamped Steel
Japanned and Galvanised.



C131.

NORFOLK LATCHES
Wrought Japanned.



C139.

OFFICE CHAIR CASTORS
Finish, Electro., Brass and Chromium.
Size: 1 1/2", 2".



C140.

HOSPITAL CASTORS
Plain and also with Brake and Ball Bearing.
Sizes: 2", 2 1/2", 3", 4", 5"



C135.

TEA WAGON CASTOR
2" and 3".



C141.

TEA WAGON CASTOR
Size: 2".



C119.

SOLID BRONZE BOLTS
Finish, Flor. Bronze, Chromium Plated, and Satin Nickel.
3", 4", 6", 8", 10" long.



C122.

BARREL BOLTS
Antique on Brass. With Long Shoot.
Sizes: 2", 2 1/2", 3", 4", 6".



C125.

BRASS BARREL BOLT
(Necked Shoot.)
1/2" wide x 2 1/2", 3", 4".




C129.

CHAIN BOLTS
Japanned, 6", 8". Florentine, 6".



C132.

WROUGHT BAR STAPLES
Size: 2 1/2" wide for 3" x 2" Beams.
In a pair one staple has open top.



C136.

"SWIVLO" PLATE CASTORS
Ball Bearing.
Sizes: 1", 1 1/2", 1 3/4".



C142.

BALL CASTORS
Steel Ball runs in any direction and will not tear floor coverings.
Width overall: 1 1/2", 1 3/4", 1 7/8".



C143.

BALL BEARING SWIVEL CASTORS
With Semi-Steel Wheels.
Sizes: 2", 2 1/2", 3", 4", 5", 6".
With "Baco" Rubber Wheels.
Sizes: 2", 2 1/2", 3", 4", 5", 6".



C144.

CASTOR SOCKET
For Wood.



C145.

STATIONARY CASTORS
With Semi-Steel Wheels.
Sizes: 3", 4", 4 1/2", 6".
With "Baco" Rubber Wheels.
Sizes: 3", 4", 4 1/2", 6".



C120.

TOWER BOLTS
Black, Bright Bolts: 3", 4", 6", 8", 10", 12".
Galvanised: 3", 4", 6", 8", 10", 12".



C123.

PANIC BOLTS
As approved by Board of Health
12", 18", 24", 30", 36", 42", 48".

C126.
CARRIAGE DOOR OR BUDGET LOCK

Made to Mortice into Door or to Screw on Surface.
Depth of Lock: 1/2", 1", 1 1/2".



C127.

CUPBOARD BOLTS
Japanned, Brass, Nickel Plated.
Sizes: 2", 2 1/2", 3", 4".
Florentine Bronze: 1 1/2".




C130.

GATE SPRINGS
Japanned: 16", 18", 20".



C133.

FARM GATE CATCHES
The Knob and Ring Gate Catch cannot be opened by stock and is made to screw into post or bolt through as illustrated.
Japanned or Galvanised.



C134.

FLUSH BOLTS
For Cupboards.
Brass: 3", 4".
Heavier Type: 6", 8", 10", 12".



C137.

CASTOR SOCKET
For 1/2" Tubing.



C138.

DOMES OF SILENCE
A Castor for Chairs and Tables, etc.
In sets of four. 1/2", 5/8", 3/4", 1", 1 1/2".

CASTORS, ETC.

DANKS FOR ALL KINDS OF BUILDERS' HARDWARE

Sash Lifts, Fasteners, Openers, Etc.



C146.
BAR SASH LIFTS
Florentine Bronze, Nickel Plated.
Size: 2" x 3".




C147.
RING SASH LIFTS
Antique Finish.
Polished Brass.
Satin Nickel.



C148.
HOOK PATTERN SASH LIFTS
Antique Copper.
Nickel Plated.




C149.
SASH FASTENERS
Nickel Plated and Florentine
Finish on Steel. Also Brass.



C153.
COMBINATION CASEMENT STAYS
Combination Stay and Fastener. Does away
with the necessity of having a separate Fastener.
Antique Copper Finish. Steel and Brass.
Nickel Plated.



C150.
BEACON SASH LIFTS
Florentine and
Nickel Plated.




C151.
STAYLOCK WINDOW FASTENING
Florentine Bronze.



C154.
LOCKING SASH LIFTS
Florentine Bronze.




C155.
BUTTONS
Japanned: 1 1/2", 1 3/4", 2",
2 1/2", 2 3/4" Brass. 1 1/2" 2".




C156.
SASH WEIGHTS
From 2 lbs. up
to any weight
required.



C152.
PRESTON'S FANLIGHT OPENERS
The Most Efficient Type of Opener.
12", 15" and 18" Iron Screw. Cords to
Suit. 4' 6", 6', 8', 10' and 12' Drop



C157.
"CIRCLO" FANLIGHT OPENER
A Perfect Lock either
Open or Closed. Bronze
Finish. Complete with
4' 6" Double Cord and
Wood Grip Handles.



C158.
THE "OUVRO" EVERY-WAY OPENER



C159.
SASH PULLEYS
Stamped Steel.
Cast Iron and Bill
Bearings



C160.
CASEMENT FASTENERS
Antique Copper
Finish, plain
design, with
Mortice or
Hook Plate.



C161.
ALL BRASS SASH ROLLER
1 1/2" x 5" and 2" x 3".
Brass Wheel, Steel Plate.
Size: 1 1/2" x 5".


DANKS



C162.
SASH SCREWS
Brass Knob.
Steel Screw.
Sizes: 1/2" x 2",
3/4" x 3".



C164.
ROLLER
As used in con-
junction with
"Acme" Sash
Balances.



C163.
"ACME" SASH BALANCES
Standard Type.
(1) They consist of: (a) Watch
Spring; (b) Steel tape of 40 inches
length, rustproof, untwistable and
unbreakable; (c) Casing of electro-
galvanised rustproof steel.
(2) There are two types: (a) side installations for
standard use on the jamb; (b) overhead type for
narrow mullions.
(3) The "Acme" Sash Balance is manufactured in
seven ranges: 4 1/2, 6, 8, 10, 12, 14, 16 lbs.

WARDROBE FITTINGS, ETC.



C165.
WARDROBE CLOTHES HANGERS
These Expanding Hangers can support several Coat
Hangers and can be had in four sizes:
9", 12", 14", 16".
Also in Better Quality.



C167.
ROD SOCKETS
For 1/2", 3/4", 1" Rod
Electro. Brassed Finish.



C168.
"WARDRO" PUSH BUTTON CATCH
Bronze, Chromium or Nickel Plated.
Specially designed for large
Cupboards, Wardrobes, etc.




C166.
SLIDING ROD HOOKS
For Wardrobes.
Electro. Brassed Finish
for 1/2", 3/4" Rod.



C169.
REVOLVING WARDROBE HOOK
Florentine or
Nickel Plated.



C170.
CAST WARDROBE HOOK
Finished in Electro.
Brassed Oxidized
Copper, Nickel
Plated.



C171.
"EGRO" PUSH BUTTON CATCH
Florentine Chrome, Nickel Plated.
Specially designed for large Cupboards,
Wardrobes, etc

LET US QUOTE YOU FOR DISTINCTIVE FITTINGS FOR YOUR HOME

Hat and Coat Hooks, Etc., Mirror Fittings




C175.
COAT HOOK
 Finish, Florentine
 Bronze, Chromium
 and Nickelplated.



C176.
**DOUBLE WARDROBE
 HOOKS**
 Nickelplated and Florentine



C177.
**HAT AND
 COAT HOOKS**
 Finish, Florentine
 Bronze, Chromium
 and Nickelplated.




C178.
GLASS MOVEMENTS
 Capstan Pattern, with Lock Nut.
 Solid Brass.




C179.
HAT AND COAT HOOKS
 Small and Medium size.
 Finish, Florentine Bronze.


WE STOCK A
 LARGE
 AND VARIED
 ASSORTMENT
 OF HARDWARE
 FOR EVERY
 CLASS OF
 BUILDING.
 WRITE OR CALL
 FOR FURTHER
 DETAILS.



C182.
MIRROR ARMS
 Elbow Arms for Frameless
 Mirrors. Will hold in any
 desired position. Nickel-
 plated Finish.



C180.
GLASS PLATES
 Finish, Brass and
 Brassed
 1 1/2", 1 3/4", 1 7/8", 2".



C181.
MOVEMENTS
 Brassed for use on Mirrors.
 1 1/2".



C183.
NAME PLATES
 Finished in Brass and Copper.
 9 1/2" x 2 1/4" x 1" Letters.
 Any type or Design of Plate
 can be supplied.



C184.
NAME PLATES
 Solid Sheet Copper, mounted on Wood Back. Oxidised Finish.



C185.
ENAMELLED SIGNS
 Sizes: 6" x 1 1/2".

In the following:—Letters. Ladies' Bathroom. Ladies' Cloak-
 room. Manager. No Admittance. No Hawkers or Canvassers.
 No Smoking. Please Enter. Please Knock. Please Open.
 Please Ring. Please Shut the Gate. Private. Private Entrance.
 Public Telephone. Pull. Push. Side Entrance. Back
 Entrance. Bar. Bathroom. Ladies. Caretaker. Cashier.
 Cloak Room. Dining Room. Enter. Enter Without Knocking.
 Gentlemen. Gentlemen's Bathroom. Gentlemen's Cloak Room
 Inquiries. Lavatory. Tradesmen. Letters. Please Close.
 Please Shut the Door.



C186.
**HOUSE
 NUMBERS**
 Brass, 2" high.

Finish,
 Polished
 Brass,
 Florentine
 Bronze,
 Chromium
 Plated.

C187.
**Enamelled
 House
 Numbers**




Any Number
 can be
 Supplied.

MAY ALSO BE HAD IN COLOURED
 BAKELITE—WHITE, WALNUT, PRIMROSE.
 Size, 2".

Finish,
 Florentine
 Bronze,
 Chromium
 Plated,
 Hammered,
 Mission,
 Satin Nickel



C188.
**HOUSE
 NUMBERS**
 Cast Brass.



C189.
MIRROR AND GLASS CLIPS
 Nickelplated Finish.

A.—Side.
 AB.—Side, Large.
 AL.—Side, Short.
 B.—Corner, for Inside Mirrors.
 C.—Side, for Inside Mirrors.
 D.—Corner, for Outside Mirrors.


E.—Side, for Outside Mirrors.
 F.—Large Corner, for Inside Mirrors.
 G.—Large Side, for Inside Mirrors.
 H.—Large Corner, for Outside Mirrors.
 J.—Side, Heavy, Extra Wide.

Abbreviations Used:—
 A.B., Antique Brass Finish.
 E.B., Electro-brassed Finish.
 F.B., Florentine Bronze Finish.


A.C., Oxidised Copper Finish.
 N.P., Nickelplated Finish.
 P.B., Polished Brass Finish.

WE CARRY A LARGE ASSORTMENT OF HIGH QUALITY HARDWARE

CABINET HANDLES, CATCHES, ETC.




C191.
Cabinet Handles
Antique Finish on Solid Brass.
Small and Medium Sizes.
Pedestal to match.



C192
Cabinet Handles
Drop Pattern, finished in Antique
Copper.
Small and Medium Size.
Cupboard Turns and Pedestal Handles
to match.




C205.
Ice Chest Lever Catch
Nickel Plated.




C207.
Ice Chest Roller Catch
Improved Type, Nickel Plated.
Lighter Catch for Kitchen Cabinet,
nickel plated.



C214.
**Kitchen
Cabinet Catch**
Right or Left Hand.
Nickel plated.
For flush or offset
doors.




C193.
Made in Bakelite
Colours: Red, Cream, Green,
Light Green, Natural.
Sizes: 1 1/2", 2 1/2".



C196.
Nickel Plated on Solid Brass
Sizes: 3", 4".



C199.
Nickel Plated on Solid Brass
With Red, Green or Natural Inserts
Sizes: 3, 4 1/2".



C206.
**Push Button Cupboard
Catches**
Florentine and Nickel Plated, and
Chrome on Iron and Brass.
Also Various in Bakelite



C208.
Handrail Bracket
Japanned Steel
3", 3 1/2" projection.
Also Brass in Various
Colours.




C209.
**Shutter
Knobs**
Brass, Antique
Nickel Plated.
3/4", 1", 1 1/4",
1 1/2", 1 3/4", dia.



C215.
Flat Corner Irons
Made of Flat Bright Steel
with countersunk screw
holes.
2 1/2" x 2 1/2", 3" x 3",
3 1/2" x 3 1/2", 4" x 4".



C216.
**Corner
Brackets**
Made of Flat Bright
Steel.
1 1/2" x 1 1/2", 2" x 2",
3" x 3", 4" x 4".



C194.
Made in Bakelite with 2 Nickel Strips
Colours: Red, Blue, Black, Light Green,
Natural.
Sizes: 3 1/2", 5".



C197.
Made in Bakelite with Nickel Strip
Colours: Red, Blue, Black, Cream,
Light Green, Natural.
Sizes: 3 1/2", 5".



C198.
Solid Brass Handles
Finished in Chrome Plate.
Florentine Bronze or Satin Nickel
Sizes: 3", 4".



C203.
Stamped Card Pull
Takes cards 2 1/2" x 1 1/2".




C204.
Stamped Card Frame
Takes cards 2 1/2" x 1 1/2".




C210.
**Spring
Gripper
Catch**



C213.
Elbow Catch
Nickel Plated and
Steel.



C211.
Cupboard Turns
Antique Knob.
3/4", 1", 1 1/2", 1 3/4" diam.
Also Polished Brass.



C212.
**Pressed Steel
Box Handles**
Japanned
3 1/2", 3 3/4", 4".




C217.
Shelf Brackets
Tinned—3" x 2", 4" x 3", 5" x 4", 6" x 5",
8" x 6", 10" x 8".
Japanned steel, stamped in one piece, un-
breakable—3" x 4", 4" x 5", 5" x 6",
6" x 8", 7" x 9", 8" x 10", 10" x 12",
12" x 14". Also with Stay.
Folding Type Brackets
Japanned Finish
Size: 8" x 8" and 12" x 12"



C218.
Flush Rings
Japanned
Size: 3 1/2" x 3 1/2"

THE QUALITY IS REMEMBERED LONG AFTER THE PRICE IS FORGOTTEN


Curtain and Picture Fittings, Etc.



C220.
CURTAIN ROD BRACKETS
Brass Plated, Single, 3"-4".
Double and Treble, for Curtain and Valance.



C221.
SIDE HOOKS
AND EYES
Solid Brass.
Sizes: 3", 1", 1 1/2",
1 1/4" and 2".
In Pairs.




C222.
CURTAIN RODS
Plain Pattern, Brass Finish. Extending
Pattern from 24" to 46", with Knobs
Hooks and Brackets.



C223.
EXPANDING CURTAIN ROD
Strong, Rustless Coiled Spring. Adjustable to
any width required. Can be fixed to any
tension. Hook ends. Cut to any length
specified. Supplied with screw eyes to fit.




C224.
BRASS CURTAIN RINGS
Sizes: 1", 1 1/2", 1 3/4", 1 1/2", 1 3/4", 2".



C225.
CURTAIN ROD BRACKETS
For use with Brass-cased
Tube. Solid Brass.
Sizes: 1", 1 1/2", 1 3/4" and 2", 1".



C226.
SPEAR ENDS
For Curtain Rods.
Sizes: 1", 1 1/2", 1 3/4",
Nickelplated, Electro-Brassed
and Antique Copper Finishes.



C227.
BRASS-CASED TUBE
Diameter: 1", 1 1/2", 1 3/4", 2", 1 1/2".

C228.
PICTURE WIRE
Gilt, in 25 ft. coils. Best
make. Light, Medium and
Heavy.



C240.
COT FITTINGS
For Drop-side Cots. Consist of
two Long Rails and Fittings as
illustrated. Oxidised Finish.



C229.
PICTURE MOULDING
HOOKS
Fancy Antique Design.
Also Brassed.



C230.
PICTURE HOOKS
Plain Brass, with
Nails. Also A.C.



C231.
BRASS
PICTURE
HANGERS
Does not damage
walls. Single Pin,
Small and
Medium;
also Double
Pin, Large.



C232.
ESCUTCHEON
PLATES
Finished in
Brass,
Florentine.
Antique Copper
and Nickel-
plated.



C233.
BRASS CUP HOOKS
(Round.) Sizes: 1", 1 1/2", 1 3/4",
1 1/2", 1 3/4", 2".



C239.
PICTURE
MOULDING
HOOKS
Antique Coppered
and Brassed.



C238.
PICTURE
HOOKS
Complete with
Nails.
Large Range of
Patterns.



C237.
CARPET PINS AND
SOCKETS
Solid Brass. Used for
keeping down Carpet Ends.
Sizes: 1 1/2", 2".




C235.
HOOKS AND EYES
Bright. 1 1/2", 2", 2 1/2", 3", 4", 5", 6", 8", 10", 12".



C236.
BRASS CABIN HOOKS
Sizes: 2 1/2", 3", 3 1/2", 4", 5", 6", 8".



C244.
DUST ARRESTERS
Prevent Dust and Draught from coming
under Doors. Automatically lift as Door
is opened and swings clear of Carpet.
Antique Finish, also Wood with Brass Ends;
also Florentine, Polished Brass and Painted.
Specify Width of Door When Ordering



C241.
BEDSTEAD FITTINGS
These fit direct to Mattress and Post,
making Side Rails unnecessary.
Sold in Sets of 4



C242.
LETTER BOXES
Made of Galvanised
Iron, Hinged Lid
at top, with Hasp
and Staple to take
Padlock.



C243.
BRASS CARPET ENDS
Made of Polished Brass and
folds over ends of Carpets.
2" wide x 22 1/2", 24", 27", 30",
36" long.

"DORSEAL" SQUEEGEE DRAUGHT EXCLUDER

For the Bottoms of Doors.
Steel Lined, Rubber Coated
Suedette covered. Simply
fixed on the bottom of Door.
Flexible Strip allows free
movement over Carpets.

GIVE US A TRIAL—SATISFACTION GUARANTEED


PULLEYS, BLOCKS, ETC




C245.
WESTON'S
DIFFERENTIAL
PULLEY BLOCKS
Supplied with
40 ft. of Chain to
lift 10 foot capa-
city. 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100.



C253.
SIDE PULLEYS
Single: 1/2", 1", 1 1/2", 2", 3", 4", 5", 6", 7", 8", 9", 10", 11", 12", 13", 14", 15", 16", 17", 18", 19", 20", 21", 22", 23", 24", 25", 26", 27", 28", 29", 30", 31", 32", 33", 34", 35", 36", 37", 38", 39", 40", 41", 42", 43", 44", 45", 46", 47", 48", 49, 50.



C254.
GALVANISED STEEL FLEXIBLE
WIRE ROPE
Composed of 6 Strands.
Diameter: 1/8", 1/4", 3/8", 1/2", 5/8", 3/4", 7/8", 1", 1 1/8", 1 1/4", 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2", 2 3/4", 3", 3 1/4", 3 1/2", 3 3/4", 4", 4 1/4", 4 1/2", 4 3/4", 5", 5 1/4", 5 1/2", 5 3/4", 6", 6 1/4", 6 1/2", 6 3/4", 7", 7 1/4", 7 1/2", 7 3/4", 8", 8 1/4", 8 1/2", 8 3/4", 9", 9 1/4", 9 1/2", 9 3/4", 10", 10 1/4", 10 1/2", 10 3/4", 11", 11 1/4", 11 1/2", 11 3/4", 12", 12 1/4", 12 1/2", 12 3/4", 13", 13 1/4", 13 1/2", 13 3/4", 14", 14 1/4", 14 1/2", 14 3/4", 15", 15 1/4", 15 1/2", 15 3/4", 16", 16 1/4", 16 1/2", 16 3/4", 17", 17 1/4", 17 1/2", 17 3/4", 18", 18 1/4", 18 1/2", 18 3/4", 19", 19 1/4", 19 1/2", 19 3/4", 20", 20 1/4", 20 1/2", 20 3/4", 21", 21 1/4", 21 1/2", 21 3/4", 22", 22 1/4", 22 1/2", 22 3/4", 23", 23 1/4", 23 1/2", 23 3/4", 24", 24 1/4", 24 1/2", 24 3/4", 25", 25 1/4", 25 1/2", 25 3/4", 26", 26 1/4", 26 1/2", 26 3/4", 27", 27 1/4", 27 1/2", 27 3/4", 28", 28 1/4", 28 1/2", 28 3/4", 29", 29 1/4", 29 1/2", 29 3/4", 30", 30 1/4", 30 1/2", 30 3/4", 31", 31 1/4", 31 1/2", 31 3/4", 32", 32 1/4", 32 1/2", 32 3/4", 33", 33 1/4", 33 1/2", 33 3/4", 34", 34 1/4", 34 1/2", 34 3/4", 35", 35 1/4", 35 1/2", 35 3/4", 36", 36 1/4", 36 1/2", 36 3/4", 37", 37 1/4", 37 1/2", 37 3/4", 38", 38 1/4", 38 1/2", 38 3/4", 39", 39 1/4", 39 1/2", 39 3/4", 40", 40 1/4", 40 1/2", 40 3/4", 41", 41 1/4", 41 1/2", 41 3/4", 42", 42 1/4", 42 1/2", 42 3/4", 43", 43 1/4", 43 1/2", 43 3/4", 44", 44 1/4", 44 1/2", 44 3/4", 45", 45 1/4", 45 1/2", 45 3/4", 46", 46 1/4", 46 1/2", 46 3/4", 47", 47 1/4", 47 1/2", 47 3/4", 48", 48 1/4", 48 1/2", 48 3/4", 49", 49 1/4", 49 1/2", 49 3/4", 50", 50 1/4", 50 1/2", 50 3/4", 51", 51 1/4", 51 1/2", 51 3/4", 52", 52 1/4", 52 1/2", 52 3/4", 53", 53 1/4", 53 1/2", 53 3/4", 54", 54 1/4", 54 1/2", 54 3/4", 55", 55 1/4", 55 1/2", 55 3/4", 56", 56 1/4", 56 1/2", 56 3/4", 57", 57 1/4", 57 1/2", 57 3/4", 58", 58 1/4", 58 1/2", 58 3/4", 59", 59 1/4", 59 1/2", 59 3/4", 60", 60 1/4", 60 1/2", 60 3/4", 61", 61 1/4", 61 1/2", 61 3/4", 62", 62 1/4", 62 1/2", 62 3/4", 63", 63 1/4", 63 1/2", 63 3/4", 64", 64 1/4", 64 1/2", 64 3/4", 65", 65 1/4", 65 1/2", 65 3/4", 66", 66 1/4", 66 1/2", 66 3/4", 67", 67 1/4", 67 1/2", 67 3/4", 68", 68 1/4", 68 1/2", 68 3/4", 69", 69 1/4", 69 1/2", 69 3/4", 70", 70 1/4", 70 1/2", 70 3/4", 71", 71 1/4", 71 1/2", 71 3/4", 72", 72 1/4", 72 1/2", 72 3/4", 73", 73 1/4", 73 1/2", 73 3/4", 74", 74 1/4", 74 1/2", 74 3/4", 75", 75 1/4", 75 1/2", 75 3/4", 76", 76 1/4", 76 1/2", 76 3/4", 77", 77 1/4", 77 1/2", 77 3/4", 78", 78 1/4", 78 1/2", 78 3/4", 79", 79 1/4", 79 1/2", 79 3/4", 80", 80 1/4", 80 1/2", 80 3/4", 81", 81 1/4", 81 1/2", 81 3/4", 82", 82 1/4", 82 1/2", 82 3/4", 83", 83 1/4", 83 1/2", 83 3/4", 84", 84 1/4", 84 1/2", 84 3/4", 85", 85 1/4", 85 1/2", 85 3/4", 86", 86 1/4", 86 1/2", 86 3/4", 87", 87 1/4", 87 1/2", 87 3/4", 88", 88 1/4", 88 1/2", 88 3/4", 89", 89 1/4", 89 1/2", 89 3/4", 90", 90 1/4", 90 1/2", 90 3/4", 91", 91 1/4", 91 1/2", 91 3/4", 92", 92 1/4", 92 1/2", 92 3/4", 93", 93 1/4", 93 1/2", 93 3/4", 94", 94 1/4", 94 1/2", 94 3/4", 95", 95 1/4", 95 1/2", 95 3/4", 96", 96 1/4", 96 1/2", 96 3/4", 97", 97 1/4", 97 1/2", 97 3/4", 98", 98 1/4", 98 1/2", 98 3/4", 99", 99 1/4", 99 1/2", 99 3/4", 100", 100 1/4", 100 1/2", 100 3/4, 101, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200.



C258.
WROUGHT TACKLE PULLEYS
For Manila Rope. Very strongly made for heavy work. In Single, Double and Treble. Sheaves: 2 1/2", 3", 3 1/2", 4", 4 1/2", 5", 6". Suit Rope Circumference: 1 1/2", 1 3/4", 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2".




C246.
DOOR SHEAVES
Of best quality Wrought Steel, with Hardened Steel Ball-bearings. No. 1 size for ordinary Showcase, Doors, etc. Case is 1 1/8" thick. No. 2 size for Heavy Doors. Case is 3/4" thick.



C247.
STEEL TRACK
Copper Coated, in 10 ft lengths. Made for use with Door Sheaves.



C248.
FORGED SHACKLES
Sizes: 1/2", 5/8", 3/4", 7/8", 1", 1 1/8", 1 1/4", 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2", 2 3/4", 3", 3 1/4", 3 1/2", 3 3/4", 4", 4 1/4", 4 1/2", 4 3/4", 5", 5 1/4", 5 1/2", 5 3/4", 6", 6 1/4", 6 1/2", 6 3/4", 7", 7 1/4", 7 1/2", 7 3/4", 8", 8 1/4", 8 1/2", 8 3/4", 9", 9 1/4", 9 1/2", 9 3/4", 10", 10 1/4", 10 1/2", 10 3/4", 11", 11 1/4", 11 1/2", 11 3/4", 12", 12 1/4", 12 1/2", 12 3/4", 13", 13 1/4", 13 1/2", 13 3/4", 14", 14 1/4", 14 1/2", 14 3/4", 15", 15 1/4", 15 1/2", 15 3/4", 16", 16 1/4", 16 1/2", 16 3/4", 17", 17 1/4", 17 1/2", 17 3/4", 18", 18 1/4", 18 1/2", 18 3/4", 19", 19 1/4", 19 1/2", 19 3/4", 20", 20 1/4", 20 1/2", 20 3/4", 21", 21 1/4", 21 1/2", 21 3/4", 22", 22 1/4", 22 1/2", 22 3/4", 23", 23 1/4", 23 1/2", 23 3/4", 24", 24 1/4", 24 1/2", 24 3/4", 25", 25 1/4", 25 1/2", 25 3/4", 26", 26 1/4", 26 1/2", 26 3/4", 27", 27 1/4", 27 1/2", 27 3/4", 28", 28 1/4", 28 1/2", 28 3/4", 29", 29 1/4", 29 1/2", 29 3/4", 30", 30 1/4", 30 1/2", 30 3/4", 31", 31 1/4", 31 1/2", 31 3/4", 32", 32 1/4", 32 1/2", 32 3/4", 33", 33 1/4", 33 1/2", 33 3/4", 34", 34 1/4", 34 1/2", 34 3/4", 35", 35 1/4", 35 1/2", 35 3/4", 36", 36 1/4", 36 1/2", 36 3/4", 37", 37 1/4", 37 1/2", 37 3/4", 38", 38 1/4", 38 1/2", 38 3/4", 39", 39 1/4", 39 1/2", 39 3/4", 40", 40 1/4", 40 1/2", 40 3/4", 41", 41 1/4", 41 1/2", 41 3/4", 42", 42 1/4", 42 1/2", 42 3/4", 43", 43 1/4", 43 1/2", 43 3/4", 44", 44 1/4", 44 1/2", 44 3/4", 45", 45 1/4", 45 1/2", 45 3/4", 46", 46 1/4", 46 1/2", 46 3/4", 47", 47 1/4", 47 1/2", 47 3/4", 48", 48 1/4", 48 1/2", 48 3/4", 49", 49 1/4", 49 1/2", 49 3/4", 50", 50 1/4", 50 1/2", 50 3/4", 51", 51 1/4", 51 1/2", 51 3/4", 52", 52 1/4", 52 1/2", 52 3/4", 53", 53 1/4", 53 1/2", 53 3/4", 54", 54 1/4", 54 1/2", 54 3/4", 55", 55 1/4", 55 1/2", 55 3/4", 56", 56 1/4", 56 1/2", 56 3/4", 57", 57 1/4", 57 1/2", 57 3/4", 58", 58 1/4", 58 1/2", 58 3/4", 59", 59 1/4", 59 1/2", 59 3/4", 60", 60 1/4", 60 1/2", 60 3/4", 61", 61 1/4", 61 1/2", 61 3/4", 62", 62 1/4", 62 1/2", 62 3/4", 63", 63 1/4", 63 1/2", 63 3/4", 64", 64 1/4", 64 1/2", 64 3/4", 65", 65 1/4", 65 1/2", 65 3/4", 66", 66 1/4", 66 1/2", 66 3/4", 67", 67 1/4", 67 1/2", 67 3/4", 68", 68 1/4", 68 1/2", 68 3/4", 69", 69 1/4", 69 1/2", 69 3/4", 70", 70 1/4", 70 1/2", 70 3/4", 71", 71 1/4", 71 1/2", 71 3/4", 72", 72 1/4", 72 1/2", 72 3/4", 73", 73 1/4", 73 1/2", 73 3/4", 74", 74 1/4", 74 1/2", 74 3/4", 75", 75 1/4", 75 1/2", 75 3/4", 76", 76 1/4", 76 1/2", 76 3/4", 77", 77 1/4", 77 1/2", 77 3/4", 78", 78 1/4", 78 1/2", 78 3/4", 79", 79 1/4", 79 1/2", 79 3/4", 80", 80 1/4", 80 1/2", 80 3/4", 81", 81 1/4", 81 1/2", 81 3/4", 82", 82 1/4", 82 1/2", 82 3/4", 83", 83 1/4", 83 1/2", 83 3/4", 84", 84 1/4", 84 1/2", 84 3/4", 85", 85 1/4", 85 1/2", 85 3/4", 86", 86 1/4", 86 1/2", 86 3/4", 87", 87 1/4", 87 1/2", 87 3/4", 88", 88 1/4", 88 1/2", 88 3/4", 89", 89 1/4", 89 1/2", 89 3/4", 90", 90 1/4", 90 1/2", 90 3/4", 91", 91 1/4", 91 1/2", 91 3/4", 92", 92 1/4", 92 1/2", 92 3/4", 93", 93 1/4", 93 1/2", 93 3/4", 94", 94 1/4", 94 1/2", 94 3/4", 95", 95 1/4", 95 1/2", 95 3/4", 96", 96 1/4", 96 1/2", 96 3/4", 97", 97 1/4", 97 1/2", 97 3/4", 98", 98 1/4", 98 1/2", 98 3/4", 99", 99 1/4", 99 1/2", 99 3/4", 100", 100 1/4", 100 1/2", 100 3/4, 101, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200.



C249.
WIRE ROPE CLIPS
To suit Rope.
Diam. 5/16", 3/8", 1/2", 5/8", 3/4", 7/8", 1", 1 1/8", 1 1/4", 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2", 2 3/4", 3", 3 1/4", 3 1/2", 3 3/4", 4", 4 1/4", 4 1/2", 4 3/4", 5", 5 1/4", 5 1/2", 5 3/4", 6", 6 1/4", 6 1/2", 6 3/4", 7", 7 1/4", 7 1/2", 7 3/4", 8", 8 1/4", 8 1/2", 8 3/4", 9", 9 1/4", 9 1/2", 9 3/4", 10", 10 1/4", 10 1/2", 10 3/4", 11", 11 1/4", 11 1/2", 11 3/4", 12", 12 1/4", 12 1/2", 12 3/4", 13", 13 1/4", 13 1/2", 13 3/4", 14", 14 1/4", 14 1/2", 14 3/4", 15", 15 1/4", 15 1/2", 15 3/4", 16", 16 1/4", 16 1/2", 16 3/4", 17", 17 1/4", 17 1/2", 17 3/4", 18", 18 1/4", 18 1/2", 18 3/4", 19", 19 1/4", 19 1/2", 19 3/4", 20", 20 1/4", 20 1/2", 20 3/4", 21", 21 1/4", 21 1/2", 21 3/4", 22", 22 1/4", 22 1/2", 22 3/4", 23", 23 1/4", 23 1/2", 23 3/4", 24", 24 1/4", 24 1/2", 24 3/4", 25", 25 1/4", 25 1/2", 25 3/4", 26", 26 1/4", 26 1/2", 26 3/4", 27", 27 1/4", 27 1/2", 27 3/4", 28", 28 1/4", 28 1/2", 28 3/4", 29", 29 1/4", 29 1/2", 29 3/4", 30", 30 1/4", 30 1/2", 30 3/4", 31", 31 1/4", 31 1/2", 31 3/4", 32", 32 1/4", 32 1/2", 32 3/4", 33", 33 1/4", 33 1/2", 33 3/4", 34", 34 1/4", 34 1/2", 34 3/4", 35", 35 1/4", 35 1/2", 35 3/4", 36", 36 1/4", 36 1/2", 36 3/4", 37", 37 1/4", 37 1/2", 37 3/4", 38", 38 1/4", 38 1/2", 38 3/4", 39", 39 1/4", 39 1/2", 39 3/4", 40", 40 1/4", 40 1/2", 40 3/4", 41", 41 1/4", 41 1/2", 41 3/4", 42", 42 1/4", 42 1/2", 42 3/4", 43", 43 1/4", 43 1/2", 43 3/4", 44", 44 1/4", 44 1/2", 44 3/4", 45", 45 1/4", 45 1/2", 45 3/4", 46", 46 1/4", 46 1/2", 46 3/4", 47", 47 1/4", 47 1/2", 47 3/4", 48", 48 1/4", 48 1/2", 48 3/4", 49", 49 1/4", 49 1/2", 49 3/4", 50", 50 1/4", 50 1/2", 50 3/4, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100.



C250.
BARN DOOR HANGERS
For hanging Barn Door from overhead runners. 4", 5", 6", 7", 8", 9", 10", 11", 12", 13", 14", 15", 16", 17", 18", 19", 20", 21", 22", 23", 24", 25", 26", 27", 28", 29", 30", 31", 32", 33", 34", 35", 36", 37", 38", 39", 40", 41", 42", 43", 44", 45", 46", 47", 48", 49, 50.



C251.
CLOTHES LINE PULLEYS
Galvanised
Complete with Hooks or Pulleys only



C255.
CLEAT HOOKS
Japanned: 3", 4", 5", 6".
Galvanised: 4", 5", 6".
Brass: 2 1/2", 3", 3 1/2", 4".



C256.
ROPE THIMBLES (GALVANISED)
Heart Shape.
Width: 1", 1 1/4", 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2", 2 3/4", 3", 3 1/4", 3 1/2", 3 3/4", 4", 4 1/4", 4 1/2", 4 3/4", 5", 5 1/4", 5 1/2", 5 3/4", 6", 6 1/4", 6 1/2", 6 3/4", 7", 7 1/4", 7 1/2", 7 3/4", 8", 8 1/4", 8 1/2", 8 3/4", 9", 9 1/4", 9 1/2", 9 3/4", 10", 10 1/4", 10 1/2", 10 3/4", 11", 11 1/4", 11 1/2", 11 3/4", 12", 12 1/4", 12 1/2", 12 3/4", 13", 13 1/4", 13 1/2", 13 3/4", 14", 14 1/4", 14 1/2", 14 3/4", 15", 15 1/4", 15 1/2", 15 3/4", 16", 16 1/4", 16 1/2", 16 3/4", 17", 17 1/4", 17 1/2", 17 3/4", 18", 18 1/4", 18 1/2", 18 3/4", 19", 19 1/4", 19 1/2", 19 3/4", 20", 20 1/4", 20 1/2", 20 3/4, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50.

To suit Diam. Rope: 5/16", 3/8", 7/16", 1/2", 5/8", 3/4", 7/8", 1", 1 1/8", 1 1/4", 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2", 2 3/4", 3", 3 1/4", 3 1/2", 3 3/4", 4", 4 1/4", 4 1/2", 4 3/4", 5", 5 1/4", 5 1/2", 5 3/4", 6", 6 1/4", 6 1/2", 6 3/4", 7", 7 1/4", 7 1/2", 7 3/4", 8", 8 1/4", 8 1/2", 8 3/4", 9", 9 1/4", 9 1/2", 9 3/4", 10", 10 1/4", 10 1/2", 10 3/4, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50.




C257.
BARN DOOR ROLLERS
Diam. of Wheel: 4", 5", 6", 8"



C259.
AWNING PULLEYS
Japanned. Single: 1", 1 1/4", 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2", 2 3/4", 3", 3 1/4", 3 1/2", 3 3/4", 4", 4 1/4", 4 1/2", 4 3/4", 5", 5 1/4", 5 1/2", 5 3/4", 6", 6 1/4", 6 1/2", 6 3/4", 7", 7 1/4", 7 1/2", 7 3/4", 8", 8 1/4", 8 1/2", 8 3/4", 9", 9 1/4", 9 1/2", 9 3/4", 10", 10 1/4", 10 1/2", 10 3/4, 11, 12, 13, 14, 15, 16,

BOLTS, SCREWS, NAILS

NAILS
 Etc.

GALVANISED WIRE CLOTHES LINES
 7 Strand, in 50 and 100 ft. Coils.


C271.

"ACME" CLOTHES HOIST


This hoist does away with unsightly clothes props and is quite simple to work.

Is well made, and of such strength that it may be used to hoist farm produce, such as a bag of wheat or chaff, or a slaughtered sheep.

C272.

Steel Wire Brads

Sizes: $\frac{1}{4}$ ", $\frac{3}{8}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", $1\frac{3}{4}$ ", 2", $2\frac{1}{4}$ ", $2\frac{1}{2}$ ".
 In varying gauges from 14, 15, 16, 17, 18, 19, 20.



C273.

STRAINING SCREWS

For use on Guys of Wireless Masts. Slackness can be instantly taken up. Size of Screw: $\frac{3}{4}$ ", $\frac{5}{16}$ ", $\frac{3}{8}$ ", $\frac{7}{16}$ ", $\frac{1}{2}$ ", $\frac{5}{8}$ ", $\frac{3}{4}$ ".

C274.

Clout Tacks


Bright or Galvanised. $\frac{3}{8}$ ", $\frac{1}{2}$ ", $\frac{5}{8}$ ", $\frac{3}{4}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ".



C277.

Dowell Screws

2" x 12 gauge.
 $2\frac{1}{2}$ " x 12, 14 gauge.
 1" x 7, $1\frac{1}{4}$ " x 9, $1\frac{1}{2}$ " x 10.



C278.

Wirenails

Flat Heads $\frac{3}{4}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", $1\frac{3}{4}$ ", 2", $2\frac{1}{4}$ ", 3".
 Bullet Heads 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", $1\frac{3}{4}$ ", 2", $2\frac{1}{4}$ ", 3", $3\frac{1}{4}$ ", 4", 5", 6".

C282.

Floor Brads

Oval 2", $2\frac{1}{4}$ ", $2\frac{1}{2}$ ".



C287.

Deck Spikes

For bridge building, etc. $\frac{3}{4}$ " x 5", 6", 7", $\frac{7}{16}$ " x 8".



C293.

Screw Eyes

(Bright)

No. 1, 2, 3, 4, 5, 6, 8, 10, 12, 14, 16, 18, 20.

C270.

"AUSTRAL" ROTARY CLOTHES HOISTS

Ideal for Small Yards or Roofs of Flats

120 ft. of line in 16 ft. diameter.

170 ft. of line in 20 ft. diameter.

Erection free and at your convenience in the Metropolitan Area.



C275.

Stove Screws and Nuts

Countersunk Heads. $\frac{1}{4}$ " to 2" x $\frac{3}{8}$ " dia. $\frac{1}{4}$ " to 2" x $\frac{5}{16}$ " dia. $\frac{1}{4}$ " to 3" x $\frac{3}{16}$ " dia. $\frac{1}{4}$ " to 3" x $\frac{1}{2}$ " dia. $\frac{1}{4}$ " to 3" x $\frac{5}{16}$ " dia. $\frac{1}{4}$ " to 3" x $\frac{3}{4}$ " dia.



C283.

Stove Screws and Nuts

Round Heads. $\frac{1}{4}$ " to 2" x $\frac{3}{8}$ " dia. $\frac{1}{4}$ " to 2" x $\frac{5}{16}$ " dia. $\frac{1}{4}$ " to 3" x $\frac{3}{16}$ " dia. $\frac{1}{4}$ " to 3" x $\frac{1}{2}$ " dia. $\frac{1}{4}$ " to 3" x $\frac{5}{16}$ " dia. $\frac{1}{4}$ " to 3" x $\frac{3}{4}$ " dia.



C288.

Plough Bolts and Nuts

In various types. Square or Round Neck or with Nib.



C276.

Tyre Bolts


$\frac{1}{4}$ " x 2", $2\frac{1}{4}$ ", $2\frac{1}{2}$ ", $2\frac{3}{4}$ ", 3".



C279.

Engineers' Nuts and Bolts

Lengths $\frac{3}{4}$ " up to 24". Up to $3\frac{3}{4}$ " in $\frac{1}{4}$ " rises. Up to 12" in $\frac{1}{2}$ " rises. Then on in 1" rises. Diameter $\frac{1}{4}$ " to 1".



C284.

Coach Bolts and Nuts

Lengths $\frac{3}{4}$ " up to 24". Up to $3\frac{3}{4}$ " in $\frac{1}{4}$ " rises. Up to 12" in $\frac{1}{2}$ " rises. Then on in 1" rises. Diameter $\frac{3}{16}$ " to 1".



C289.

Coach Screws

$\frac{1}{4}$ " x $1\frac{1}{2}$ ", 2", $2\frac{1}{4}$ ", 3", $3\frac{1}{2}$ ", 4". $\frac{5}{16}$ " x $1\frac{1}{2}$ ", 2", $2\frac{1}{4}$ ", 3", $3\frac{1}{2}$ ", 4". $\frac{3}{8}$ " x $1\frac{1}{2}$ ", 2", $2\frac{1}{4}$ ", 3", $3\frac{1}{2}$ ", 4". $\frac{1}{2}$ " x 2", $2\frac{1}{4}$ ", 3", $3\frac{1}{2}$ ", 4", $4\frac{1}{2}$ ", 5", 6".



C280.

Set Screws

Hexagon Heads.

Sizes: $\frac{1}{4}$ " x $\frac{3}{8}$ ", $\frac{3}{8}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2". $\frac{5}{16}$ " x $\frac{3}{8}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2". $\frac{3}{8}$ " x $\frac{3}{8}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2". $\frac{1}{2}$ " x 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2".



C285.

Nuts

(Square)

Tapped ready for use $\frac{3}{16}$ ", $\frac{1}{4}$ ", $\frac{5}{16}$ ", $\frac{3}{8}$ ", $\frac{7}{16}$ ", 3", $\frac{1}{2}$ ", $\frac{3}{4}$ ", 1".

C290.

Handrail Screws

4", $4\frac{1}{2}$ ", 5" and 6" x $\frac{1}{2}$ ".

C291.

Eye Bolts and Nuts

Sizes:

$\frac{3}{8}$ " x $1\frac{1}{2}$ " to 6". $\frac{5}{16}$ " x $1\frac{1}{2}$ " to 6". $\frac{3}{8}$ " x $1\frac{1}{2}$ " to 6". $\frac{1}{2}$ " and $\frac{3}{4}$ " x 3" to 6". Special Sizes can be Made to Order.



C281.

Wing Nuts

IRON

Tapped ready for use.

Sizes:

$\frac{3}{16}$ ", $\frac{1}{4}$ ", $\frac{5}{16}$ ", $\frac{3}{8}$ ", $\frac{7}{16}$ ", $\frac{1}{2}$ ", $\frac{5}{8}$ ".



C286.

Hexagon Nuts

Sizes:

$\frac{5}{16}$ ", $\frac{1}{4}$ ", $\frac{5}{16}$ ", $\frac{3}{8}$ ", $\frac{7}{16}$ ", $\frac{1}{2}$ ".



C292.

Iron Washers

$\frac{3}{8}$ ", $\frac{5}{16}$ ", $\frac{3}{8}$ ", $\frac{7}{16}$ ", $\frac{1}{2}$ ", $\frac{5}{8}$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ", $\frac{5}{16}$ ", $\frac{3}{8}$ ", $\frac{7}{16}$ ", $\frac{1}{2}$ ".

BOLTS, SCREWS, ETC.



C295.
BLUED CUT TACKS
1", 1 1/2", 2", 2 1/2".

TINNED CUT TACKS
1", 1 1/2", 2", 2 1/2".

Special Large Heads
in Blued and Tinned.
1", 1 1/2".

CUT COPPER TACKS
1", 1 1/2", 2", 2 1/2".



C299.
COPPER RIVETS AND WASHERS
Length: 1/2", 3/4", 1", 1 1/4", 1 1/2", 2", 2 1/2", 3".
In varying Gauges from 6, 7, 8, 9, 10, 12.
In 1/2 lb. Packets.
Also in Assorted 1/2 lb. Packets.

C296.
COPPER BOAT NAILS
Sizes: 1/2", 1", 1 1/4", 1 1/2", 1 3/4", 2", 2 1/4", 3", 3 1/4", 4", 5".

C297.
COPPER ROVES
Sizes: 1/2", 3/4", 1".



C298.
BIFURCATED RIVETS
For Mending Harness
Large and Small Tins.




C300.
COPPERED STAPLES
Sizes: 1", 1 1/2", 2".

C301.
GALVANISED
ROOF BOLTS
AND NUTS
3/16" x 1/2", 5/8", 3/4".



C307.
HOLDFASTS
Straight or Bent Pattern.
3", 4", 5", 6", 7" long.



C302.
WOOD SCREWS
Sizes: 1/4", 1/2", 3/4", 1", 1 1/4", 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2", 3", 3 1/4", 4", 5", 6".
Gauges: 00 up to 28.

C306.
CORRUGATED WOOD FASTENERS
Plain and Divergent.
Largely used for joining Timber.
1/2" x 4 and 6 corrugations.
3/4" x 4, 5 and 6 corrugations.
1" x 4, 5 and 6 corrugations.
1 1/4" x 5 and 6 corrugations.




ORDER BY
NUMBER ONLY—
DON'T
CUT CATALOGUE



C305. 12 14 16 18
TINNED RIVETS
No. 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16,
18, 20. In Packets of 1000.

GALVANISED




C311.
MAGPIE PATTERN VENTILATORS
For Outside Use.

BRACKETS SUPPLIED TO SUIT ALL TYPES
AND SIZES OF SPOUTING.




C314.
GALVANISED IRON SPOUTING
Quadrant Pattern.

All Sizes of Galvanised Spikes and Tubes Supplied.



C315.
GALVANISED O.G. SPOUTING

For All Particulars re Sizes and Gauges, refer to Next Page.



C319. GALVANISED IRON RIDGING
FOR ALL PARTICULARS RE SIZES AND GAUGES OF ABOVE PRODUCTS, REFER TO NEXT PAGE.



C308.
SCREW HOOKS
Sizes: 1 1/2", 2", 2 1/4", 3 1/4", 3 1/2", 4", 4 1/2", 4 3/4".




C309.
SPRING HEAD ROOFING NAILS
Sizes: 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2".


IRON PRODUCTS



C312.
INSIDE VENT FOR USE WITH
MAGPIE VENTS
Flat Galvanised



C313.
WUNDERLICH VENTS
Painted, 9" x 6".



C317.
GALVANISED AIR BRICKS
Bar Pattern.
Sizes: 9" x 3", 9" x 6".



C316.
ANGLES FOR
SPOUTING



C320.
ELBOWS AND SHOES
To suit all sizes of
Down Pipe



C310.
TERRA COTTA
AIR BRICKS
Sizes: 9" x 3",
9" x 6".

PLASTER VENTS
For Internal Use.
Oblong or Oval Shape.
Plain or with Galvan-
ised Fly Wire.




C318.
HEADS FOR DOWN
PIPING
Sizes: 2", 2 1/2", 3", 4".



C321.
SOIL PANS (OVAL)
Sizes: 17" long x 13" deep,
18" long x 14" deep.
Also same sizes with
Iron Straps.

QUOTES GLADLY GIVEN FOR LINES NOT ILLUSTRATED

GALVANISED IRON PRODUCTS Cont.



C322.

**Corrugated
Galvanised
Iron Tanks**

Strongly made. True to gauge throughout. With or without cone-shaped cover. Ordinary or double soldered as desired.

Tanks up to and including 8 ft. 6 in. diameter can be forwarded by rail complete. Larger sizes either by special arrangements or in sections if desired we will supply the curved sections and tops and bottoms for any of the sizes in the following list as well as for larger tanks.

Capacity.	Gauge.	Diameter.	Height.	Weight without Cover			Weight with Cover.		
Imp. Gallons		ft. ins.	feet.	cwt.	qrs.	lbs.	cwt.	qrs.	lbs.
500	24	4 0	6	1	0	14	1	1	14
750	24	5 0	6	1	2	0	1	3	0
1,000	24	5 9	6	2	0	0	2	1	0
1,500	24	7 0	6	2	2	0	3	0	0
2,000	24	8 3	6	3	0	0	3	2	14
3,000	22	8 6	8	4	0	0	4	3	0

Particulars of larger sizes on application.

IRON

**FIRE
PLACES**



C323.

Made of 22 Gauge Iron Galvanised or Black Enamel Finish. Height of Opening, 4 ft. Height Over All, 14 ft. to Top of Flue Pipe.

SIZES:

30 inches wide
36 inches wide
48 inches wide

**GALVANISED IRON SPOUTING,
in 6 ft. Lengths—**

"QUADRANT" SPOUTING

3", 4", 4½", 5", 6", in 24, 26 and 28 gauge.

"O.G." SPOUTING

3", 3½", 4", 4½", 5", 6", in 24, 26, 28 gauge.

RIDGING

12", 14", 15", 16", 18", 20", in 24, 26, 28 gauge

DOWNPIPE

Soldered or Grooved Seams.

1½", 2", 2½", 3", 3½", 4", 5", 6", in 24, 26, 28 gauge

SQUARE DOWNPIPE

3" x 3", 4" x 2", 4" x 3", 4" x 4", 6" x 4", in 24, 26, 28 gauge

Can also be had with Riveted Seams at small extra cost.

HEADS FOR DOWNPIPES

2", 2½", 3", 3½", 4".

SHOES AND ELBOWS

To suit all sized pipes.

ANGLES FOR SPOUTING

All Sizes.

All the above illustrated on the previous page.

WE STOCK THE FOLLOWING LINES—

GALVANISED CORRUGATED IRON

"Orb," up to 12 ft.

Zincanneal, up to 10 ft.

PLAIN GALVANISED IRON

Also in Zincanneal.

6 ft. x 36", 30", 24", by 28, 26, 24, 22, 20, 18, 16 gauge.

GALVANISED RIPPLE IRON

Up to 10 ft., in 26 gauge only.

BLACK IRON

6 ft. x 36", 30", 24", by 26, 24, 22, 20, 18, 16 gauge

HOOP IRON


¾", 1", 1½", 2" wide, in ½ cwt. coils

SKYLIGHTS

Send for particulars of sizes and prices.

WE APPRECIATE YOUR ORDER WHETHER LARGE OR SMALL

PEERLESS CARD TABLE COMPANION ~ ~ ~



KEEPS YOUR TABLE
TOP CLEAR FOR
PLAYING. ~ ~ ~

FITS EITHER ROUND
OR SQUARE LEGS.

A NECESSARY-
ADJUNCT TO EVERY
CARD TABLE. ~ ~



Manufactured in various colours

MADE IN AUSTRALIA. Reg No. 9574

C324.

May be had in Blue, Green and Brown,
Lacquered Finishes.



C325.

PLAITED SASH CORDS

JUTE

No. 3, 4, 5



C328.

BLIND LADDER TAPE

Best woven.

VENETIAN BLIND
CORD

Best White Lines.

GLACIE CORD

In colours.

CHAIR WEBBING

Good Quality. 2" wide in
bundles of 18 yards



C326.

SISAL TWINE

For Garden Use
In 1 lb. and 7 lb.
Reels.



C327.

REAPER AND BINDER TWINE

In Balls.



C329.

"SNAPPY" CATCHES

Rubber Rollers steady door when
slamming and hold firmly when
closed.



C331.

MANILA ROPE

Best Quality. Cut to any length.

Approximate Weight per 100 ft.

1"	1 1/4"	1 1/2"	1 3/4"	2"	2 1/4"	2 1/2"	2 3/4"	3"	Dia.
5	7	10	12	16	20	28	28	35	lbs.



C330.


BRAIDED SASH LINES

The best Sash Line produced. Also used for purposes requiring a
high-grade cord line.

Made in Cotton and Australian Linen.

No.	6	7	8	9	10	12
Approx feet to lb.	72	54	43	36	30	23

ROPE CLOTHES LINES IN VARIOUS LENGTHS



C332.

"ZINCROID" FLY WIRE

Best quality Fly Wire, the same as used on
our Doors and Screens


18", 20", 22", 24", 26", 28", 30", 32", 34", 36", 42"
48" wide. Also 24", 30", 36", 42" in 26 and
28 gauge.

BRONZE FLY WIRE

Made of Phosphor Bronze Wire and withstands

Sea Air

24", 28", 30", 36", 42", 48"



C333.

PERFORATED ZINC

In sheets 7 ft. and 8 ft. x 3 ft.

PLAIN SHEET ZINC

We carry full stocks of all gauges
of Plain Zinc. Prices on application.


EXPANDED METAL

In sheets 9 ft. x 2 ft. and 1/2 in.
mesh.

Japanned Black Finish.




C334.



C335.

The above illustrations show two most popular designs.
Send for our Complete Seasonal List of Fly Doors
and Fittings.

ALL
TYPES
OF
BRICK
BONDING
CARRIED
IN STOCK



C336.

"BRICTOR"

THE BEST REINFORCEMENT FOR
BRICKWORK

In rolls 150 ft. long. Galvanised in widths
1 1/2", 2 1/2".

GET OUR QUOTE FIRST — IT WILL PAY YOU

FENCING REQUIREMENTS



C337.

Our Fencing Wires are made from the best quality open hearth steel, being heavily galvanised and smoothly finished.

The following shows an approximate calculation of Fencing Wire in two popular sizes:—

Quantities of Wire required for each mile of fencing.			
One Wire		Two Wires	
No.	Gauge	cwt. qrs. lbs.	cwt. qrs. lbs.
No. 8	Gauge	3 0 7	6 0 14
No. 10	Gauge	2 0 15	4 1 2
Three Wires		Four Wires	
No.	Gauge	cwt. qrs. lbs.	cwt. qrs. lbs.
No. 8	Gauge	9 0 12	12 1 1
No. 10	Gauge	6 1 19	8 2 0

WIRE NETTING

C339.

Height in Inches	Size of Mesh	Wire Gauge
Rabbit Sizes—		
12	x	1 1/2
18	x	1 1/2
36	x	1 1/2
42	x	1 1/2
36	x	1 1/2
42	x	1 1/2
42	x	1 1/2
42	x	1 1/2
72	x	1 1/2

Pig Sizes—

24	x	4	x	16
30	x	4	x	16
36	x	4	x	16
30	x	3	x	16
36	x	3	x	16



Height in Inches	Size of Mesh	Wire Gauge
Poultry Sizes—		
24	x	2
30	x	2
36	x	2
48	x	2
72	x	2

Bird Sizes—

24	x	1 1/2	x	22
30	x	1 1/2	x	22
36	x	1 1/2	x	22
24	x	1 1/2	x	20
30	x	1 1/2	x	20
36	x	1 1/2	x	20
24	x	1	x	20
30	x	1	x	20
36	x	1	x	20

IRON FENCING POSTS (Fireproof)

Each post is bored to the following spacings:—5, 6, 5, 6, 8, 6, 6 inches; also an open slot on the top to permit a barbed wire being run in, with a tying hole immediately under, which could be used for a plain wire if desired.

Depth in Ground

There is an extra hole 6 inches below the usual bottom wire hole. This can be used for a good line wire for sheep netting or as a guide when driving post, to ensure correct depth in ground. The manner in which these posts are bored allows the erection of almost any type of fence and will enable the use of either 30, 36, or 42 inch wire netting, also barbed wire.

The best method to adopt in erecting a fence with iron posts is to use the wooden strainer in conjunction.

With every 250 posts supplied there is a driving cap given free. These caps prevent the tops of the posts becoming burred or damaged during hard driving. The handle of this driving cap makes it impossible for the post to get out of alignment during driving.

Length	5 1/2	6 feet
Weight per 10 posts	72	78 lbs.


Black Varnished.



C342.

STAPLES

FOR WIRE NETTING
 3/4", 1", 1 1/4" Galvanised.
 FOR FENCING WIRE
 1", 1 1/4", 1 1/2" Galvanised.



C343.

DROPPER STAPLES

(Galvanised)

FOR USE ON WOODEN DROPPERS
 2 1/4" long.



Section of Post
 showing hole for
 wire.

BARBED WIRE




C338.

Extra high quality, that satisfies the demand for well constructed, long lasting Barbed Wire. The price is considerably less than usually asked for ordinary grades. Tough annealed wire, galvanised with a heavy coating of pure zinc, long sharp four-pointed rust-resisting round barbs.

Iowa—

No.	Approx. lengths to cwt.
No. 12	400 yds.
No. 13	520 yds.
No. 14	700 yds.

Waukegan Pattern, 12 1/2 gauge, 14 gauge, in 112 lb. coils.



C340.

WIRE NETTING FASTENERS

(Galvanised)

To Fasten Wire Netting to Fencing as Illustrated. Very quickly and easily fixed. Supplied in gross packets.

C341.

IRON FENCING POSTS

Easy to Handle
 and Erect.




Illustration showing Two Popular
 Types of Fences.

WE SPECIALIZE IN COUNTRY ORDERS

"SEBCO" Expansion Devices

C344.



★ DRYVIN

The DRYVIN is an Expansion Shield you hammer home. In drilling, the hole of the fixture is used as a template, thus eliminating all spotting or use of special templates. The DRYVIN is dropped in through the hole of the fixture, and then with a few blows of the hammer the nail is driven home. No laborious work with a screwdriver or wrench, no wood plugs, screws, or bolts required. Just hit the nail with a hammer.

Size Diameter Length of Shield not the nail	Outside Diameter and Drill Required	Working Load, Pounds	Quantity in Standard Package	Quantity in Standard Shipping Carton	Shipping Weight Per 100
7/8" x 3/16"	3/16"	130	100	1000	1.2 lbs.
1 1/4" x 3/16"	3/16"	150	100	1000	1.6 lbs.
1" x 1/2"	1/2"	200	100	1000	2 1/4 lbs.
1 1/4" x 1/2"	1/2"	300	100	1000	2 3/4 lbs.
1 1/2" x 1/2"	1/2"	350	100	1000	3 1/2 lbs.
2 1/4" x 5/16"	5/16"	500	100	500	6 1/2 lbs.
2 3/4" x 5/16"	5/16"	500	100	500	8 lbs.
2" x 3/4"	3/4"	700	100	500	10 1/4 lbs.
3 1/4" x 3/4"	3/4"	700	50	250	13 1/2 lbs.
2 1/2" x 1"	1"	1200	50	250	18 lbs.
3 1/2" x 1"	1"	1200	50	250	25 lbs.

Use the same diameter drill as the Dryvin

C346.



★ LOXIN

A LOXIN Shield will never yield. Carries greater loads, easier to install, securer than most other methods. No grouting of bolts, drilling requirements cut in half, no lead or cement required, no waiting for material to set. When properly installed the LOXIN will develop the strength of machine bolts used. It can be inserted in either a loose or tight hole. In the case of a tight hole the shield can be tapped into place with a hammer. Under this condition it gives the best results.

Diam of Bolt with which shield is used	Length of Shield	Cuts de Dam and Drill Required	Quantity in Standard Package	Quantity in Standard Shipping Carton	Shipping Weight Per 100
1/2"	1 1/4"	1/2"	100	1000	3 1/2 lbs.
3/4"	1 1/2"	3/4"	100	1000	4 lbs.
1"	1 3/4"	1"	100	1000	4 1/2 lbs.
1 1/4"	2"	1 1/4"	50	500	8 lbs.
1 1/2"	2 1/4"	1 1/2"	25	250	18 lbs.
1 3/4"	2 1/2"	1 3/4"	25	250	26 lbs.
2"	2 3/4"	2"	25	250	37 lbs.


For
Making
Attachments
to
Brick,
Stone
or
Hollow
Walls.

"SEBCO"
DRILL POINTS
AND
HAND CHUCKS

"SEBCO" Drill Points
are made of special steel-
alloy scientifically heat-
treated to stand hard use
in masonry drilling.

TWIST TYPE.

Sizes: 3/16", 1/2", 5/16",
3/8", 1", 1 1/2".



C347.

TOGGLE BOLT
(Complete)

Size Drill Required	Number Pieces in a Box
3/16"	100
1/4"	100
5/16"	100
3/8"	100
1/2"	100
5/8"	100
3/4"	100
1"	100
1 1/4"	50

Diam. and Length
of Screw

3/16"	x	3"
1/4"	x	4"
5/16"	x	4"
3/8"	x	6"
1/2"	x	6"
5/8"	x	6"
3/4"	x	6"

C345.



★ TAMPIN

For use with machine screws or bolts. Unequalled where shallow hole for installation is necessary and and where work has to be dismantled from time to time. TAMPINS are unequalled for electrical and sanitary installations and all similar attachments to concrete, brick or stone. The Wedge Nut is threaded for standard machine bolts and screws. All sizes have two fins on the conical nut, which prevents the nut from turning in the lead. The special TAMPIN alloy lead sleeve will enter all irregularities of the masonry hole and will not yield under a heavy load.

Size of Bolt or Screw with which Shield is Used	Dimensions of Minimum Holes Required		Quantity in Standard Package	Quantity in Standard Shipping Carton	Shipping Weight Per 100 (Inc. Tool)
	Diam.	*Depth			
3/16"	3/16"	5/8"	100	1000	2 lbs.
1/4"	1/4"	5/8"	50	500	5 lbs.
5/16"	5/16"	1 1/4"	50	250	14 lbs.
3/8"	3/8"	1 1/4"	50	250	19 lbs.
1/2"	1/2"	2"	50	250	24 lbs.

TOGGLE BOLTS

An ideal fastening for lath-pressed boards, hollow metal, and plaster, hollow tile, terra cotta or sheet metal. Channel construction permits toggle head to fold closely over bolt and pass through a small hole. Toggle head set off centre to fall quickly into place. "Sebco" Toggles bear on extreme ends, avoiding breaking of brittle material.

C348.



★ SCRUIIN

This is a new design anchor which gives greater holding power; requiring a smaller installation hole for the corresponding size screw. It takes more sizes of screws grouped in a more convenient series than other designs. It also has a larger range of holding power through various sizes of hole diameters. The holding power in average conditions of masonry is higher in the short length for No. 8 and 14 sizes, but in the case of a plaster wall or other soft-surfaced masonry we recommend the use of the long length.




*NOTE.—A deeper hole should be used in making attachments to soft masonry.

Screw Size and Length of Anchor	Fractional Screw Size	Outside Diam. and Drill Required	Quantity in Standard Package	Quantity in Standard Shipping Carton	Shipping Weight Per 100
1 1/4" x 6-8	3/16"	3/4"	100	1000	1 1/2 lbs.
1 1/2" x 6-8	3/16"	3/4"	100	1000	2 1/4 lbs.
1 3/4" x 10-12-14	5/16"	5/8"	100	1000	2 3/4 lbs.
1 1/2" x 10-12-14	5/16"	5/8"	100	1000	3 1/4 lbs.
1 3/4" x 16-18	3/8"	7/8"	50	500	5 lbs.
1 1/2" x 20-22-24	3/8"	7/8"	50	500	8 lbs.

SINCE 1859 DANKS HAVE LED IN QUALITY

"DASPYL" Die Pressed and Turned Brass Fittings

For Petrol - Oil - Refrigerators, Etc.

							
TYPE 60F Sleeve Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	TYPE 61F Nut Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	TYPE 68F Single Union Gas Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	TYPE 62F Double Union Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	TYPE 69F Elbow Gas Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	TYPE 41F SAE Nut Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	TYPE 48F SAE Union Gas Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	TYPE 49F Elbow Gas Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"
							
TYPE 63F Check Valve Gas Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	TYPE 66F Female Union Gas Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	TYPE 65F Double Elbow Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	TYPE 72F Two-way Tee Gas Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	TYPE 71F Vertical Tee Gas Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	TYPE 64F Three-way Tee Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	TYPE 70F Female Elbow Gas Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	
							
TYPE 46F Female SAE Union Gas Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	TYPE 50F Female SAE Elbow Gas Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	TYPE 42F SAE Double Union Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	TYPE 55F SAE Double Elbow Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	TYPE 44F SAE Three-way Tee Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	TYPE 45F SAE 1/8 Gas Tee Gas Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	Dole Pat. Nut Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	
							
Dole Pat. Body Gas Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	Dole Pat. Elbow Gas Tube 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	Red. Bush Gas 1/8" to 1/8"	M. & F. Elbow Gas 1/8" x 1/8"	Socket Gas 1/8" x 1/8"	Nipple Gas 1/8" x 1/8"	Long Nipple Gas 1/8" x 1/8" 1/8" x 1/16" 1/8" x 1/8"	
Please Order by Number, Description and Size							
Windshield Cleaner Fittings							
							
Red. Socket Gas 1/8" to 1/8" 1/8" to 1/8"	Drain Cock Gas 1/8"	Priming Cup Gas 1/8"	Gas 1/8" x 1/8"	TYPE 76F 1/8" x 1/8" Gas x 1/16" Tube	1/8" Gas x 1/8" Tube 1/8" Gas x 1/16" Tube		

Please Order by Number, Description and Size

Windshield Cleaner Fittings

DANKS SPECIALIZE IN PETROL UNIONS AND CONNECTIONS

Motor Accessories

Apart from the Lines illustrated, we carry a very comprehensive range of Motor Accessories, as follows:—

Air Compressors, and all fittings and connections for same.

Battery Clips, terminals, earth straps, etc.

Beading (Aluminium), half-round and angle; plain and fluted.

Bendix Springs, screws and washers, etc.

Belts (Fan): V and Flat type; Bonnet Lacing.

Brushes for wire wheels, engine and chassis cleaning.

Brake Fluid, Brake Lining, drill and countersink, hollow rivet punch.

Caps for Petrol Tanks (plain and locking), Radiator Caps, etc.

Cans, 2 gal, for petrol; spare necks, caps and pourers for same.

Celluloid for Curtains: .015, .020 Sheets, 24" x 54".

Chamois Leathers, Basil or Goat Skin, 21" x 20", 23" x 22", 24" x 23", 26" x 25".

Cloth (Cleaning), 28 lb. Cartons.

Stockingette: Roll about 20 yds., or small Motorist's Pkge., Soft Polishing Cloth, 18".

Coils, Electric, 6v. or 12v., and condensers for same.

Control Cables: Choke, wire and casing. Choke Lever, for dashboard.

Cork Packing Sheets: 36" x 12" x $\frac{1}{16}$ ", 36" x 12" x $\frac{3}{32}$ ", 36" x 12" x $\frac{1}{8}$ ", 36" x 24" x $\frac{1}{16}$ ", 36" x 24" x $\frac{3}{32}$ ", 36" x 24" x $\frac{1}{8}$ ", 36" x 24" x $\frac{3}{16}$ ", 36" x 24" x $\frac{1}{4}$ ".

Cotter Pins: Steel Split Pins, Motor sizes, from $\frac{1}{2}$ " x $\frac{1}{16}$ " to $2\frac{1}{2}$ " x $\frac{1}{4}$ "; also in tins of 100 assorted.

Clevis Pins: Sizes to suit all Cars.

Cut-outs, Electric, 6v. and 12v.

Door Anti-Rattlers.

Electrical Parts: Distributor Points, Covers, Rotors, etc., Carbon Brushes.

Fasteners for Cushions: Turn Buttons, Dot Fasteners, etc.

Files, Magneto; Flex Stones, for Contacts.

Fuses for Electrical Systems.

Funnels for Petrol and Oil, Round or Square with Straight or Angle Spouts

—Plain or Non-Splash Types.

SOLDER TYPE UNIONS

Nut
X36.



Tube
 $\frac{3}{8}$ "
 $\frac{1}{2}$ "
 $\frac{5}{8}$ "
 $\frac{3}{4}$ "
 $\frac{7}{8}$ "
 $1\frac{1}{8}$ "
 $1\frac{1}{2}$ "

Tail
X37.



Tube

$\frac{1}{8}$ "
 $\frac{3}{16}$ "
 $\frac{1}{4}$ "
 $\frac{5}{16}$ "
 $\frac{3}{8}$ "
 $\frac{1}{2}$ "
 $\frac{5}{16}$ " TAIL FOR
 $\frac{1}{4}$ " TUBE

Single Body
X38.



Tube
 $\frac{5}{16}$ " x 26 x $\frac{1}{8}$ "
Gas Tube
 $\frac{1}{8}$ " x $\frac{5}{16}$ "
 $\frac{1}{8}$ " x $\frac{3}{4}$ "
 $\frac{1}{8}$ " x $\frac{1}{2}$ "
 $\frac{1}{8}$ " x $\frac{5}{16}$ "
 $\frac{1}{8}$ " x $\frac{3}{8}$ "
 $\frac{1}{8}$ " x $\frac{1}{2}$ "
 $\frac{1}{8}$ " x $\frac{5}{8}$ "
 $\frac{1}{8}$ " x $\frac{3}{4}$ "
 $\frac{1}{8}$ " x $1\frac{1}{2}$ "
 $\frac{1}{2}$ " x $\frac{1}{2}$ "

Double Body
X39.



Tube
 $\frac{5}{16}$ " x 26 - $\frac{5}{16}$ " x 26 $\frac{1}{8}$ "
Gas Gas
 $\frac{1}{8}$ " x $\frac{1}{8}$ "
 $\frac{1}{8}$ " x $\frac{1}{4}$ "
 $\frac{5}{8}$ " x $\frac{3}{8}$ "
 $\frac{1}{8}$ " x $\frac{1}{2}$ "
 $\frac{5}{16}$ " or $\frac{5}{16}$ "
 $\frac{1}{8}$ "

Single Union
X40.



Gas Tube
 $\frac{1}{8}$ "
 $1\frac{1}{8}$ " x $\frac{3}{16}$ "
 $1\frac{1}{8}$ " x $\frac{1}{4}$ "
 $1\frac{1}{8}$ " x $\frac{5}{16}$ "
 $1\frac{1}{8}$ " x $\frac{3}{8}$ "
 $1\frac{1}{8}$ " x $\frac{1}{2}$ "

Double Union
SINGLE NUT
X41.



Tube
 $\frac{1}{4}$ "
 $\frac{5}{16}$ "
 $\frac{3}{8}$ "

Double Union
X42.



Tube
 $\frac{1}{8}$ "
 $\frac{5}{16}$ "
 $\frac{1}{4}$ "
 $\frac{5}{16}$ "
 $\frac{3}{8}$ "
 $\frac{1}{2}$ "

Elbow
X43.



Tube
 $\frac{1}{4}$ "
 $\frac{5}{16}$ "
 $\frac{3}{8}$ "

Tee
X44.



Tube
 $\frac{1}{8}$ "
 $\frac{1}{4}$ "
 $\frac{5}{16}$ "
 $\frac{3}{8}$ "



X45.

Fem. Elbow

$\frac{1}{8}$ "



X46.

Fem. Tee

GAS
 $\frac{1}{8}$ "



X47.

Ford Petrol
Pipe Nut

TUBE
 $\frac{1}{4}$ "

INVERTED FLARED UNIONS

Suit Chrysler, De Soto, Plymouth, Dodge, Buick, etc.

Nut
X48.



Tube
 $\frac{3}{16}$ "
 $\frac{1}{4}$ "
 $\frac{5}{16}$ "
 $\frac{3}{8}$ "
 $\frac{1}{2}$ "

Single Body
X49.



Gas Tube
 $\frac{1}{8}$ " x $\frac{5}{16}$ "
 $\frac{1}{8}$ " x $\frac{1}{4}$ "
 $\frac{1}{8}$ " x $\frac{5}{16}$ "
 $\frac{1}{8}$ " x $\frac{3}{8}$ "
 $\frac{1}{8}$ " x $\frac{1}{2}$ "
 $\frac{3}{8}$ " x $\frac{1}{2}$ "

Double Body
X50.




Tube
 $\frac{3}{16}$ "
 $\frac{1}{4}$ "
 $\frac{5}{16}$ "

Elbow
X51.




Gas Tube
 $\frac{1}{8}$ " x $\frac{5}{16}$ "
 $\frac{1}{8}$ " x $\frac{1}{4}$ "
 $\frac{1}{8}$ " x $\frac{5}{16}$ "
 $\frac{1}{8}$ " x $\frac{3}{8}$ "
 $\frac{1}{8}$ " x $\frac{1}{2}$ "
 $\frac{3}{8}$ " x $\frac{1}{2}$ "

M & F Tee
X52.



Gas
 $\frac{1}{8}$ "

Tank Flange
& Lock Ring
X53.



Gas
 $\frac{1}{8}$ "
 $\frac{1}{4}$ "

Tank Flange
Plain
X54.




Gas
 $\frac{1}{8}$ "
 $\frac{1}{4}$ "

Brass Plug
X55.



$\frac{1}{8}$ " Gas
 $\frac{1}{4}$ " "

Cap & Liner
for Petrol Tank
X56.





$1\frac{1}{2}$ " Opening
 $1\frac{3}{4}$ " "
2" "

Flanged Cap
and Liner
for Petrol Tank

X57.

$1\frac{1}{2}$ " Opening

NEEDLE VALVE PETROL TAPS




PETROL TAPS



X62.
 (Full Way)

Gas Tube
 $\frac{1}{8}" \times \frac{5}{8}"$
 Or
 $\frac{3}{8}" \times \frac{5}{8}"$
 Double Ended



"JD" QUALITY MOTOR PRODUCTS

Chassis Black (anti-corrosive)—Tins 1 pt., 1 qt., $\frac{1}{2}$ gal., 1 gal., 4 gals.

Gasket Cement—2 oz. Bottle; Tins 2 ozs., 16 ozs., $\frac{1}{2}$ gal., 1 gal.

Gasket Putty—4 oz. Tins.

Hood Dressing (waterproof), Black— $\frac{1}{2}$ pt., 1 pint.

Hood and Tyre Paint, Black— $\frac{1}{2}$ pt., 1 pt., 1 gal.

Liquid Radiator Seal—8 oz. Tin.

Radiator Cement Powder for tubular radiators— $1\frac{1}{2}$ oz. Tin.

Radiator Cleaner—1 pt.

"Slick" Auto. Polish—8 oz., 16 oz. Bottles.

Rust Nut—4 oz., 8 oz. Press Can, $\frac{1}{2}$ gal. Tin.

"Value" Grinding Compound, 2 in 1 oil mixed—2 oz. Tin.

"Value" Grinding Compound, Medium or Coarse—1 oz. Tin.

Vulcanizer Outfits (5 minute), in Cartons.

Vulcanizer Patch and Heat Units—Tins of 6, 12, Packets of 144.

Motor Accessories

Gaskets (Copper-Asbestos): Round, oval, semi-finished, Cylinder Head, cork, etc.

Liquid Gasket: "Gasket Goo," in 3 oz. and 11 oz. tubes.

Gauges, Tyre: Kismet, plunger type, 50 lb. and 140 lb.

Gauze: Brass Wire, for oil or petrol, 18 to 120 mesh, rolls 24" wide.

Grease Guns, Hoses, etc., for all systems.

Grease Nipples, for Alemite and Zerk systems; straight or angle.

Goggles: For dust protection, Industrial work, welding, etc.

Grinding Compound, for valve grinding, lapping bearings.

Hose for Air: Tyre Pump, $\frac{3}{16}"$, Garage Air Line, $\frac{1}{4}"$, $\frac{5}{16}"$, $\frac{3}{8}"$, for Radiators 1" to 3", in 3' lengths; also moulded hoses for certain makes of cars.

Hydrometers: Eagle Battery Tester.

Insulation Tape, in 2 oz., 4 oz. and 8 oz. rolls.

Indicators: Mudguard, Fendicators, screw or clamp-on types.

Joints: Ball Joints for Controls.

Keys: Woodruff $\frac{3}{8}" \times \frac{1}{16}"$ to $1\frac{1}{2}" \times \frac{3}{8}"$; also in assorted boxes.

Measures for Oil and Petrol: $\frac{1}{2}$ pt., 1 pt., 1 qt., $\frac{1}{2}$ gal., 1 gal., 2 gal., 4 gal.

Motor Products: "JD" Quality, as enumerated.

Motor Grease.

Nuts: Nickel-plated, Dome, $\frac{3}{16}"$, $\frac{1}{4}"$, $\frac{5}{16}"$, $\frac{3}{8}"$, $\frac{7}{16}"$, $\frac{1}{2}"$, $\frac{5}{8}"$, Whitworth.

Oil Cans: Wesco Force Feed $\frac{1}{3}$ pint; $\frac{1}{2}$ pint, 1 pint.

Oil Filters: "Colem," for all makes of cars.

Oil Syringes: Small, 8"; medium, 12"; large, 18".

Packing: Sump $\frac{1}{64}"$, $\frac{1}{32}"$, $\frac{1}{16}"$; rolls 36" wide.

Petrol Filters: Visible Bowl type.

Phosphor Bronze Bushing, Metal, Solid and Cored, $\frac{3}{8}"$ to 5" dia. x 12" long.

Piston Rings for all Cars and Engines, Std. and O/Size.

Petrol Pump Repair Kit, diaphragms and fittings.

Pullers: Gear and Sprocket Pullers, small and large.

TRY DANKS FIRST FOR ALL MOTOR REQUIREMENTS

Radiator Faucet with automatic shut-off valve for filling radiators.

Rivets—Aluminium, Pan Head, Brass, Tubular, etc.

Rubber — Molded Shackles, Bushes, Hoses, etc.

Screws—N.P. Stove Screws and Nuts, S.A.E. Metal Thread Screws and Nuts. S.A.E. N.P. Screws and Nuts. Assorted $\frac{1}{2}$ gross packets.

Shim Brass—6 ins. wide x .001 in., .0015 in., .002 in., .003 in., .004 in., .005 in., .006 in., .008 in., .010 in., .012 in., .015 in.

Shim Steel—6 ins. wide x .002 in., .003 in., .004 in., .005 in., .006 in., .008 in., .010 in., .015 in.

Assorted sized packets, Brass. Assorted Tins, Steel or Brass.

Shock Absorbers and Knee Action Fluid, various grades to suit all makes of Shock Absorbers.

Solder—Silver, in Wire or Strip. Resin or Acid Cored in 1 lb. reels or small pkts.

Sponges—Auto., Turkey, Honeycomb, No. 2 Medium.

Springs—Coil, Tension and Expansion, Brake, Accelerator, etc. Also in assorted boxes.

Switches — Tail-light, Toggle, Push-pull, Rotary, Dimmer, Starter (foot).

Taper Pins from No. 7/0 x $\frac{3}{4}$ in. to No. 10 x 6 ins. Also in assorted boxes.

Taps—Petrol. Enots' concentric, cork seated, push-pull type. $\frac{1}{8}$ in. gas, $\frac{1}{4}$ in. gas, and double ended for $\frac{3}{16}$ in., $\frac{1}{4}$ in., $\frac{5}{16}$ in., $\frac{3}{8}$ in. copper tube.

Terminals — for Plugs, Distributors, Coil, Earth Leads, Battery or Lighting Wires.

Tool Rolls—canvas, 12 divisions.

Tow Ropes—1 in. and $1\frac{1}{4}$ in. circumference Steel Wire Rope, 20 ft.

Tyre Levers—14 in. and 18 in.

Valves—Schrader Cores and Caps.

Valve Lifters—Types to suit old and modern cars.

Valve Seat Cutters and Pilots.

Valve Grinders—Suction type, rubber cups, small, medium and large.

Washers—Bright Steel, Spring (flat and sq. section), Double Spring, Steel (nickel plated), Spacing, Mudguard Repair Washers, Fibre, Star Lock. Spring Washers and Fibre Washers in assorted tins.

COMPRESSED AIR EQUIPMENT GARAGE AIR HOSE UNIONS

X70.

Compo. Seat. Quick Detachable Coupling.

$\frac{1}{8}$ " gas for $\frac{3}{16}$ " hose
 $\frac{1}{8}$ " gas for $\frac{1}{4}$ " hose
 $\frac{1}{8}$ " gas for $\frac{5}{16}$ " hose
 $\frac{1}{8}$ " gas for $\frac{3}{8}$ " hose

$\frac{1}{8}$ " gas for $\frac{3}{16}$ " hose
 $\frac{1}{8}$ " gas for $\frac{1}{4}$ " hose
 $\frac{1}{8}$ " gas for $\frac{5}{16}$ " hose
 $\frac{1}{8}$ " gas for $\frac{3}{8}$ " hose



Spare Seats Obtainable.

AIR HOSE STEMS

X71.

$\frac{1}{8}$ " gas x $\frac{3}{16}$ " hose
 $\frac{1}{8}$ " gas x $\frac{1}{4}$ " hose
 $\frac{1}{8}$ " gas x $\frac{5}{16}$ " hose
 $\frac{1}{8}$ " gas x $\frac{3}{8}$ " hose
 $\frac{1}{8}$ " gas x $\frac{5}{16}$ " hose

$\frac{1}{8}$ " gas x $\frac{3}{16}$ " hose
 $\frac{1}{8}$ " gas x $\frac{1}{4}$ " hose
 $\frac{1}{8}$ " gas x $\frac{5}{16}$ " hose
 $\frac{1}{8}$ " gas x $\frac{3}{8}$ " hose
 $\frac{1}{8}$ " gas x $\frac{5}{16}$ " hose

$\frac{1}{8}$ " gas x $\frac{3}{16}$ " hose
 $\frac{1}{8}$ " gas x $\frac{1}{4}$ " hose
 $\frac{1}{8}$ " gas x $\frac{5}{16}$ " hose
 $\frac{1}{8}$ " gas x $\frac{3}{8}$ " hose
 $\frac{1}{8}$ " gas x $\frac{5}{16}$ " hose



AIR SAFETY VALVES

X72.

Small Type Adj., 120 lbs.

Screwed $\frac{1}{4}$ ", $\frac{3}{8}$ ", $\frac{1}{2}$ " Gas.

Also Large Type, 150-400 lbs.

Compo. Disc. Seat.



X73.

AIR CHUCKS (Automatic)

$\frac{1}{4}$ ", $\frac{5}{16}$ " and $\frac{3}{8}$ " Hose. $\frac{1}{4}$ " Gas Fem. Straight Type $\frac{1}{4}$ " Gas.
Spare Washers Obtainable.



STOP VALVES

X75.

With special seats for air.


Sizes: $\frac{1}{4}$ ", $\frac{3}{8}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ " Gas.




AIR CHECK VALVES

X74.

With Compo. Disc Valve and Guide.



Opens and closes only when there is a definite change in direction of air flow. Stops air blowing back from receiver, fitted with long guide and piston, forming air cushion to stop hammering of seat.
 $\frac{1}{4}$ " Gas, $\frac{3}{8}$ " Gas, $\frac{1}{2}$ " Gas, $\frac{3}{4}$ " Gas. Spare Seats: $\frac{1}{4}$ ", $\frac{3}{8}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ " Gas.



AIR BLOW GUNS

X76.

Blow Gun with hose stem for $\frac{3}{16}$ ", $\frac{1}{4}$ ", $\frac{5}{16}$ " and $\frac{3}{8}$ " Hose.

Blow Gun, fitted with air chuck, with hand control, for $\frac{3}{16}$ ", $\frac{1}{4}$ ", $\frac{5}{16}$ " and $\frac{3}{8}$ " Hose.

WE STOCK EVERYTHING FOR YOUR CAR

AIR CHUCK COUPLINGS




X77.

Female Plug
3/8" and 1/2" Gas.



X78.

Female Body
3/8" and 1/2" Gas



X79.

Male Plug
3/8" and 1/2" Gas.



X80.

Male Body
1/2" Gas only.

Quick coupling of all air tools to the hose line. Positively no leaks. Air cannot leak through beside pin because air does not touch the pin in its passage through the coupler.

STRONG RELIABLE JACKS



X81.

Twin-Screw

Ball Bearing—			
Height	Lift	Capacity	Weight
6 1/2"	9"	30 cwt.	6 lbs.
P.A.H.—			
6"	8"	30 cwt.	6 lbs.




X82.

Single-Screw

Ball Bearing—			
Height	Lift	Capacity	Weight
9"	5 1/2"	20 cwt.	6 1/2 lbs.
Plain—			
7 1/2"	4"	20 cwt.	6 lbs.

Plain and
Ball
Bearing


QUICK LIFT HYDRAULIC JACKS



X83.

2-Ton Jack

Min. Max.			
Weight			
8 lbs.			
Height of Jack	7"	16"	
Hydraulic Lift	5"		
Extension Screw	4"		



X84.

5-Ton Jack

Min. Max.			
Weight			
20 lbs.			
Height of Jack	9 1/2"	16 1/2"	
Hydraulic Lift	7"		

Wheel Pullers—Hub and shock type.

Welding Rods and Fluxes.

Water—Distilled, in bottles only.

White Metal—Hoyts, six grades to suit all purposes. State requirements.

Wire—Electric cables for car lighting, ignition, starting, etc. 100 ft. spools and in bulk.

"J.D." GARAGE ASSORTMENTS

In Divided Steel Boxes.

Bolts and Nuts, Nuts, Setscrews—1 gross and 1/2 gross lots.

Cotter Pins—12 gross. Clevis Pins 168.

Lamp Sockets and Connections—7 doz.

Metal Thread Screws and Nuts, S.A.E.—8 gross.

Wood Screws—4 1/2 gross.

Petrol Unions—74, 89, 125 pieces.

Pump Cup Washers—24.

Washers—Spring, 6 1/2 gross; Plain, 4 1/2 gross.

Rivets—Brass Tubular, 1400.

Self-Tapping Screws—256.

Terminals—Lighting and Ignition, etc., 264.


Bendix Screws and Washers—90 pieces.

Although we always endeavour to supply goods exactly as represented; if we should be out of stock we will send the nearest type or brand to fulfil the order, unless instructed otherwise. If goods have to be bought in we will endeavour to procure same and pass them on at the best price obtainable, and we trust they will be acceptable to our customers on these terms.

To avoid mistakes when ordering parts, please state exactly particulars regarding model and year of car, also any necessary measurements with sketch or complete description of part wanted, also showing location on car.

"JD" QUALITY MOTOR PRODUCTS WILL KEEP YOUR CAR YOUNG

LIFTING JACKS (Continued)



X85.	BUMPER BAR TYPE				X86.
Measurements—	Overall	Low	Raise	Full	Capacity
	Height	Lift		Height	
X85	32 3/4"	8 3/4"	23"	31 1/4"	2000 lbs.
X86	32 3/4"	9"	20"	29"	1500 lbs.

BRIGHT STEEL BOLTS, NUTS AND SET SCREWS



X90.
Bright Steel Bolts and Nuts
Hexagon Head.
Whitworth, S.A.E. and B.S.F. Standard.



X91.
Bright Steel Hexagon Nuts
Whitworth, S.A.E. and B.S.F. Standard.

X92.
Bright Steel Castellated Nuts
All Sizes.



Bright Steel Set Screws
Small Head. Whitworth Thread.
Bright Steel Hexagon Set Screws
Whitworth, S.A.E. and B.S.F. Standard.

X93.
Spring Lock Washers



Flat or Square Section.
Superior Quality,
1/8" to 1".

Masse



BATTERIES

Made in Three Grades
each with a range of

6 Volt 7 to 21 Plates
12 Volt 9 to 18 Plates

A SIZE FOR EVERY CAR

X87.
The Masse Supercol Battery is guaranteed for 24,000 miles or 24 months.

X88.
The Masse MA Type is guaranteed 18,000 miles or 18 months.

X89.
The Masse Crown Battery is guaranteed 12,000 miles or 12 months.

HIGH GRADE AUTO. GLOBES

6 Volt or 12 Volt — S.C. or D.C. — Single or Double Filament.



X95.
Flanged Type.



X96.
Headlight.



X97.
Stoplight.




X98.
Tail Light.



X99.
Pilot Light.

"REFORM" BRITISH DROP FORGED SPANNERS

Jaws Accurately Milled to Sizes.



Heads inclined 15 degrees.

X100.


S.A.E. Standard Milled Openings.

5/16" x 3/8", 3/8" x 7/16", 7/16" x 1/2", 1/2" x 9/16", 9/16" x 5/8", 5/8" x 3/4", 3/4" x 7/8", 7/8" x 1", 1" x 1 1/8", 1 1/8" x 1 1/4", 1 1/4" x 1 1/2", 1 1/2" x 1 3/4", 1 3/4" x 2"

Specially Selected Steel. Heat Treated and Hardened.

DANKS FOR HIGH QUALITY MOTOR TOOLS

"REFORM" SUPER-CHROME VANADIUM D.E. SPANNERS
 DROP FORGED OF SPECIAL ALLOY STEEL
 Long — Thin — Unbreakable



Heads inclined 15 degrees.

X101.

S.A.E. STANDARD MILLED OPENINGS

$\frac{5}{16}$ " x $\frac{3}{8}$ ", $\frac{3}{8}$ " x $\frac{7}{16}$ ", $\frac{7}{16}$ " x $\frac{1}{2}$ ", $\frac{1}{2}$ " x $\frac{9}{16}$ ", $\frac{9}{16}$ " x $\frac{5}{8}$ ", $\frac{5}{8}$ " x $\frac{3}{4}$ ", $\frac{3}{4}$ " x $\frac{7}{8}$ ", $\frac{7}{8}$ " x $\frac{15}{16}$ ", $\frac{15}{16}$ " x 1",
 $\frac{15}{16}$ " x $1\frac{1}{16}$ ", $1\frac{1}{16}$ " x $1\frac{1}{8}$ ".

ADJUSTABLE EXPANDING REAMERS



X103.

Full Range, $\frac{1}{4}$ " to 3".

Spare Blades and Nuts Available.

CHANNEL TOP KIT

NO. 333 AND NO. 444



X105.

Available in "Keystone" or "Hercules."

Sockets made of case hardened, heat treated steel.

Eight socket sizes: $\frac{7}{16}$ ", $\frac{1}{2}$ ", $\frac{9}{16}$ ", $\frac{5}{8}$ ", $1\frac{1}{16}$ ", $\frac{3}{4}$ ", $\frac{7}{8}$ ", $1\frac{5}{16}$ ".


Handle $\frac{1}{2}$ " hexagon steel, 8" long, attaches to socket with spring and ball snap.

Channel top, rattle-free case of heavy gauge pressed steel, nickel plated and highly polished.

No. 444 is the same as No. 333, but with Whitworth sizes: $\frac{3}{8}$ ", $\frac{7}{16}$ ", $\frac{1}{2}$ ", $\frac{5}{8}$ ", $\frac{3}{4}$ ", $\frac{7}{8}$ ", $1\frac{1}{8}$ ", $1\frac{5}{8}$ ".

THE RATCHET KIT

NO. 555, S.A.E., AND NO. 555W., WHITWORTH



X106.

Available in "Keystone" or "Hercules."

Sockets made of case hardened, heat treated steel.

Eight socket sizes: $\frac{7}{16}$ ", $\frac{1}{2}$ ", $\frac{9}{16}$ ", $\frac{5}{8}$ ", $1\frac{1}{16}$ ", $\frac{3}{4}$ ", $\frac{7}{8}$ ", $1\frac{5}{16}$ ".
 Ratchet handle, 7" drop forged steel, heat treated pawl, 36° swing turns the nut.
 Hexagon handle, 8" long, may be used with ratchet handle as long adapter.

Channel top case, nickel plated and highly polished.



X102.

Wrench Size: $\frac{5}{8}$ " x $\frac{9}{16}$ ".

**LECTROLITE STARTER AND
MANIFOLD WRENCH**

LECTROLITE

BOX WRENCHES

SOLD SINGLY OR IN SETS



X104.

CHROME VANADIUM DOUBLE END

Twelve Point Box Type Wrench.


Full Set of 6 Wrenches.

Wrench Size: $\frac{5}{8}$ " x $\frac{7}{16}$ ", $\frac{3}{4}$ " x $\frac{9}{16}$ ", $\frac{7}{8}$ " x $1\frac{1}{16}$ ",
 $\frac{15}{16}$ " x $1\frac{1}{8}$ ", $1\frac{1}{8}$ " x $1\frac{1}{4}$ ", $1\frac{1}{4}$ " x $1\frac{1}{2}$ ".

Also in set of 5 omitting $1\frac{1}{8}$ " x $1\frac{1}{4}$ ".

And in Whitworth and B.S.F. Sizes—Sets $\frac{1}{2}$ " to $1\frac{1}{8}$ " Whitworth.

**NEW BRITAIN OR
BLACKHAWK
SOCKET WRENCH SETS**



X107.

Obtainable in the following sizes:—


14, 25, 36 and 40 Pieces.

Any size made up to requirements.

WE STOCK EVERY REQUIREMENT FOR WASHING AND POLISHING CARS

SUPERETTE AIR VACUUM OPERATED WARNING SIGNALS

No tank, check valve or other accessories are required. The operation of these horns is 100% automatic. Installation is simple, any good mechanic will be able to install these horns in less than half an hour.



X108.
SUPERETTE, Sr.

Finish: Polished Lacquer. Dimensions: Length 14½", width 7½", height 4½".




X109.
SUPERTONE
STRAIGHT SINGLE MODEL

(For under hood installation.)

Finish: Polychrome Lacquer.

Dimensions: Length 18½", diameter 5".

Equipped with universal bracket for installing the horn on radiator support rod of the car, manual control for operating horn from steering column, necessary hose and fittings.



Assembled.

HOSE
CLAMPS

X110.

Sizes: 1" to 4½".

Apart.

SAL-AMBER High Quality MOTOR OIL

A pure oil obtainable in any grade for Internal Combustion Engines. Also in lower grades for industrial purposes. Sal-Amber Oils are extensively used in Motor Car, Steam, Gas and Oil Engines, and for Factory and Agricultural Machinery. Sal-Amber is stocked in the following grades:—"E" Light, "A" Medium, "AH" Medium Heavy, "BB" Heavy, "B" Extra Heavy.

Also Gear Oil . . . Cup, Pressure Gun, and Graphite Lubricants Oil-Dag Colloidal Graphite




X111.
PUMP WASHERS
1" to 2".



"Rega"
Hand Power
Spraying
Outfit


X113.

For applying all kinds of liquids to all kinds of surfaces. Easy to operate, very efficient.



X112.
"REGA"
QUADRUPLE PUMP
Delivers a large volume of air quickly at high pressure.

THE "REGA" SPRAY PISTOL
(PATENT)




PATENTED.
No. 19213/29

Also Fantail Type for Air Pressure. Pistol Capacity, ½ pint.

"REGA" HIGH CLASS

X114.

Very popular. Compact for small tool boxes. Brass Cylinder, 20" x 1½".




REGA "DED-EZE" TYRE PUMP

"DED-EZE" PUMP
X115.

(Double Acting)
Simple, Durable, Efficient
and Light in Weight.

FLEXIBLE METAL TUBING FOR ALL PURPOSES

X116.



Asbestos-Packed Exhaust Flexible Tubing. Unpacked Flexible Tubing for Conduit, etc. Braided Flexible Tubing for Oil and Petrol Pipes, etc. Grease Gun Flex. Flexible Conduit (Brass, Nickel Plated). Vacuum Cleaner Suction Tubing (Black and White Cotton Braided).


PLEASE WRITE TO US FOR ANY ACCESSORIES NOT LISTED IN THIS SECTION

MARPLES' FIRMER CHISELS

T1.

Beech Handled

Sizes: 1/16", 1/8", 3/16", 1/4", 5/16", 3/8", 7/16", 1/2", 5/8", 3/4", 7/8", 1", 1 1/4", 1 1/2", 1 3/4", 2".



FIRMER CHISELS, MARPLES'

T2.

Bevelled Edge, Octagon Boxwood Handle

Sizes: 1/16", 1/8", 3/16", 1/4", 5/16", 3/8", 7/16", 1/2", 5/8", 3/4", 7/8", 1", 1 1/4", 1 1/2", 1 3/4", 2"



MARPLES' REGISTERED CHISELS

T3.

Double Hooped Ash Handle

Sizes: 1/4", 3/8", 1/2", 5/8", 3/4", 7/8", 1", 1 1/4", 1 1/2", 1 3/4", 2"



SOCKET FIRMER CHISELS

T4. MARPLES'

Light, Ash Handled, Iron Hooped

Sizes: 1/4", 5/16", 3/8", 7/16", 1/2", 5/8", 3/4", 7/8", 1", 1 1/4", 1 1/2", 1 3/4", 2"


Woodworkers' and Builders' Tools



T5. BUTT CHISELS, MARPLES'

Ash Handled, Leather Tipped

Sizes: 3/8", 1/2", 5/8", 3/4", 7/8", 1", 1 1/4", 1 1/2", 1 3/4", 2"




T6. FIRMER GOUGES, MARPLES'

Round Beech Handled, Ground Outside

CHIP-CARVING KNIVES


T7.

All set and sharpened ready for use



For METALWORKERS' TOOLS

See Pages 156 to 181



Cork Rubbers for Joiners and Cabinet Makers

T8.

STRIKING KNIVES, Ward & Payne's

T9.



CARPENTERS' LEAD PENCILS

Dixon's Hard Black Graphite Framers


—will not scratch.

Polished Cedar or Red and Black

GUARANTEED QUALITY!

CHIP-CARVING TOOLS

T10.



A—Veiner, B—Chisel, C—Porting Tool, D—Gouge


DANKS OFFER QUALITY TOOLS AT COMPETITIVE PRICES

HAND AND RIP SAWS




T11.

Disston's "D8" SKFW Back. Refined Crucible Steel Blades. Apple Handles, 5 Brass Screws. 6624: Panel, 8-12 points, 16", 18", 20", 22", 24". 6625: Hand, 26", 5-8 points. 6626: Rip, 28", 3-4 points.




T12.

Sirdar Skew Back. Spring Steel Apple Handle, 4 Brass Screws. Panel, 10-12 pts., 22". Hand, 26", 5-8 pts. Rip, 28", 3-4 pts.




T13.

Spear & Jackson's "Spearior" Brand. Standard line improved Crucible Steel. 20", 22", 24", 26", 28".




T14.

Disston's Buck or Tenon Saws. Crucible steel Apple handles. 3 Brass Screws. Blued back, 8", 10", 12", 14". Also Spear & Jackson's, as above.



T15.


Tyzack's Bowden Tenon Saws, for household use 10", 12", 14".



T16.

Keyhole Saw and Pad, with adjustable blade. Rd. hardwood handle. 10" blade.

BUCK AND BOW SAWS



T17.

BUCK SAWS

30" x 2 1/2" blades. Disston's Peg Tooth or Lightning Tooth and Jackson's.



T18.


MARPLES' TURNING BOW SAWS
Beech frame, bow handle. 10", 12", 14".

T19.

NEST OF SAWS

One each, keyhole compass and pruning. Disston's, Spears & Jackson's, Tyzack's and Sirdar.

CROSSCUT SAWS




T20.

Disston's Plain or Peg Tooth. 2 Gauges thinner on back than on tooth edge. Sizes: 5', 5 1/2', 6', 6 1/2'.

**DISSTON'S CROSSCUT SAW
T21.**



Tasmanian Tooth. 4 Gauges thinner on Back than on Tooth Edge. Sizes: 5', 5 1/2', 6', 6 1/2'.



T22.


DISSTON'S OR PEG AND RAKER ONE-MAN CROSSCUT SAW




T23.

EXTRA HANDLES FOR ABOVE:

T24.



Brass Back Dovetail Saw. British. Sizes: 6", 7", 8".





T25.
STEEL SAW SETS
Popular make.

TAINTOR HAND SAW SET

T26.

With guide.

Also with wood handles.




T27.

Disston's Kitchen Saws. Round back, bright blade, 5" wide. 14".




T28.

Keyhole Saw and Pad. Combination Keyhole, Saw Pad and Screwdriver.




OUR WAREHOUSE IS CENTRAL AND EASY TO FIND



**DISSTON'S
IMPROVED
SAW CLAMP**
T29.

By the use of this Clamp a Saw may be held at any angle, or square, as the operator may desire.
9" Jaw. Japanned.




**Disston's
Saw
Clamp**


T30.

This cut shows a saw and the guide in proper position for filing the first side. There are three marks on one of the hubs of the swivel attachment, and one mark on the other. One of the three marks shows when it is in position for the first side, and the other designates when it is in position for filing the other side. The third, or centre mark, shows when it is in position for filing Rip Saws. To obtain the correct position loosen the wing nut and move the guide around to the point desired; after tightening wing nut, loosen screw in file handle and adjust the file for the shape of tooth wanted. A good way is to select a tooth of correct shape and set file down into it, tighten set screw in handle, then file a tooth to see if the shape suits. If not, turn the file a little to the right or left and try another tooth until the proper shape is obtained. Then file every other tooth. When one side is filed, reverse saw and attachment and file the other teeth. For Rip Saws, place the file at right angles with the saw and file every tooth. Always keep the file as near horizontal as possible.

The Stanley "Pistol Grip" Adjustable Saw Set
T37.



This Saw Set embodies several unique and important features not heretofore seen in tools of this description. The shape of the Body and Handle enables the user to operate the tool with the least possible exertion, and the Saw is held firmly against the gauge while the tooth is being set. It can be readily adjusted by means of the knurled thumb screw. The same adjustment can be easily obtained for duplicate work. The tool is designed so that the Saw teeth are in full view. This enables the user to quickly adjust the tool to the tooth to be set. The plunger and anvil are made of tool steel—hardened and tempered. All parts are carefully machined and are interchangeable. The tool is given a fine black finish.




**T38.
Miller Falls
Coping Saw
No. 40**



**T39.
Wire Frame Coping Saw**




**T40. Extra Blades for Miller Falls Coping Saw
in Loop or Pin Pattern**




Disston's Triumph Saw Sets

- T31.—For hand, back, web and butchers' saw blades from 10 to 16 pt.
- T32.—For hand, back, web and narrow band saws; 10 pts. to the inch and coarser.
- T33.—For circular and crosscut saws 14 g. and lighter.
- T34.—For circular and crosscut saws 12 g. and lighter.

Morrill's Special Saw Set for Hand Saws
T35.




Morrill's Patent Saw Sets




T36.

- No. 3.—For Single Tooth Crosscut.
- No. 4.—For Lightning Tooth Crosscut.

For
Highest
Quality
and
Keenest
Values



**T41.
Avia Fret Saw Blades**



**T41a.
Weller or Piercing Saw Frames
Adjustable to take Blades of various
lengths**

WE SUPPLY HIGH GRADE TOOLS AT REASONABLE PRICES

Stanley's Adjustable Planes



Smoothing Plane

T42.

Size	Length	Cutter
3	8"	19"
4	9"	21"
4½	10"	23"



T43. Jack Planes

Size	Length	Cutter
5	14"	21"
5½	15"	23"



Carriage Makers' Rabbet Planes

T44.

An excellent tool for a wide variety of jobs. Specially designed for heavy work.

Size	Length	Cutter
10½	9"	21"
10	13"	23"
10½	13"	25"



Fore and Jointer Planes

T45.

Plain or Corrugated Bottom.

Size	Length	Cutter
6	18"	28"
7	22"	30"
8	24"	32"



Stanley "Bed Rock" Adjustable Planes

T46.

	Size	Length	Cutter
Smooth—	604	9"	2"
	604½	10"	2½"
Jack—	605	14"	2"
	605½	15"	2½"
Jointer—	607	22"	28"




Bull-nose Rabbet Planes

T47.

Designed specially for Fine Cabinet Work where accuracy is most essential. Will lie perfectly flat on either side—the sides and bottom being square with each other—and can be used either right or left. Both Cutter and Throat Opening are adjustable.

No. 90.—Nickel Plated. 4" Long 1" Cutter.



Side Rabbet Planes

T48.

For Side Rabbeting and Trimming Mouldings, Dados, and Grooves of all kinds, this Plane is most useful.

Will work close up into corners. Nos. 98 and 99. Length, 4". Cutter, 1".



Duplex Rabbeter and Fillester

T49.

This Plane becomes a Rabbet Plane by removing the arm to which the fence is secured. Can also be used as a Bull-nose Rabbet Plane. Fitted with a Spur for working across the grain, and has also a Depth Gauge.

No. 78.—8½" Long. 1½" Cutter.



Improved Rabbet Planes

T50.

Lies perfectly flat on either side. Can be used with right or left hand equally well while planing into corners or against vertical surfaces. Fitted with Depth Gauge and

Size	Length	Cutter
190		1½"
191	all 8"	1½"
192		1"



T51.—Record Jack Planes.

T52.—Record Block Planes.

T53.—Record Smooth Planes.

T54.—Record Rabbet Planes.

T55.—Record Side Rabbet Planes.

RECORD PLANES

We also stock a complete range of the English-made RECORD PLANES

T56.—Record Router Planes.

T57.—Record Duplex Rabbet.

T58.—Record Bull Nose.



T59.—Record Circular.

T60.—Record Light Comb.

T61.—Record Plough.

T62.—Record Multiplane.


WE CATER FOR THE TRADESMAN AND HOME CARPENTER




T63.

Stanley Block Plane

No. 110.—7½" Long, 1½" Cutter.



T64.

 Adjustable, 7½" Long, 1½" Cutter.
 A Plane of exceptional value No. 220


T65.

 5½" Long, 1½" Cutter.
 Fine adjustment. No. 103

Double Ender

T66.

 Has two Slots and two Cutter Seats, making
 it applicable as a Block or Bull-nose Plane.
 No. 130, 8" Long, 1½" Cutter.



No. 140

T67.

**Stanley Rabbet and
Block Plane**

 A detachable side will easily
 change it from a Block Plane
 to a Rabbet Plane. The
 Cutter is adjustable endwise,
 and set on a skew.

7" Long, 1½" Cutter.




T68.

Stanley or Record Combination Plane

 Main Stock and Sliding Section are so arranged that
 cutters of different widths can be used. Fitted with
 adjustable Fence or Guide and Depth Gauge, also with
 Spurs for use in working across the grain, and can be
 used Right or Left Hand.

 This Plane combines seven tools in one—Beading and
 Centre Beading, Rabbet and Filletster, Dado, Plow,
 Matching, Sash, and a Slitting Plane. It has Seven
 Beading Tools—1, 3/16, 1/2, 5/16, 3/4, 7/16, 1; Ten Plow
 and Dado Bits—1, 3/16, 1/2, 5/16, 3/4, 7/16, 1, 1 1/2, 2, 3; a
 Slitting Blade, a Tonguing Tool, and a Sash Tool.

No. 45.—Nickel Finish, Rosewood Handle and Fences.

**Stanley
UNIVERSAL
PLANE**


T70.

COMPLETE WITH 52 TOOLS, BITS, ETC.

 This tool in the hands of an ordinary Carpenter can be used for all kinds of
 work covered by a full assortment of so-called Fancy Planes.

SPECIFICATIONS (See Diagram).

 This Plane is Nickel-plated, the 52 Cutters are arranged in four separate Cases,
 and the entire Outfit is packed in a neat Wooden Box. This Plane consists of:—
 A Main Stock (A) with two sets of Transverse Sliding Arms, a Depth Gauge
 (F) adjusted by a screw, and a Slitting Cutter with Stop.


 A Sliding Section (B) with a Vertically Adjustable Bottom.
 The Auxiliary Centre Bottom (C) is to be placed in front of the Cutter as an
 extra support, or stop when needed. This bottom is adjustable both vertically
 and laterally.

 Fences D and E.—Fence D has a lateral adjustment, by means of a Screw,
 for extra fine work. The Fences can be used on either side of the Plane,
 and the Rosewood Guides can be tilted to any desired angle, up to 45 deg.,
 by loosening the Screws on the Face. Fence E can be reversed for Centre
 Beading Wide Boards.


 An Adjustable Stop, to be used in Beading the Edges of Matched Boards,
 is inserted on the left-hand side of Sliding Section (B).

No. 55.—Price Complete with 52 Tools, Bits, etc.

 This Plane
 takes the place
 of a
**FULL
RANGE**
 of so-called
 Fancy Planes.

**ORDER
YOURS
AT ONCE!**


Arranged as Moulding Plane.




Open Throat.

T69.

**Woodworker's Router
Planes**

 Adapted to surface the bottom of
 Grooves, Panels, Depressions, etc.,
 below the general surface of any
 woodwork. Invaluable to Cabinet
 Makers, Stairbuilders, Patternmakers,
 etc. Supplied with two Steel Bits—
 1/4" and 3/8".


No. 71.—Nickel-finish.



Closed Throat.

GOOD TOOLS ARE AN INVESTMENT

**Mathieson's
Wood Planes**




Smoothing Plane
T71.
Sizes: 2", 2 1/4", 2 1/2".



Smoothing Plane
T72.
Sizes: 2", 2 1/4", 2 1/2"


**Mathieson's Wood
Planes**
T73.

Red Beech Oiled Jack Plane.
Sizes: 2", 2 1/4", 2 1/2".



Trying Plane
T75.

22" x 2 1/4".




**Mathieson's Skew Eyed
Hollows and Rounds**
Red Beech, Oiled.



T74.

Sizes: Nos. 2, 4, 6, 8, 10, 12, 14, 16, 18.
In Half-sets, 2 1/8".



Plow, Beading and Matching Plane
T79.

This is a very handy tool for light work. It consists of a main stock, carrying a spur and a depth gauge, and forming a support for one side of the cutter; a sliding section, carrying a spur and forming a support for the other side of the cutter, and a fence with a 6" adjustment. The handle is metal, being a part of the main stock. The cutters comprise 9 plow and dado bits, 1/4", 3/16", 1/8", 5/16", 3/8", 7/16", 1/2", 5/8" and 3/4"; 7 beading tools, 1/4", 3/16", 1/8", 5/16", 3/8", 7/16" and 1/2"; and a 1/4" tonguing tool. 9 1/2" Long. Nickel Plated. 17 Cutters.


Berg's and Stanley's Plane Irons



T80.

Sizes: 1 1/2", 2", 2 1/4", 2 1/2", 2 3/4".


German Jack Irons



T81. Sizes: 1 1/2", 1 3/4", 1 7/8", 2".

German Pattern Jack Planes
T77.

Sizes: 1 1/2", 1 3/4", 2". Red Beech. Mathieson's.



T82

Sizes: 1", 1 1/4", 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2", 2 3/4", 3", 3 1/4", 3 1/2", 3 3/4", 4", 4 1/4", 4 1/2", 4 3/4", 5", 5 1/4", 5 1/2", 5 3/4", 6", 6 1/4", 6 1/2", 6 3/4", 7", 7 1/4", 7 1/2", 7 3/4", 8", 8 1/4", 8 1/2", 8 3/4", 9", 9 1/4", 9 1/2", 9 3/4", 10", 10 1/4", 10 1/2", 10 3/4", 11", 11 1/4", 11 1/2", 11 3/4", 12", 12 1/4", 12 1/2", 12 3/4", 13", 13 1/4", 13 1/2", 13 3/4", 14", 14 1/4", 14 1/2", 14 3/4", 15", 15 1/4", 15 1/2", 15 3/4", 16", 16 1/4", 16 1/2", 16 3/4", 17", 17 1/4", 17 1/2", 17 3/4", 18", 18 1/4", 18 1/2", 18 3/4", 19", 19 1/4", 19 1/2", 19 3/4", 20", 20 1/4", 20 1/2", 20 3/4", 21", 21 1/4", 21 1/2", 21 3/4", 22", 22 1/4", 22 1/2", 22 3/4", 23", 23 1/4", 23 1/2", 23 3/4", 24", 24 1/4", 24 1/2", 24 3/4", 25", 25 1/4", 25 1/2", 25 3/4", 26", 26 1/4", 26 1/2", 26 3/4", 27", 27 1/4", 27 1/2", 27 3/4", 28", 28 1/4", 28 1/2", 28 3/4", 29", 29 1/4", 29 1/2", 29 3/4", 30", 30 1/4", 30 1/2", 30 3/4", 31", 31 1/4", 31 1/2", 31 3/4", 32", 32 1/4", 32 1/2", 32 3/4", 33", 33 1/4", 33 1/2", 33 3/4", 34", 34 1/4", 34 1/2", 34 3/4", 35", 35 1/4", 35 1/2", 35 3/4", 36", 36 1/4", 36 1/2", 36 3/4", 37", 37 1/4", 37 1/2", 37 3/4", 38", 38 1/4", 38 1/2", 38 3/4", 39", 39 1/4", 39 1/2", 39 3/4", 40", 40 1/4", 40 1/2", 40 3/4", 41", 41 1/4", 41 1/2", 41 3/4", 42", 42 1/4", 42 1/2", 42 3/4", 43", 43 1/4", 43 1/2", 43 3/4", 44", 44 1/4", 44 1/2", 44 3/4", 45", 45 1/4", 45 1/2", 45 3/4", 46", 46 1/4", 46 1/2", 46 3/4", 47", 47 1/4", 47 1/2", 47 3/4", 48", 48 1/4", 48 1/2", 48 3/4", 49", 49 1/4", 49 1/2", 49 3/4", 50", 50 1/4", 50 1/2", 50 3/4", 51", 51 1/4", 51 1/2", 51 3/4", 52", 52 1/4", 52 1/2", 52 3/4", 53", 53 1/4", 53 1/2", 53 3/4", 54", 54 1/4", 54 1/2", 54 3/4", 55", 55 1/4", 55 1/2", 55 3/4", 56", 56 1/4", 56 1/2", 56 3/4", 57", 57 1/4", 57 1/2", 57 3/4", 58", 58 1/4", 58 1/2", 58 3/4", 59", 59 1/4", 59 1/2", 59 3/4", 60", 60 1/4", 60 1/2", 60 3/4", 61", 61 1/4", 61 1/2", 61 3/4", 62", 62 1/4", 62 1/2", 62 3/4", 63", 63 1/4", 63 1/2", 63 3/4", 64", 64 1/4", 64 1/2", 64 3/4", 65", 65 1/4", 65 1/2", 65 3/4", 66", 66 1/4", 66 1/2", 66 3/4", 67", 67 1/4", 67 1/2", 67 3/4", 68", 68 1/4", 68 1/2", 68 3/4", 69", 69 1/4", 69 1/2", 69 3/4", 70", 70 1/4", 70 1/2", 70 3/4", 71", 71 1/4", 71 1/2", 71 3/4", 72", 72 1/4", 72 1/2", 72 3/4", 73", 73 1/4", 73 1/2", 73 3/4", 74", 74 1/4", 74 1/2", 74 3/4", 75", 75 1/4", 75 1/2", 75 3/4", 76", 76 1/4", 76 1/2", 76 3/4", 77", 77 1/4", 77 1/2", 77 3/4", 78", 78 1/4", 78 1/2", 78 3/4", 79", 79 1/4", 79 1/2", 79 3/4", 80", 80 1/4", 80 1/2", 80 3/4", 81", 81 1/4", 81 1/2", 81 3/4", 82", 82 1/4", 82 1/2", 82 3/4", 83", 83 1/4", 83 1/2", 83 3/4", 84", 84 1/4", 84 1/2", 84 3/4", 85", 85 1/4", 85 1/2", 85 3/4", 86", 86 1/4", 86 1/2", 86 3/4", 87", 87 1/4", 87 1/2", 87 3/4", 88", 88 1/4", 88 1/2", 88 3/4", 89", 89 1/4", 89 1/2", 89 3/4", 90", 90 1/4", 90 1/2", 90 3/4", 91", 91 1/4", 91 1/2", 91 3/4", 92", 92 1/4", 92 1/2", 92 3/4", 93", 93 1/4", 93 1/2", 93 3/4", 94", 94 1/4", 94 1/2", 94 3/4", 95", 95 1/4", 95 1/2", 95 3/4", 96", 96 1/4", 96 1/2", 96 3/4", 97", 97 1/4", 97 1/2", 97 3/4", 98", 98 1/4", 98 1/2", 98 3/4", 99", 99 1/4", 99 1/2", 99 3/4", 100", 100 1/4", 100 1/2", 100 3/4", 101", 101 1/4", 101 1/2", 101 3/4", 102", 102 1/4", 102 1/2", 102 3/4", 103", 103 1/4", 103 1/2", 103 3/4", 104", 104 1/4", 104 1/2", 104 3/4", 105", 105 1/4", 105 1/2", 105 3/4", 106", 106 1/4", 106 1/2", 106 3/4", 107", 107 1/4", 107 1/2", 107 3/4", 108", 108 1/4", 108 1/2", 108 3/4", 109", 109 1/4", 109 1/2", 109 3/4", 110", 110 1/4", 110 1/2", 110 3/4", 111", 111 1/4", 111 1/2", 111 3/4", 112", 112 1/4", 112 1/2", 112 3/4", 113", 113 1/4", 113 1/2", 113 3/4", 114", 114 1/4", 114 1/2", 114 3/4", 115", 115 1/4", 115 1/2", 115 3/4", 116", 116 1/4", 116 1/2", 116 3/4", 117", 117 1/4", 117 1/2", 117 3/4", 118", 118 1/4", 118 1/2", 118 3/4", 119", 119 1/4", 119 1/2", 119 3/4", 120", 120 1/4", 120 1/2", 120 3/4", 121", 121 1/4", 121 1/2", 121 3/4", 122", 122 1/4", 122 1/2", 122 3/4", 123", 123 1/4", 123 1/2", 123 3/4", 124", 124 1/4", 124 1/2", 124 3/4", 125", 125 1/4", 125 1/2", 125 3/4", 126", 126 1/4", 126 1/2", 126 3/4", 127", 127 1/4", 127 1/2", 127 3/4", 128", 128 1/4", 128 1/2", 128 3/4", 129", 129 1/4", 129 1/2", 129 3/4", 130", 130 1/4", 130 1/2", 130 3/4", 131", 131 1/4", 131 1/2", 131 3/4", 132", 132 1/4", 132 1/2", 132 3/4", 133", 133 1/4", 133 1/2", 133 3/4", 134", 134 1/4", 134 1/2", 134 3/4", 135", 135 1/4", 135 1/2", 135 3/4", 136", 136 1/4", 136 1/2", 136 3/4", 137", 137 1/4", 137 1/2", 137 3/4", 138", 138 1/4", 138 1/2", 138 3/4", 139", 139 1/4", 139 1/2", 139 3/4", 140", 140 1/4", 140 1/2", 140 3/4", 141", 141 1/4", 141 1/2", 141 3/4", 142", 142 1/4", 142 1/2", 142 3/4", 143", 143 1/4", 143 1/2", 143 3/4", 144", 144 1/4", 144 1/2", 144 3/4", 145", 145 1/4", 145 1/2", 145 3/4", 146", 146 1/4", 146 1/2", 146 3/4", 147", 147 1/4", 147 1/2", 147 3/4", 148", 148 1/4", 148 1/2", 148 3/4", 149", 149 1/4", 149 1/2", 149 3/4", 150", 150 1/4", 150 1/2", 150 3/4", 151", 151 1/4", 151 1/2", 151 3/4", 152", 152 1/4", 152 1/2", 152 3/4", 153", 153 1/4", 153 1/2", 153 3/4", 154", 154 1/4", 154 1/2", 154 3/4", 155", 155 1/4", 155 1/2", 155 3/4", 156", 156 1/4", 156 1/2", 156 3/4", 157", 157 1/4", 157 1/2", 157 3/4", 158", 158 1/4", 158 1/2", 158 3/4", 159", 159 1/4", 159 1/2", 159 3/4", 160", 160 1/4", 160 1/2", 160 3/4", 161", 161 1/4", 161 1/2", 161 3/4", 162", 162 1/4", 162 1/2", 162 3/4", 163", 163 1/4", 163 1/2", 163 3/4", 164", 164 1/4", 164 1/2", 164 3/4", 165", 165 1/4", 165 1/2", 165 3/4", 166", 166 1/4", 166 1/2", 166 3/4", 167", 167 1/4", 167 1/2", 167 3/4", 168", 168 1/4", 168 1/2", 168 3/4", 169", 169 1/4", 169 1/2", 169 3/4", 170", 170 1/4", 170 1/2", 170 3/4", 171", 171 1/4", 171 1/2", 171 3/4", 172", 172 1/4", 172 1/2", 172 3/4", 173", 173 1/4", 173 1/2", 173 3/4", 174", 174 1/4", 174 1/2", 174 3/4", 175", 175 1/4", 175 1/2", 175 3/4", 176", 176 1/4", 176 1/2", 176 3/4", 177", 177 1/4", 177 1/2", 177 3/4", 178", 178 1/4", 178 1/2", 178 3/4", 179", 179 1/4", 179 1/2", 179 3/4", 180", 180 1/4", 180 1/2", 180 3/4", 181", 181 1/4", 181 1/2", 181 3/4", 182", 182 1/4", 182 1/2", 182 3/4", 183", 183 1/4", 183 1/2", 183 3/4", 184", 184 1/4", 184 1/2", 184 3/4", 185", 185 1/4", 185 1/2", 185 3/4", 186", 186 1/4", 186 1/2", 186 3/4", 187", 187 1/4", 187 1/2", 187 3/4", 188", 188 1/4", 188 1/2", 188 3/4", 189", 189 1/4", 189 1/2", 189 3/4", 190", 190 1/4", 190 1/2", 190 3/4", 191", 191 1/4", 191 1/2", 191 3/4", 192", 192 1/4", 192 1/2", 192 3/4", 193", 193 1/4", 193 1/2", 193 3/4", 194", 194 1/4", 194 1/2", 194 3/4", 195", 195 1/4", 195 1/2", 195 3/4", 196", 196 1/4", 196 1/2", 196 3/4", 197", 197 1/4", 197 1/2", 197 3/4", 198", 198 1/4", 198 1/2", 198 3/4", 199", 199 1/4", 199 1/2", 199 3/4", 200", 200 1/4", 200 1/2", 200 3/4, 201", 201 1/4", 201 1/2", 201 3/4, 202", 202 1/4", 202 1/2", 202 3/4, 203", 203 1/4", 203 1/2", 203 3/4, 204", 204 1/4", 204 1/2", 204 3/4, 205", 205 1/4", 205 1/2", 205 3/4, 206", 206 1/4", 206 1/2", 206 3/4, 207", 207 1/4", 207 1/2", 207 3/4, 208", 208 1/4", 208 1/2", 208 3/4, 209", 209 1/4", 209 1/2", 209 3/4, 210", 210 1/4", 210 1/2", 210 3/4, 211", 211 1/4", 211 1/2", 211 3/4, 212", 212 1/4", 212 1/2", 212 3/4, 213", 213 1/4", 213 1/2", 213 3/4, 214", 214 1/4", 214 1/2", 214 3/4, 215", 215 1/4", 215 1/2", 215 3/4, 216", 216 1/4", 216 1/2", 216 3/4, 217", 217 1/4", 217 1/2", 217 3/4, 218", 218 1/4", 218 1/2", 218 3/4, 219", 219 1/4", 219 1/2", 219 3/4, 220", 220 1/4", 220 1/2", 220 3/4, 221", 221 1/4", 221 1/2", 221 3/4, 222", 222 1/4", 222 1/2", 222 3/4, 223", 223 1/4", 223 1/2", 223 3/4, 224", 224 1/4", 224 1/2", 224 3/4, 225", 225 1/4", 225 1/2", 225 3/4, 226", 226 1/4", 226 1/2", 226 3/4, 227", 227 1/4", 227 1/2", 227 3/4, 228", 228 1/4", 228 1/2", 228 3/4, 229", 229 1/4", 229 1/2", 229 3/4, 230", 230 1/4", 230 1/2", 230 3/4, 231", 231 1/4", 231 1/2", 231 3/4, 232", 232 1/4", 232 1/2", 232 3/4, 233", 233 1/4", 233 1/2", 233 3/4, 234", 234 1/4", 234 1/2", 234 3/4, 235", 235 1/4", 235 1/2", 235 3/4, 236", 236 1/4", 236 1/2", 236 3/4, 237", 237 1/4", 237 1/2", 237 3/4, 238", 238 1/4", 238 1/2", 238 3/4, 239", 239 1/4", 239 1/2", 239 3/4, 240", 240 1/4", 240 1/2", 240 3/4, 241", 241 1/4", 241 1/2", 241 3/4, 242", 242 1/4", 242 1/2", 242 3/4, 243", 243 1/4", 243 1/2", 243 3/4, 244", 244 1/4", 244 1/2", 244 3/4, 245", 245 1/4", 245 1/2", 245 3/4, 246", 246 1/4", 246 1/2", 246 3/4, 247", 247 1/4", 247 1/2", 247 3/4, 248", 248 1/4", 248 1/2", 248 3/4, 249", 249 1/4", 249 1/2", 249 3/4, 250", 250 1/4", 250 1/2", 250 3/4, 251", 251 1/4", 251 1/2", 251 3/4, 252", 252 1/4", 252 1/2", 252 3/4, 253", 253 1/4", 253 1/2", 253 3/4, 254", 254 1/4", 254 1/2", 254 3/4, 255", 255 1/4", 255 1/2", 255 3/4, 256", 256 1/4", 256 1/2", 256 3/4, 257", 257 1/4", 257 1/2", 257 3/4, 258", 258 1/4", 258 1/2", 258 3/4, 259", 259 1/4", 259 1/2", 259 3/4, 260", 260 1/4", 260 1/2", 260 3/4, 261", 261 1/4", 261 1/2", 261 3/4, 262", 262 1/4", 262 1/2", 262 3/4, 263", 263 1/4", 263 1/2", 263 3/4, 264", 264 1/4", 264 1/2", 264 3/4, 265", 265 1/4", 265 1/2", 265 3/4, 266", 266 1/4", 266 1/2", 266 3/4, 267", 267 1/4", 267 1/2", 267 3/4, 268", 268 1/4", 268 1/2", 268 3/4, 269", 269 1/4", 269 1/2", 269 3/4, 270", 270 1/4", 270 1/2", 270 3/4, 271", 271 1/4", 271 1/2", 271 3/4, 272", 272 1/4", 272 1/2", 272 3/4, 273", 273 1/4", 273 1/2", 273 3/4, 274", 274 1/4", 274 1/2", 274 3/4, 275", 275 1/4", 275 1/2", 275 3/4, 276", 276 1/4", 276 1/2", 276 3/4, 277", 277 1/4", 277 1/2", 277 3/4, 278", 278 1/4", 278 1/2", 278 3/4, 279", 279 1/4", 279 1/2", 279 3/4, 280", 280 1/4", 280 1/2", 280 3/4, 281", 281 1/4", 281 1/2", 281 3/4, 282", 282 1/4", 282 1/2", 282 3/4, 283", 283 1/4", 283 1/2", 283 3/4, 284", 284 1/4", 284 1/2", 284 3/4, 285", 285 1/4", 285 1/2", 285 3/4, 286", 286 1/4", 286 1/2", 286 3/4, 287", 287 1/4", 287 1/2", 287 3/4, 288", 288 1/4", 288 1/2", 288 3/4, 289", 289 1/4", 289 1/2", 289 3/4, 290", 290 1/4", 290 1/2", 290 3/4, 291", 291 1/4", 291 1/2", 291 3/4, 292", 292 1/4", 292 1/2", 292 3/4, 293", 293 1/4", 293 1/2", 293 3/4, 294", 294 1/4", 294 1/2", 294 3/4, 295", 295 1/4", 295 1/2", 295 3/4, 296", 296 1/4", 296 1/2", 296 3/4, 297", 297 1/4", 297 1/2", 297 3/4, 298", 298 1/4", 298 1/2", 298 3/4, 299", 299 1/4", 299 1/2", 299 3/4, 300", 300 1/4", 300 1/2", 300 3/4, 301", 301 1/4", 301 1/2", 301 3/4, 302", 302 1/4", 302 1/2", 302 3/4, 303", 303 1/4", 303 1/2", 303 3/4, 304", 304 1/4", 304 1/2", 304 3/4, 305", 305 1/4", 305 1/2", 305 3/4, 306", 306 1/4", 306 1/2", 306 3/4, 307", 307 1/4", 307 1/2", 307 3/4, 308", 308 1/4", 308 1/2", 308 3/4, 309", 309 1/4", 309 1/2", 309 3/4, 310", 310 1/4", 310 1/2", 310 3/4, 311", 311 1/4", 311 1/2", 311 3/4, 312", 312 1/4", 312 1/2", 312 3/4, 313", 313 1/4", 313 1/2", 313 3/4, 314", 314 1/4", 314 1/2", 314 3/4, 315", 315 1/4", 315 1/2", 315 3/4, 316", 316 1/4", 316 1/2", 316 3/4, 317", 317 1/4", 317 1/2", 317 3/4, 318", 318 1/4", 318 1/2", 318 3/4, 319", 319 1/4", 319 1/2", 319 3/4, 320", 320 1/4", 320 1/2", 320 3/4, 321", 321 1/4", 321 1/2", 321 3/4, 322", 322 1/4", 322 1/2", 322 3/4, 323", 323 1/4", 323 1/2", 323 3/4, 324", 324 1/4", 324 1/2", 324 3/4, 325", 325 1/4", 325 1/2", 325 3/4, 326", 326 1/4", 326 1/2", 326 3/4, 327", 327 1/4", 327 1/2", 327 3/4, 328", 328 1/4", 328 1/2", 328 3/4, 329", 329 1/4", 329 1/2", 329 3/4, 330", 330 1/4", 330 1/2", 330 3/4, 331", 331 1/4", 331 1/2", 331 3/4, 332", 332 1/4", 332 1/2", 332 3/4, 333", 333 1/4", 333 1/2", 333 3/4, 334", 334 1/4", 334 1/2", 334 3/4, 335", 335 1/4", 335 1/2", 335 3/4, 336", 336 1/4", 336 1/2", 336 3/4, 337", 337 1/4", 337 1/2", 337 3/4, 338", 338 1/4", 338 1/2", 338 3/4, 339", 339 1/4", 339 1/2", 339 3/4, 340




STANLEY'S UNIVERSAL SPOKESHAVE
T86.

Both handles are detachable, so that either one can be screwed into the socket on top of the stock, thus allowing the Spokeshave to be worked into the corners, or panels, as no other Spokeshave can do. Supplied with both a straight and curved bottom.

Polished. Rosewood Handles. 9½" Long. 1½" Cutter.


Marple's Beechwood Spokeshave
T87.



Sizes: 1½", 2", 2½", 3", 4".

Round or Square Fronts
T88.

Also Marple's Plated Spokeshaves (below) in Beechwood or Boxwood.



STANLEY SPOKESHAVES.

T96.

Double Iron. Raised Handles. 10" Long. 2½" Cutter.



STANLEY SPOKESHAVES.

T97.

Double Iron, Raised Handles, Adjustable Mouth. 10" Long. 2½" Cutter.




STANLEY SPOKESHAVES.

T98.


Straight Handles, Double Iron, Adjustable Mouth. 10" Long. 2½" Cutter.

STANLEY ADJUSTABLE SCRAPERS



T89.


Suitable for Veneer, Cabinet and Floor scraping. The angle of blade is adjustable.



Nº 112

T90.

Same form as Bailey Plane, with blade adjustable endwise and for angles. 9" Long. 2½" Blade.




Nº 81

Stanley No. 81 Scraper

T91.

With rosewood face for use on finest cabinet work. Raised handles, pierced for hanging when not in use. Cast in one piece.

10" Long. 2½" Blade. Nickelled.



Case Scraper

T92.

An excellent box scraper, that is also adaptable for planing floors, etc. Malleable Iron. 2" Steel Cutter.

DISSTON'S SAW HANDLES



Tenon Saw
T93.

Without Screws. In sizes up to 18".



Unbored Hand and Rip Saws
T94.

Without Screws. In sizes up to 28".



Nest Saws
T95.

Highest Quality and Keenest Prices.

Full Stocks of Saw Screws to Fit Disston's Handles

Stanley Cabinet Scraper

T99.

Made so that blade may be sprung to a slight curve.



Beechwood Screwdriver Handles

T100. Sizes: 4" to 12".



Beechwood Firmer Chisel Handles

T101. Sizes: ½" to 2".



Octagon Boxwood Chisel Handles

T102. Sizes: ½" to 2".



American Socket Chisel Handles

T103.

Leather Tipped. Sizes: ½" to 2".



QUOTATIONS FOR TOOLS GLADLY GIVEN — WRITE OR 'PHONE

"Yankee" Spiral Ratchet Screwdriver



T104.

This is the standard for Spiral Screwdrivers, and drives or draws screws by pushing on handle, or by a Ratchet movement, or it can be made rigid, as an ordinary Screwdriver. The spindle has two spirals, one right and one left hand with corresponding nuts. To drive screws in, the Shifter is moved to end of slot towards bit; to drive screws out, it is moved to end of slot towards handle.

- T105.—"Yankee" Spiral Ratchet Screwdriver, No. 35.
T106.—"Yankee" Spiral Ratchet Screwdriver, No. 31.
T107.—"Yankee" Spiral Ratchet Screwdriver, No. 30.



Set of Drills

T109.

To suit "Yankee" Spiral Ratchet Screwdrivers.

"Yankee" Quick Return Spiral Ratchet Screwdriver, No. 130

T108.

This is the regular pattern No. 30 with a spring added in handle, which causes the handle to come back for the next push, in driving screws in or out.

It is a "quick return" and more rapid as well as convenient in practical use, than pulling the handle back.

SEE
ALSO
PAGE 164 for
POCKET
SCREWDRIVERS



T114. "Yankee" Plain Screwdrivers

Sizes: 2", 3", 4", 5", 6", 8", 10", 12".




T115. "Yankee" Cabinet Screwdrivers

(Slim Blades.) Sizes: 2½", 3½", 4½", 5½", 6½", 7½", 8½", 9½", 10½", 12½", 15½".



T116. Marple's London Screwdrivers


Sizes: 4", 5", 6", 7", 8", 10", 11", 12", 18".



T117. "Yankee" Ratchet Screwdrivers

Adjustment for right or left hand is made by slide movement in direction of length of blade.

Sizes: 2", 3", 4", 5", 6", 8", 10", 12".




T118. Marple's Round Blade Screwdrivers

Sizes: 4", 5", 6", 7", 8", 10", 11", 12", 18".

"Yankee" Automatic Drill, No. 40

T110.



No. 40.—Has ratchet movement which can be used to advantage in hard or soft wood. Has eight Drill Points, 1/16" to 11/64".

"Yankee" Automatic Drill, No. 44


T111.



No. 44.—The cap on top of Drill has a screw attached to it by revolving which the spring is made longer or shorter, and as a result weaker or stronger, to suit work in hand, and save breakage of drills. Has eight Drill Points, 1/16" to 11/64".

"Yankee" Automatic Drill, No. 41

T112.




No. 41.—Has eight Drill Points, 1/16" to 11/64", which are in plain sight when magazine is open. During the return movement of handle the Drill Point revolves backward to clear chips, etc.

Reciprocating Drill

T113.



This Drill can be used for Steel, Brass and other metals, as well as all varieties of woods. It is so constructed that the Drill runs continuously to the right, during both the forward and backward movement of the driver.



Combined Steel Claw Wrench, Hammer and Chisel

T119.

18" Long.



Mathieson's Carpenters' Pincers

T120.

English. 6", 7", 8", 9".



Carpenters' Mallets

T121.

Beech, 5", 6", 6½".

Nail Pullers

T122.

(At left):

18" Long. Jaws and Shark.
Drop Forged from High-grade Steel.



QUALITY, ECONOMY AND RELIABILITY


HAMMERS



Carpenters' Adze Eye
Claw Hammers

T123.

Cheney's (Handled). Made of Tool
Steel.




Cheney's Adze Eye
Farriers' Hammers

T124.

Highest quality, and the most popular
make.

Shoe Hammers
T125.




Telephone Hammers
T126.

Ideal for Brads, Tacks, etc.



Mohawk Adze Eye Claw
Hammer
T127.

A Reliable Hammer at a Moderate
Price.



Cast Steel Claw
Hammer
T128.

Good Household Quality. Plain Eye.



English Pin Hammers
With Best Polished Ash Handles
T129.

Joiners' Hammers.



French Pattern Cabriolet
Hammers
T130.

Best quality steel, with claw.



T131.
Brades'
Carpenters'
Adze
Nos. 1, 2, 3.

T132.
Brades'
Ship
Adze
Nos. 1, 2, 3.



T133.
Brades'
Wheelers'
Adze

Bronzed
Nos. 1, 2, 3.

Also Gilpins
in types
illustrated.

FOR ENGINEERS' HAMMERS, Etc., See Page 173

Handled Mauls
T134.
Best Timber
Rings



Maul Rings
T135.
Sizes: 4½", 5".



HANDLES

For Axes, Hammers, Sledges, etc.
Highest Quality, Selected Timber



T136.

No. 1. Axe Handles, Second Growth Hickory,
in No. 1 and Extra Quality.
No. 2. Axe Handles, Hickory, Boys'.
No. 4. Claw Hammer Handles.
No. 6. Adze Handles, Hickory, No. 1.

No. 3. Hatchet Handles, Hickory.
No. 5. Engineers' Hand Hammer Handles, sizes 14, 16, 18, 20,
22, 24, 30, 36 ins.
No. 7. Sledge Hammer Handles, Hickory.

ALWAYS BUY TOOLS BY REPUTABLE MAKERS




Marples' Plated Squares

T137.

Rosewood or Ebony

Sizes: 4½, 6, 7½, 9, 10½, 12.



Stanley Squares

T138.

Metallic Stocks

Sizes: 4½, 6, 7½, 9, 12.

Order by

Number

Do Not

Cut

Catalogue

SQUARES, BEVELS


Precision Made - High Quality



"Eureka" Flush Sliding Bevels

T143.

Special Iron Stock. Nickel Finish. Steel Blade which can be secured at any angle by turning end screw shown at lower end of stock.




Stanley Sliding Bevel

T144.

Rosewood Stock. Flush Brass Lever, which instantly releases or tightens Blade.


Sizes, ins.: 8, 10, 12, 14.



Stanley Plated Rosewood Squares

T139.


Sizes: 4½, 6, 7½, 9, 10, 12.



Stanley Angle Dividers

T140.

With this Tool any angle can be found and bisected. Fitting moulding or other wood work to odd angles can be done with ease and certainty. It is also graduated for the parts of circle commonly used. A handy Tool for laying out work. The Angle Divider is accurately made and can be used as a Try or "T" square



Stanley Plated Mitre Squares

T141.

Sizes: 4½, 6, 8, 10, 12

A Handy Tool!



Stanley Adjustable Try and Mitre Squares

T142.

One of the handiest tools in a Carpenter's Kit. Especially useful for doing short work about windows, doors, etc., or in putting on butts or locks. The Blade is adjustable and as it can be reversed, provides any size of try or mitre square within the capacity of the tool. In reversing, it is not necessary to remove the blade from the handle, consequently the tool is always assembled and ready for use.

The locking device is such as to insure the blade being firmly and accurately secured at any point desired. The edges of the Blade are machined, graduated in 8ths, 16ths and 32nds of inches and the tool is square inside and out.

It is also an excellent depth and marking gauge.

Both Handle and Blade are nickel plated. Made in three sizes.

No. 21—6", 9" and 12" Blade.

Also Stocked—Rabone and L. S. Starrett Try and Mitres.

Steel Timber Squares

T145.

No. 100—Marked in 1/32, 1/16, 1/8, 1/4, 1/2, 3/4, with Brace Measure, 8 Square, 1/100 Scale and Essex's New Board Measure, giving feet and inches in full.

No. 100R. — Same as above, but with addition of Rafter Table.

No. 500R. — 1/10, 1/12, 1/16, 1/8, 1/4, Board and Brace Measure.

Stanley Steel Rafter or Framing Squares

T146.

These Squares are made with the same careful attention to detail and the same high quality of material and workmanship as distinguishes all Stanley Tools. Every Square is Weldless, or in other words, made from one piece of steel, and all four edges are machined. Particular attention is called to the finish of all numbers and the depth and accuracy of the graduations. Special care has been given to the simplifying of all tables used, so that the workman can get the measurements he desires with ease and rapidity. Body 24" x 2". Tongue, 16" or 18" x 1½".

Rafter or Framing, Brace, Octagon, Essex Board Measure and 1/100 Scale.

REMEMBER THE LOWEST PRICE IS NOT ALWAYS ECONOMICAL


PLUMBS and LEVELS



T147.

Stanley's Plumb and Level

Two side views, Arch Top Plate, Patent Grip
Sizes, inches: 12, 14, 16, 18, 22, 24, 27, 30.



T148.

Stanley's Adjustable Level and Plumb
Plated Ends

Sizes, inches: 24, 26, 28, 30.



T149.

Stanley's Duplex Levels with Plumbs

Size, inches: 24, 27, 30; Triple Stock: 27, 30.

Also Stocked: Rabone and Marples' Plumbs and Levels



Stanley's Level Sight

T150.


Can be attached to any level and afford a convenient and accurate means for levelling at a distance.

Rabone's Boxwood Rule and Plumb Level

T151.

Brass Tipped at Ends

Sizes: 6, 8, 10, 12 in.



Stanley Level Tubes (Centre marked)

T152.

2 in., 2½ in., 3 in., 3½ in., 4 in.
Also Rabone's Plain and Cat's Eyes



Hall Octagon

T153.


Line and Surface Level



T154.

**Brass
Plumb
Bobs**

Size	Weight
00	1½ oz.
0	2½ oz.
1	3½ oz.
2	4½ oz.
3	6 oz.
4	8 oz.
5	10 oz.
6	13 oz.



**Stanley
Trammel
Points**

T155.

A practical form of Trammel Point adapted for use on an ordinary Carpenter's Rule, and on many kinds of work will take the place of more expensive Trammel Points, Callipers, or Dividers.

Compasses or Wing Dividers

T156.

Sizes: 6, 7, 8, 9, 10, 12 in.




Stanley's Plumb and Level

T157.

Not Adjustable. Two Side Views.

Sizes: 12, 14, 16, 18 in.

Since 1859
John Danks &
Son Pty. Ltd.
have been the
recognized
leaders for
Tools for all
Trades,
Builders
Supplies, etc.
etc.



Starrett's Levelling Instrument

T158.

Warranted to be true in every respect.


It is adapted for the use of architects, carpenters, stone-masons, and others, for levelling, getting angles, etc. It is made of iron, japanned, except the sight tube, which is of brass, nickel-plated. Directions sent with instrument.

Order by Number—Do Not Cut Catalogue.


**Stanley Levelling
Stand**

T159.

For determining levels from a given point to one at a distance. It can be attached to a stake and adjusted to a horizontal position even though the stake may not be exactly perpendicular. Nickel plated.



ACCURATE! DEPENDABLE!



STARRETT TRANSIT
T160.

To meet the demands of contractors, builders, carpenters, farmers, and others for a transit and level, low in price, yet sufficiently accurate for their needs, the Starrett transit and level have been developed. These instruments are very simple and free from complications and confusing adjustments.

The instrument is composed of iron and brass, and consists of a tripod, to the head of which is connected by a ball-and-socket joint and upper plate, which can be levelled by the levelling screws.

This plate is recessed to contain a graduated arc for taking horizontal angles. The arc is $\frac{1}{2}$ of a circumference, reading 90° each side of 0, and being independent of level and sight tube can be turned and used at any point of a complete circle. On this plate rests a triangular frame to which are attached a level, a graduated arc for taking vertical angles, graduated 45° each side of 0, and a sight tube. The plain sight tube has no lenses, is brass, 12" long; in one end is a small eye aperture, in the other the usual cross wires.


The Telescope has cross lines, is adjustable to distances and is same size and length as plain sight tube. The lens is well protected from dirt and breakage by a friction cap, and a shutter for the eye aperture.

With short legs, as shown in the cut, the instrument is 8" high. With long extension legs, which fasten on over the short legs, the height can be from 2' 8" to 4' 8". The sight tube, level case, and graduated arcs are nickel-plated, the other parts are japanned.


The advantages of this transit are as follows:—The head is held to the tripod with a bolt and knurled nut, so as to make it stationary at any given point; the graduated arc can be clamped to the base plate by throwing a small cam arrangement and a spring indexing finger to mesh in the arc graduations.

Directions for setting up and using are enclosed with each transit

One Foot, Four Fold, Boxwood



- T161.—Rabone's 1167—2 ft., four fold.
T162.—" 1167—3 ft., four fold.
T163.—" 1112—3 ft., four fold.
T164.—" 1113—3 ft., four fold.



Arch Joint, Bevelled Edges
T165.

Edge Plates, Bevelled Edges, with eight scales; $\frac{1}{8}$ " wide.

Arch Joint
T166.

German Silver Mounts, Bevelled Edge, eight scales; 1" wide.

BOXWOOD RULES


Boxwood, Two Feet
Four Fold

T167.
Round Joint

Marked in $\frac{1}{8}$ ", $\frac{1}{4}$ " wide.

Round Joint

T169.
Marked in $\frac{1}{8}$ " and $\frac{1}{16}$ ", 1" wide.



Arch Joint


Width Markings

- T170.— $\frac{1}{8}$ " : $\frac{1}{8}$ ", $\frac{1}{16}$ ", $\frac{1}{10}$ ", $\frac{1}{12}$ ".
T171.— $\frac{1}{8}$ " : $\frac{1}{8}$ ", $\frac{1}{16}$ ", $\frac{1}{10}$ ", $\frac{1}{12}$ ".
T172.— $\frac{1}{8}$ " : $\frac{1}{8}$ ", $\frac{1}{16}$ ", $\frac{1}{10}$ ", $\frac{1}{12}$ ".


**Brass Bound
Arch Joint**

T173.

With spirit level and degrees on joint. A really handy and indispensable rule.



Make this Catalogue your Guide for all your Needs in
Tools and other Supplies.



Boxwood Bench Rules—Brass Tipped

Brass Bound
T174.

Inside and outside edges
Marked $\frac{1}{8}$ ", $\frac{1}{16}$ ", and scale,
 $\frac{1}{8}$ " wide.




Marked in $\frac{1}{8}$ ".

T175. $\frac{1}{2}$ " wide x $\frac{1}{4}$ " thick, 48" long.

T176.—1" wide x $\frac{3}{16}$ " thick, 24" long. T177.—1" wide x $\frac{3}{16}$ " thick, 36" long.

**Boxwood Rules,
Three Feet
Four Fold**



- T178. Marked $\frac{1}{8}$ ", $\frac{1}{10}$ ", $\frac{1}{12}$ " and $\frac{1}{16}$ "; 1" wide.
T179.—Marked $\frac{1}{8}$ ", $\frac{1}{10}$ ", $\frac{1}{12}$ " and $\frac{1}{16}$ "; $\frac{1}{8}$ " wide.
T180. Marked $\frac{1}{8}$ ", $\frac{1}{10}$ ", $\frac{1}{12}$ " and $\frac{1}{16}$ "; $\frac{1}{8}$ " wide.


Also 4 feet, Four Fold.

Blindman's Rule

T181.

18" wide, square joint, with figures deeply marked in indelible black. A useful Tool for use in defective light, or for those with poor eyesight.
RABONE'S IVORY RULES, Plain and Bevelled Edges, also in stock.


PLEASE WRITE TO US FOR ANY TOOLS NOT LISTED IN THIS SECTION

**Metallic Tapes****T182.**

33 ft. and 66 ft.


Marked Feet and Inches one side and Links or Decimals the other.

Also Linen Measures In 33 ft., 66 ft. and 100 ft.


**STEEL TAPES,
SURVEYORS' BANDS**
**Surveyors' Bands****T183.**On Frame. $\frac{1}{2}$ " wide.Etched feet (inches in $\frac{1}{2}$ ") and links. Every Foot and Link numbered. 66 ft. and 100 ft.**T184.****Rabone's Steel Tapes**

In Leather Cases. Flush Handles.


Marked Feet and Inches on one side and Decimals on other

 $\frac{3}{8}$ " wide: 33 feet, 66 feet, 100 feet. $\frac{1}{2}$ " wide: 33 feet, 66 feet, 100 feet.**T185.—RABONE'S STEEL TAPES**
Flush Handles. German Silver Mounts.
 $\frac{3}{8}$ " wide: 100 feet.
Marking, Morticing & Cutting Gauges
T186.**Brass Plated Marking Gauge****T187.****Beech Marking Gauge****T188.****Boxwood Marking Gauge**
With Rule Marked Beam**Rosewood Mortice Gauge****T189.****T190.****Ebony Brass Stem Mortice Gauge****T191.****Oval Mortice Gauge**
Rosewood**Cutting Gauge**
T192.

(Similar to illustration, but with Plated Head.)

**T193.****Stanley Beech Marking Gauge**
Finest Durable Quality.**T194.****Stanley Metal Marking Gauge**
Nickel Plated. Graduated.**T194a. Starrett's Nail Sets**Made of Fine Grade Steel. Concave Top. Both Ends Hardened.
Length, 4". $\frac{1}{16}$ ", $\frac{3}{32}$ ", $\frac{1}{8}$ ", $\frac{5}{32}$ ".**T195. Moore and Wright****NAIL SETS**These Nail Sets are made from a very high grade of $\frac{3}{8}$ " round tool steel about 4" long. The centres are knurled and the points are cupped. These Nail Sets are very carefully hardened and are tempered their entire length. Blue Finish. Made with $\frac{1}{16}$ ", $\frac{3}{32}$ ", $\frac{1}{8}$ ", $\frac{5}{32}$ " or assorted points.**Cast Iron Glue Pots**
T196.**TINNED INSIDE**Sizes in Pints: $\frac{1}{2}$, 1, 2, 3, 4, 5, 6, 7, 8, 10, 12, 15, 20, 25, 30.**FOR GARDEN TOOLS,**
See Garden Tool Section,
Pages 185 to 193.
AMATEUR OR ARTISAN, WE CAN SUPPLY YOUR REQUIREMENTS

Braces, Bits, Augers, etc.



T197. THE MASTER BRACE
For all styles of Bits


The Chuck Jaws open parallel, except when used for holding Taper or Bit Stock Shanks, when they adjust themselves exactly to the shape of Bit or Piece to be held. Thus they will hold securely straight Shanks from $\frac{1}{4}$ " down to $\frac{1}{2}$ ", and all styles and sizes of Bits and Tapers and irregular shaped Shanks.
Sizes: 8, 10, 12.

Ball Bearing Head and Centre Handle

The Head and Centre Handle are fitted with Ball Bearings—the Ball-Bearing Handle being unique and very desirable. Finished in best style and warranted throughout.

Barber Ratchet Braces
T198.

BALL BEARING HEAD



Centre Handle has improved adjustable bearings. These Braces have Alligator Jaws, are well made and fully nickelled.
Sizes: 8, 10, 12.

Snell-Clark Expansive Bits

T199.



No. 1—With two cutters, one boring from $\frac{1}{4}$ " to $\frac{1}{2}$ ", and the other from $\frac{3}{8}$ " to $1\frac{1}{4}$ ".
No. 2—With two cutters, one boring from $\frac{1}{2}$ " to $1\frac{1}{4}$ ", and the other from $1\frac{1}{4}$ " to 3".

EXTRA CUTTERS FOR EXPANSIVE BITS

No. 1—Cuts $\frac{1}{4}$ " to $\frac{1}{2}$ ". No. 2—Cuts $\frac{3}{8}$ " to $1\frac{1}{4}$ ". No. 3—Cuts $\frac{1}{2}$ " to $1\frac{1}{4}$ ".

No. 4—Cuts $1\frac{1}{4}$ " to 3".

NOTE.—Nos. 1 and 2 Suit No. 1 Bit; Nos. 3 and 4 suit No. 2 Bit.



T200.

Mathieson's Solid Steel Centre Bits

Sizes: $\frac{1}{4}$ ", $\frac{5}{16}$ ", $\frac{3}{8}$ ", $\frac{7}{16}$ ", $\frac{1}{2}$ ", $\frac{9}{16}$ ", $\frac{5}{8}$ ", $\frac{11}{16}$ ", $\frac{3}{4}$ ", $\frac{7}{8}$ ", $1"$, $1\frac{1}{16}$ ", $1\frac{1}{8}$ ", $1\frac{3}{16}$ ", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", $1\frac{3}{4}$ ", $1\frac{1}{2}$ ".

Cleveland Wood Bits

T201.

Do not split the wood, and will drill through Nails, etc.
NOTE.—The sizes indicate 32nds of an inch.




Sizes: 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16.




T202. Mathieson's Dowel Bits

Sizes: $\frac{3}{8}$ ", $\frac{7}{16}$ ", $\frac{1}{2}$ ", $\frac{5}{8}$ ".



T203.


Dowel Sharpeners



T204.

Chapman's Ratchet Braces

No. 17— 10" sweep, teakwood head and grip, ball-bearing head, steel sweep, nickel-plated hardened alligator jaws, hexagon shell.



Mathieson's Split Socket Braces
T205.

Sizes: 8, 10, 12.



T206.

Universal Angular Bit Stock

Used in connection with a Brace and Bit for boring holes in places where a Brace and Bit could not be used. Angle can be varied from straight to the angle shown.

Mathieson's Dowel Plates



$\frac{3}{16}$ ", $\frac{1}{4}$ ", $\frac{5}{16}$ ", $\frac{3}{8}$ ", $\frac{1}{2}$ ".
T207.



Gimlet or Nail Bits

$\frac{1}{16}$ " to $\frac{1}{8}$ ".

T208.



Bit Holder
T209.

Will hold any Bit with Square Shank.

DANKS OFFER QUALITY TOOLS AT COMPETITIVE PRICES



T210.
Countersink Bits
For Wood




T211.
Countersink Bits
For Iron



T212.
Countersink Bits
For Brass



T213.
Turnscrew Bits
Assorted Sizes




T214.
Square Rinder Bits



T215. Half Round Rinder Bits

Stanley Bit Stop
T223.



Will fit all size bits
from $\frac{1}{2}$ " to 1".

T224.
Tyzack's Beechwood
Handled Bradawls
Guaranteed Quality.

T225.
Mathieson's Twist
Gimlets

Do Not Cut
Catalogue—
Order by Number!

T216. Ford's Auger Bits



These Auger Bits have a single twist and extension lip; are fast and clean cutting and can be used on hard and soft timbers.

Sizes: $\frac{3}{16}$ ", $\frac{1}{4}$ ", $\frac{5}{16}$ ", $\frac{3}{8}$ ", $\frac{7}{16}$ ", $\frac{1}{2}$ ", $\frac{9}{16}$ ", $\frac{5}{8}$ ", $\frac{3}{4}$ ", $\frac{7}{8}$ ", 1 ", $1\frac{1}{8}$ ", $1\frac{1}{4}$ ".

T217. Mathieson's Screw Augers



Finest quality obtainable.

Sizes: $\frac{1}{4}$ ", $\frac{3}{8}$ ", $\frac{1}{2}$ ", $\frac{5}{16}$ ", $\frac{3}{4}$ ", $\frac{7}{8}$ ", 1 ", $1\frac{1}{8}$ ", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", $1\frac{3}{4}$ ", 2 ", $2\frac{1}{4}$ ", 3 ".

T218. Single Twist or Bull Nose Augers



Sizes: $\frac{1}{4}$ ", $\frac{5}{16}$ ", $\frac{3}{8}$ ", $\frac{11}{16}$ ", $\frac{1}{2}$ ", $\frac{13}{16}$ ", $\frac{7}{8}$ ", $\frac{15}{16}$ ", 1 ", $1\frac{1}{16}$ ", $1\frac{1}{8}$ ", $1\frac{3}{8}$ ", $1\frac{1}{2}$ ".

T219. Irwin's Solid Centre Auger Bits



With Extension Lip for soft wood.

Sizes: $\frac{3}{16}$ ", $\frac{1}{4}$ ", $\frac{5}{16}$ ", $\frac{3}{8}$ ", $\frac{7}{16}$ ", $\frac{1}{2}$ ", $\frac{9}{16}$ ", $\frac{5}{8}$ ", $\frac{11}{16}$ ", $\frac{3}{4}$ ", $\frac{13}{16}$ ", $\frac{7}{8}$ ", 1 ", $1\frac{1}{16}$ ", $1\frac{1}{8}$ ", $1\frac{1}{4}$ ".

T220. Mathieson's Double Twist Auger Bits



Sizes: $\frac{3}{16}$ ", $\frac{1}{4}$ ", $\frac{5}{16}$ ", $\frac{3}{8}$ ", $\frac{7}{16}$ ", $\frac{1}{2}$ ", $\frac{9}{16}$ ", $\frac{5}{8}$ ", $\frac{11}{16}$ ", $\frac{3}{4}$ ", $\frac{13}{16}$ ", $\frac{7}{8}$ ", $\frac{15}{16}$ ", 1 ", $1\frac{1}{8}$ ", $1\frac{1}{4}$ ".



T221. Mathieson's Waggon Bits

Sizes: $\frac{3}{8}$ ", $\frac{7}{16}$ ", $\frac{1}{2}$ ", $\frac{9}{16}$ ", $\frac{5}{8}$ ", $\frac{11}{16}$ ", $\frac{3}{4}$ ".

Stanley's Dowelling Jigs


T222.

This tool is for the purpose of enabling the user to bore dowel holes in the edge, end or surface of work with ease and accuracy. It will take any thickness of material up to 3". It is also an excellent bit guide for mortising.

With the Dowelling Jig the steel guide is automatically set to guide the bit properly when the Jig is clamped to the work.

A depth gauge is also furnished which can be used with or without the Jig. When used without the Jig, the gauge should be set with the large end towards the point of the bit, but in using same with the Jig it should be set with the small end down, as shown in the cut. These Jigs are made entirely of metal, the working parts being milled true. All parts are nickel plated.

No. 59, with 5 Guides (1 each $\frac{1}{4}$ ", $\frac{5}{16}$ ", $\frac{3}{8}$ ", $\frac{7}{16}$ " and $\frac{1}{2}$ ").
No. 60, with 9 Guides (1 each $\frac{3}{16}$ ", $\frac{5}{16}$ ", $\frac{3}{8}$ ", $\frac{7}{16}$ ", $\frac{1}{2}$ ", $\frac{9}{16}$ ", $\frac{5}{8}$ ", $\frac{11}{16}$ " and $\frac{3}{4}$ ").



Cleveland Wood
Bits in Sets

T226.

Box containing $\frac{1}{8}$ ", $\frac{3}{16}$ ", $\frac{1}{4}$ ",
 $\frac{5}{16}$ ", $\frac{3}{8}$ ", $\frac{7}{16}$ ", $\frac{1}{2}$ ".

Set of Wood Bits

T227.

This set consists of the following sizes Wood Bits:—

$\frac{1}{16}$ ", $\frac{3}{32}$ ", $\frac{1}{8}$ ", $\frac{5}{32}$ ", $\frac{3}{16}$ ", $\frac{7}{32}$ ",
 $\frac{1}{4}$ ", $\frac{5}{16}$ ", $\frac{3}{8}$ ".


The round polished hardwood box that goes with this set is $2\frac{1}{2}$ " in diameter and $8\frac{3}{4}$ " long.



For GARDEN TOOLS, See Pages 185 to 193 - - - A Great Range!

GIVE US AN OPPORTUNITY TO QUOTE YOU FOR YOUR REQUIREMENTS

Sash and Joiners' Cramps




T228.
Steel Bar Sash Cramps
Polished
Sizes: 24", 30", 33", 36".



T229.
"T" Section Joiners' Cramps

These Cramps are made from specially drawn tough Steel Bars with "T" edge, and are made in light and heavy section.

Light—Sizes ..	36"	42"	48"	54"	60"
To take in ..	30"	36"	42"	48"	54"
Heavy—Sizes ..	48"	54"	60"	66"	72"
To take in ..	42"	48"	54"	60"	66"



T230.
Malleable Iron "G" Cramps


These cramps are exceptionally strong, having a malleable iron frame and steel screw. The adjustable washer works on a ball at end of screw, thereby conforming to irregular pieces of work.

Sizes: 3", 4", 5", 6", 7", 8", 10", 12".



**BENCH
Stops**

(Above) T231.



(At left)


Morrills'
Pattern
T232.

The Little Booster Flooring Cramps

T233.

A good style of Cramp that is quick and reliable in action, and very popular with builders in Victoria and other States. Grips joists from 1½" to 3½" thick—will even grip firmly on to joists projecting only 1" above concrete.


Thrust 4" long. The 2' 6" lever is very powerful. All parts interchangeable.



Made of Crucible Steel parts and Mild Steel Lever. Does away with stooping. A special feature is that Ram (2) can be held at every half tooth—equal to ½". The few simple instructions are on each Cramp.

Malleable Iron Bench Screw


T234.
Size: 1½".



Woodworkers' Vise


Instantaneous grip and continuous screw action.
Sizes: 7½", 9", 10" Jaw.

T235.



"The Dawn" Junior Vise



5" Jaw



T236.

English "G" Cramps

T237.
Malleable Iron Frame.
Steel Screw.
Sizes: 3", 4", 5", 6",
7", 8"



T238.

Joiners' Cramp Heads


No. 1—To suit planks 1½" x 4".
No. 2—To suit planks 2½" x 5½".



No 4
BENCH
VALVE
OILER

T239. Carpenters' Never Leak Oil Cans

Solidly Made, Patent
"Never Leak" Spout.



Bench Hand Screws

T240.

Sizes: 8", 10", 12".

For ENGINEERS' TOOLS, See
Pages 156 to 182.

OUR KNOWLEDGE AND EXPERIENCE IS AT YOUR SERVICE


THE "STANLEY" IMPROVED MITRE BOX

T241.

The Saw Guide uprights are Steel Rods, and carry the Saw Guide Cylinders in which the Saw works.

Automatic catches at the top of the Saw Guides hold the saw locked and clear of the work when not in use, allowing the operator to use both hands when placing the work.


Movable Stops are attached to the Saw Uprights, which can be set so as to permit the Saw to cut only to the desired depth, or to prevent cutting through the base board.




Stanley Mitre Box

T242.

The Back and Frame Indexed Quadrant and Swivel Arm Bearing are in one piece, and accurately machined. The Quadrant is accurately indexed for cutting Multi-sided Pieces, and will remain mathematically correct. The Swivel Arm can be set at any point between the Index Holes on the Quadrant by means of the Clamping Set Screw on the Swivel, just back of the Front Saw Guide Upright. Can be used with a Panel Saw or Back Saw equally well. Will take Mouldings up to 4".




Brass Mitre Templates



T244.

These Mitre Templates are very useful for all kinds of mitreing purposes. They are accurately made of brass, and of superior finish.

Sizes: 3½ and 5½.



Plain and with Guide

T243. Marples' Mitre Boxes

In well seasoned Hardwood.


DRAW KNIVES



Marples' Amateurs, Draw Knives

Sizes: 5", 6".

T245.



T246.

STANLEY CHUTE BOARD AND PLANE

This is a very important tool, especially for Pattern Makers, Cabinet Makers, Printers and Electrotipers. The board is made of iron, and has an adjustable runway for the Plane. The swivel is indexed for cutting a square and a mitre, but by means of the Clamping Screw, can be set at any desired angle from 0 to 90°.



American Draw Knives

Standard Quality Razor Blade

T247.

Sizes: 6", 7", 8", 9", 10".


Carpet Stretcher

Head only, or Complete.



T249. Sets of Steel Figure and Letter Punches

Sizes: 1/16", 3/16", 1/8", 3/8", 1/2", 5/8", 3/4", 7/8", 1".




T248.

Steel Name Stamps T250.

Initials and Names to order.

ASK FOR OUR QUOTATION FIRST

T251. India Oil Stones




Very Quick Cutting. The favourite stone for mechanics.
Plain—Sizes: 6" x 2" x 1", 7" x 2" x 1", 8" x 2" x 1".
Combination, Medium and Coarse—Sizes: 7" x 2" x 1", 8" x 2" x 1".

T252. Washita Oil Stones



No. 1—A good quality stone for general use.
Lilywhite—The finest selection of Washita procurable.
Average weight of Stone, 1 lb. 4 ozs.

T253. Genuine Turkey Stones



Best Quality. The favourite stone for sharpening Sheep Shears.
Pieces 5" to 8" long, 1 1/2" to 2" wide, 3/4" to 1 1/4" thick.

T254. Hard "Arkansas" Stones



A very hard stone, suitable for giving a keen edge to Engravers' and Watchmakers' Tools. Also Dentists' and Surgeons' Instruments.
Supplied in Blocks 5 1/2" to 8" long, 1 1/2" to 2" wide, 3/4" to 1" thick.

T255. Carborundum Oil Stones



These Stones are practically unequalled for putting a keen edge on Carpenters' and Mechanics' Tools. Being porous they may be modified in their cutting by filling with vaseline. They may be thoroughly cleaned when filled up with oil and grit, by being placed in a fire without any injury to the stone.

T256. Carborundum Razor Hones




Fine or Medium Cut. Plain: 6" x 2" x 1", 8" x 2" x 1".
Combination: 6" x 2" x 1", 8" x 2" x 1".

T257. Quick Cut Oil Stones



Made of Turkish Emery. Combination of coarse and fine grits. This stone is made with one side coarse, for fast cutting, and the other for putting on a fine edge. A satisfactory, medium-priced stone for general use. Sizes: 7" x 2" x 1", 8" x 2" x 1".



T261.

Hunters' Hatchets

Brades' or Green Mountain.



T262. Bench Hatchets
Nos. 1, 2, 3, 4.



Plumb's Axes

T263.


Tasmanian Pattern
Weight: 4, 4 1/2, 4 3/4, 5 lbs.



Brades' Axes

T264.

Tasmanian Pattern
Weight: 4, 4 1/2, 4 3/4, 5 lbs.



T265.

We Also Stock
KELLY AXES


Brades' Claw Hatchets

Sizes: 1 and 2.

GRINDSTONES


Axe Stones

T258.



Round Carborundum Axe Stones

A favourite with Wood Choppers.
One side fine, other side coarse.
T259.



Genuine Newcastle Grindstones

Sizes: 12", 14", 16", 18", 20", 24", 30", 36".

Also

T260.

Grindstone Stands AND MOUNTING

In Small, Medium and Large sizes.

Carborundum Slips

FINE AND MEDIUM



T266.	Length	Width	Back	Edge
Size A—4"	1"	1"	7/16"	5/16"
" B—4 1/2"	1 1/2"	1 1/2"	3/8"	3/16"
" C—4 3/4"	2"	2"	3/8"	5/16"
" D—4 3/4"	1 1/2"	1 1/2"	3/8"	1/16"
" E—6"	2 1/2"	2 1/2"	3/8"	3/8"

India Slips

MEDIUM

T267.



No.	Length	Width	Back	Edge
No. 13	4 1/2"	1 1/2"	3/8"	3/16"
No. 14	4 1/2"	1 1/2"	3/8"	3/16"
No. 15	4 1/2"	1 1/2"	3/8"	1/16"

For GRINDERS
See Next Page

WE CAN SATISFY YOUR REQUIREMENTS LARGE OR SMALL

PIKE (NO. 9) PEERLESS SENIOR GRINDER

T268.



An efficient and durable hand power Grinder, combining high speed and great power in just the right proportion to obtain best results. Equipment—Pike patented tool rest, combining chisel holder, twist drill guide, and scissors' guide. Extension crank handle, adjustable to any length, making easy work of the most awkward grinding job.
Size: Height, 13"; length, 12½"; diameter of gear case, 9".
Size of Wheel: 6" x 1".

T269.

Pike (No. 8) Peerless Junior

An exact duplicate of the Senior Model, but smaller.
Size of Wheel, 5" x 1".
EFFICIENT! DURABLE!

T270.

Pike (No. 12) "Whirlwind" Grinder

This machine will meet the demand for a Grinder that will do heavy and quick grinding, on railway construction, quarrying, mining, and building work. Each machine is equipped with a Universal Tool Rest.

Size of Wheel: 8" x 1".



T279.

Pike (No. 4) "Household" Grinder

This machine is a plain, strongly made Grinder, suitable for general household service.

Size of Wheel: 4" x ½".



T280.

Pike (No. 5) "Domestic" Grinder

Very sturdy in construction, and suitable for Amateur Craftsman or the Mechanic.

Size of Wheel: 5½" x 1".



T281.

Pike (No. 6) "Artisan" Grinder

A very efficient Grinder at a reasonable price. Suitable for Mechanics.

Size of Wheel: 6½" x 1".

MODERN GRINDERS

In workmanship, design and finish, "Modern Grinders" are amongst the best, every detail has been carefully tested, and materials best adapted to each part have had every consideration.

Model B T271.

Extra large and heavy oiltight gear case; crank shaft has bearings at each end.

Long malleable nickelled handle adjustable.

Heavy steel wheel grip clamp screw, with two point cap. Equipped with Modern, tool rest adjustable to either side of wheel for right or left-handed operator.

Machine cut gears, easy starting and quiet running.

Finished in the attractive Modern Olive Drab Enamel. Highest grade, fast cutting electric manufactured wheel.

T272.

Modern Grinder No. B4

This machine is built for household use. The handy man about the house finds this small tool an absolute necessity.

Size of wheel: 4" x 1".

T274.

Modern Grinder No. B6

For private garage and small repair shops, mechanics, etc., who want to grind their tools on the job, or for all purposes requiring a powerful yet portable machine.

Size of wheel: 6" x 1".

Modern Grinder, Model J

(At right) T276.

Has large one-piece gear case with long bearings. Crank shaft has bearing on both ends.

Long malleable handle.

Heavy steel wheel grip clamp screw.

Bright steel tool rest, adjustable to either side of wheel for right or left-handed operator.

Machine cut gears, easy starting and quiet running.

High grade, fast cutting electric manufactured wheel.

Similar to B Models, but of lighter and cheaper construction.

T277.

Modern Grinder No. J5

Fitted with Vitrified Corundum.

Wheel: 5" x 1".

Adjustable Tool Rest.


T278.

Modern Grinder No. J6

Fitted with Vitrified Corundum.

Wheel: 6" x 1".

Adjustable Tool Rest.



WE STOCK INEXPENSIVE TOOLS FOR THE HANDY MAN



T282.

HALF-ROUND WOOD RASPS

Sizes: 6in., 8in., 10in., 12in., 14in., 16in.


T283.

HALF-ROUND CABINET RASPS

Sizes: 6in., 8in., 10in., 12in., 14in., 16in.

T284. SAW FILES

TAPER: 1.




SLIM TAPER: 2.



Sizes: 3in., 3½in., 4in., 4½in., 5in., 6in., 7in., 8in.

Make this
Catalogue
Your Guide
for All Your
Needs in
TOOLS



Knopp's Patent Seamless Nail Pocket

This Pocket is made from one piece of Best Quality Solid Leather without a seam.


T285.

PRACTICALLY EVERLASTING.

Canvas Nail Pocket

T286.

This Pocket is made from Heavy Canvas, and is strongly sewn. It will take a 3' Rule.



Canvas Bit Roll

T286a.

This Roll is made from a Heavy Quality of Waterproof Canvas, and will hold up to 30 Bits, Made to roll up and fasten with a Leather Strap

Do Not Cut
Catalogue


Order by
Number



T287.

Canvas Level Pocket

Invaluable for protecting Levels and Level Tubes. Strongly made, neatly finished. To suit Levels 24", 26", 27", 28", 30".



The AUSTRAL Rigid Tool Bag

T288.

An Oblong Waterproof Canvas Tool Bag, fitted with 3-ply bottom. The Handles, made of Solid Hide Leather, are joined together, and give extra support to bottom and sides of bag.

USEFUL INFORMATION FOR THE CARPENTER AND BUILDER

NUMBER OF SUPER FEET IN A BOARD OR PLANK

To ascertain number of superficial feet in a board or plank, apply this formula: Length × Breadth × Thickness. If board tapers: Length × Mean Breadth × Thickness. (To discover Mean Breadth, add the breadth of each end together and divide by 2.)


TIMBER

		App. No. of running ft. to 1 ton
Flooring	6" x 1½"	1557
	6" x 1"	1750
	6" x ¾"	2000
	6" x ¾"	2330
Matchboard	6" x 1½"	2800
	6" x 1"	3400
	6" x ¾"	4800
Deals	9" x 5"	350
Weatherboards	(Single)	3100

App. No. of super ft. to 1 ton

Black Butt	333
Cedar	600
Clear Pine	900
Iron Bark	310
Jarrah	360
Kauri	600
Oregon	
V.D.L. Hardwood	450
Amer. Shelving 12" x ¾"	1050

DANKS OFFER QUALITY TOOLS AT COMPETITIVE PRICES

DISSTON'S & TYZACK'S PLASTERERS' TROWELS



T289.


DISSTON'S & TYZACK'S PLASTERERS' TROWELS

 Made of highest grade Crucible Steel, and fastened
 with 7 rivets. Sizes: 11", 11½".

Also MARSHALL'S TROWELS


T290. Sizes: 10½", 11".


T291. PLASTERERS' SMALL TOOLS

Plasterers' Joint Rules
 T292.

 Sizes: 3-in., 4-in., 5-in., 6-in., 8-in.,
 10-in., 12-in., 14-in., 16-in., 18-in.,
 20-in., 22-in.

T293.
TYZACK'S &
W.H.S.
Pointing Trowels

 5-in., 6-in., 6½-in.,
 and 7-in.

T294.

DISSTON'S PLASTERERS' TROWELS

DISSTON'S PLASTERERS' TROWELS

 Same quality as T339, but with 10 rivets and
 leather grip. Sizes: 11", 11½".

W.H.S.
BRICK
TROWELS
 T295.

Capped Ends. Sizes: 12-inch, 13-inch.


T296.
Tyzack's Gauging
Trowels

(Wide or Narrow)

Sizes: 6-in., 7-in., 8-in., 9-in.

Also W.H.S. BRAND
T297.

Sizes: 6-in., 6½-in., 7-in.



T298.

Tyzack's Bed Jointers

Sizes: ⅜-in., ½-in., ⅝-in.


T299.
STEEL LINE PINS
Plugging Chisels


T300.



T301.

Tyzack's Cross Jointers

Sizes: ⅜-in., ½-in., ⅝-in.



T302.

Crown Wall Drills

For Drilling through Brick or Stone

Sizes: ½-inch, ¾-inch, 1-inch.

Lead
Plumb
Bobs

T303.


 Sizes from 1-lb.
 and upwards

REMEMBER DANKS FOR TOOLS FOR ALL TRADES.

WE CATER FOR THE TRADESMAN AND HOME CARPENTER

Brade's
BRICK
HAMMERS
T304.




Brick Bolsters
T310.
Solid Steel

Brick Hammers
New Pattern
T305.




BRICK-
LAYERS'
LINES
T309.
75 yds. Long




T313.

T306.
Hod
Irons
T308.
Lathing
Hatchets


Slaters' Hammers
T307.




All Steel Slaters' Rippers
T311.




T312.
Combined Plumb
Level & Rule



 108 3/8 102 1/4 EDGER.	 112 NARROW EDGER	 128 BEVEL EDGER	 194 STRAIGHT END EDGER	 115 CURBING EDGER	 114 SQUARE EDGER
 192 JOINTER Both Ends Straight	 134 LARGE JOINTER	 107 NARROW JOINTER Both Ends Turned Up	 109 JOINTER One End Straight	 106 JOINTER Both Ends Turned Up	 110 NARROW JOINTER One End Straight
 123 ROLLER JOINTER	Iron Products Nickel Polished CEMENT WORKERS' TOOLS Wholly made in Australia  By Australians From Australian Materials. Packed Cartoons of 1 Dozen each				 133 IRON HANDLE JOINTER
 TUCK POINTERS					 130 3/8 131 1/4 RADIUS TOOL
 199 LARGE GROOVER U Shaped Groove	 104 SMALL GROOVER Both Ends Turned Up	 191 SMALL GROOVER One End Straight	 193 LARGE GROOVER Both Ends Straight	 105 LARGE GROOVER U Shaped Groove	
 118 CURB CUTTER FINISHING TOOL	 119 CORRUGATING TOOL 10 Grooves & 1 1/2"	 116 CORNER TOOL	 132 RESISTANCE CURB TOOL	 117 CUTTER TOOL	
 195 STEPNOSER & GROOVER	 116A EXTERNAL ANGLE	 200 SCUPPER	 196 STEPNOSER with 4 Corrugations	 198 199 SCUPPER 1 1/2 Radius	 197 FLOAT 8 x 3 1/2

GOOD TRADESMEN NEED GOOD TOOLS, CONSULT DANKS

Engineers' and Metal Workers' TOOLS and NEEDS



BENCH LATHE

M1.

This Boring and Screw Cutting Lathe is quite an up-to-date tool. It has incorporated many details that no other small lathe, whatever its price, can boast. Chief points are as under:—

Helical backgears Smooth running.
 Hollow tailstock and headstock Convenient for long, thin jobs.
 Change wheels run on keyed bushes Long life and no sheared pins.
 Balanced handles to all controls Ease of manipulation.

COMPLETE SPECIFICATION.

BED.—Box casting of cantilever form, accurately machined vees, flat top, and hand scraped to finish. Lead screw lugs cast integral. Sides and vees are strongly supported by "ribs" cast solid between.

HEADSTOCK.—Of substantial design, with bearings "bored" from the solid. Adjustment provided for wear. Cone pulley to take 1" flat belt. Steps correctly "domed." Back gears are "spiral" or "helical," and give a very sweet motion, which enables large work to be executed free from chatter, full provision being made for lubrication.

Hollow spindle, which will pass 9-16" bars, completes a very useful head.
TAILSTOCK.—Again design is substantial, being strongly "webbed," thus can resist strains. Fitted with "turned" hollow steel barrel, which is clamped in position by hand screw in convenient position. Balanced handle provides a pleasant and powerful means of "feeding" when necessary.

SADDLE AND COMPOUND REST.—Here we have not stinted iron. Apron is screwed to front of saddle and carries in convenient position. "Clutch" and "quick" return. The clutch is simple and effective, and can be renewed quickly at trifling cost. Bottom slide is planed all over, and contains three "machined" tee slots, thus obtaining a large surface boring table. Balanced handle is provided with "index." Top slide, carrying tool post, is so designed that there is no chance of "spring" when under cut. Tool post is simple and efficient. Adjusting strips to all slides completes this up-to-date unit.

LEAD SCREW AND QUADRANT.—Lead screw is "Acme" thread 8 T.P.I., accurately cut and having ample bearing in lugs cast on bed. Right-hand lug carrying quadrant, which will swivel to any position. This carries the studs and change wheels. Keyed bushes are fitted to all studs and nicely knurled nuts keep change wheels in place. A full set of wheels provided, which will cut all threads in common use. We can supply a 63 wheel for "metric" threads at a small extra cost. All change wheels are machine cut.

PRINCIPAL DIMENSIONS, ETC.

Admits between centres, 16".

Swings over bed, 8 3/4".

Diameter of faceplate, 8 3/4".

Width of belt, 1".

Diameter of hole through spindles, 9/16".

Centre Morse Taper, No. 2.

Back gear ratio, 7-1.

Lead Screw, 8 T.P.I.


Size of tools taking 1/2" square.

Approximate weight, 120 lbs.

Bench Lathe

M2.

66743A is exactly similar to No. 66743 in all respects of material, workmanship and finish, also details, with the exception that we do not fit a quick return to saddle, and clutch is removed to left-hand end of lead screw, thus enabling us to fit a solid nut. Hand wheel is provided at right-hand end of screw, and is a convenient means of moving the saddle and incidentally of turning parallel.



Jacobs' Improved Drill Chuck

M3.

This chuck is especially adapted and extensively used on sensitive and high speed drill presses, lathes, tapping machines, and other purposes where a light, compact, convenient, efficient, accurate and durable Drill Chuck is required.

Number	Capacity Inches	Length Jaws Extended	Outside Diam.
2	0-21/64	2 1/2	1 11/16
3	0-17/32	3 15/16	2 5/16



Drill Chucks with Brace Shanks

M4.

These shanks are milled on centres, keeping them in perfect alignment with the other parts of the tool, and ensuring their running well, providing, of course, that the jaws in which they are held are equally accurate.




Star Drill Chuck

M5.

These Chucks have three Steel Jaws carefully adjusted into a socket to keep them in place and so arranged as to open and close with the loosening or tightening of the chuck upon the spindle.

No.	Capacity	5 0" to 1/2"	6 0" to 3/8"	7 0" to 1/4"
-----	----------	-----------------	-----------------	-----------------



Goodell-Pratt Drill Chucks with Morse Taper Shanks

M6.


These Drill Chucks are provided with standard No. 1 and No. 2 Morse Taper Shanks. In ordering, please specify which size is desired.

No. 14M.T., Capacity, 9" to 5/32".

No. 15M.T., Capacity, 0" to 1/2".

No. 15 1/2 M.T., Capacity, 0" to 3/8".

No. 16M.T., Capacity, 0" to 1/4".



Westcott's Little Giant Drill Chucks

M7.


No.	Capacity	No.	Capacity
00	0 to 1/4"	0	0 to 1/2"
1	0 to 3/8"	2	0 to 1"
2 1/2	0 to 1"		

You can always depend on DANKS
 - - for Quality, Value and Selection

FOR WOODWORKERS' TOOLS, SEE PAGES 134 TO 153


ALWAYS BUY TOOLS BY REPUTABLE MAKERS

Hand, Bench and Breast Drills




HAND DRILL
M8.

Malleable Iron Frame. Cut Gears. 3 Jaw Chuck, capacity 0 to $\frac{5}{16}$ inches. Polished Cocobolo Handles. Complete with 8 Fluted Drills (all contained in handle).



HAND DRILL
M9.

Malleable Iron Frame. Double Gears. 3 Jaw Chuck, capacity 0 to $\frac{3}{16}$ inches. Fitted with Wide Rim Gear to be grasped between thumb and finger when drill is used for fine work.




HAND DRILL
M10.

Malleable Iron Frame. Double Gears. Two Speeds. 3 Jaw Chuck capacity 0 to $\frac{1}{2}$ inch. Polished Handle with Screw Cap. Cut gears. Lathe Turned Spindle, fitted with Ball Bearings.



HAND DRILL
M11.

Malleable Iron Frame. Double Gears. Two Speeds. 3 Jaw Chuck, capacity 0 to $\frac{1}{2}$ inch. Polished Handle with Screw Cap. Cut Gears. Lathe Turned Spindle, fitted with Ball Bearings.




BENCH DRILL
M12.

Solid Iron Frame. Cut Gears. Two speeds. Adjustable Table. Steel Feed Screw. 3 Jaw Chuck, capacity 0 to $\frac{1}{2}$ inch. Also furnished with a special vyce which may be used in place of table.

Complete with vyce and 8 Fluted Drills 1-16 to 11-64.

YANKEE BREAST DRILLS
M13.

The peculiar feature of these Drills is found in the shifter on cylinder. The mere movement of this shifter into the various notches causes the tool to perform different movements. In the first notch nearest the chuck, it is an ordinary Breast Drill; in the second notch it becomes a Left-hand Ratchet; in the third notch it becomes a Right-hand Ratchet. In the fourth notch any movement of the crank, however short or turned in either direction, the drill will always turn to the right and drill continuously.



BUFFALO BALL-BEARING DRILL

(No. 611)

M14.

Automatic and Hand Feed.

Drills to centre of 11-inch circle. Drill holes up to $\frac{3}{4}$ inch. Spindle Diameter $\frac{1}{2}$ inch. Run of feed 3 inches. Run of table 10 inches. Length overall 33 ins

(No. 612)

M15.

Drills to centre of 12-inch circle, holes up to 1 inch.

REMEMBER THE LOWEST PRICE IS NOT ALWAYS ECONOMICAL

Hand, Bench and Breast Drills

HAND POST DRILL


M16.

SINGLE GEARED HAND FEED

Drills $\frac{3}{4}$ inch to centre of 12-inch circle. Drill spindle is 1-inch steel, and bored for $\frac{1}{2}$ -inch straight shank drills. Feed has a run of 3 inches. Upright column and feed screw are of steel. Extension Crank, Adjustable Table.




This Catalogue, while most comprehensive, obviously cannot show our complete range. If you cannot see exactly what you require in this Catalogue, write to us, giving particulars. We may have your requirement in stock.



BREAST DRILL

M17.

This Tool is one of the most complete of its kind. It is fitted with a 3 Jaw Chuck, capacity 0 to $\frac{3}{4}$ inch. Extension Crank. Ball Bearings. Level attachment. Gears are cut from the solid and are changeable. Chuck is made to hold taper, round or square Shank Drills, and is nickelled.



BREAST DRILL

M18.

The Breast Plate is adjustable. Speed may be changed from fast to slow by turning the Thumb Nut at "A" until the letter representing the desired speed is nearest the Chuck.


"DAWN" DRILLING MACHINES

The "Dawn" Bench Drill

No. 101.

Equipped with two speed cone pulleys, ball bearing thrust, with the main driving pulley adjustable for belt tension. The spindle takes No. 1 Morse taper shank. Drills to centre of 10" circle.



M20.



M19.

The "Dawn" Combined Bench or Post Drill

Drills $\frac{3}{4}$ " to centre of 9" circle. 2" run of feed. Diameter of spindle, $\frac{3}{4}$ ". The head has radial and vertical adjustment, giving a maximum clearance of 10" between base and end of spindle. Hand feed.



M21.

The "Dawn" Post Type Drill

No. 61

Drills 1" to centre of 12" circle. Diameter of spindle, $\frac{3}{4}$ ". Features an adjustable automatic feed, fly wheel gear direct to main spindle, and improved coupler and ball bearing thrust. Heavy fly wheel maintains momentum.


The "Dawn" Drill

No. 616.

Post type, with ball bearing automatic feed. A heavier type of machine, geared for two speeds, and drills $1\frac{1}{2}$ " to centre of 16" circle. Run of feed, 3 $\frac{1}{2}$ ". Fast and loose pulleys for belt drive supplied as extra when specified.


M22.






TWIST DRILLS WITH PARALLEL SHANKS M23.

Diameter: 1/16", 5/64", 3/32", 7/64", 1/8", 9/64", 5/32", 11/64", 3/16", 13/64", 7/32", 15/64", 1/4", 17/64", 9/32", 19/64", 5/16", 21/64", 11/32", 23/64", 3/8", 25/64", 13/32", 27/64", 7/16", 29/64", 15/32", 31/64", 1/2".



Twist Drills, Stubb's Wire Gauge Sizes, 1 to 80 M24.



Ratchet Twist Drills M25.

Shanks: 3/8" x 3/8".

Diameter: 1/8", 9/32", 5/16", 11/32", 3/4", 13/32", 7/16", 15/32", 1/2", 17/32", 9/16", 19/32", 5/8", 21/32", 11/16", 23/32", 3/4", 13/16", 7/8", 15/16", 1", 1-1/16", 1 1/8", 1-3/16", 1 1/4", 1-5/16", 1 3/8", 1-7/16", 1 1/2".



Short Twist Drills M26.

With 1/2" Parallel Shanks, for Blacksmiths' Drilling Machines.

Diameter: 1/8", 5/32", 3/16", 7/32", 1/4", 9/32", 5/16", 11/32", 3/8", 13/32", 7/16", 15/32", 1/2", 17/32", 9/16", 19/32", 5/8", 21/32", 11/16", 23/32", 3/4", 25/32", 13/16", 27/32", 7/8", 29/32", 15/16", 31/32", 1".



Twist Drills M27.

With Square Shanks to fit ordinary Braces.

Diameter: 1/16", 5/64", 3/32", 7/64", 1/8", 9/64", 5/32", 11/64", 3/16", 13/64", 7/32", 15/64", 1/4", 17/64", 9/32", 19/64", 5/16", 21/64", 11/32", 23/64", 3/8", 25/64", 13/32", 27/64", 7/16", 29/64", 15/32", 31/64", 1/2", 1-1/16", 1 1/8", 1-3/16", 1 1/4", 1-5/16", 1 3/8", 1-7/16", 1 1/2".


Taper Shank Twist Drill M28.

Diameter: 1/8", 17/64", 9/32", 19/64", 5/16", 21/64", 11/32", 23/64", 3/8", 25/64", 13/32", 27/64", 7/16", 29/64", 15/32", 31/64", 1/2", 1-1/16", 1 1/8", 1-3/16", 1 1/4", 1-5/16", 1 3/8", 1-7/16", 1 1/2".



The "Huntington" Grinding Wheel Dressers M32.

It is of utmost importance that emery wheels be kept perfectly true. For this purpose the "Huntington" Dresser will be found ideal. Although designed for the smaller wheels, the larger wheel can also be dressed with the "Huntington."



Extra Cutters for the "Huntington" Wheel Dresser M33.

These are fitted with steel frames and roller bearings; are light running and very durable.

Do Not Cut
Catalogue—
Order by Number!



Hooks and Eyes M34.

For Gut or Round Leather Belting.
Size: 1/8", 3/16", 1/4", 5/16", 3/8", 7/16", 1/2".

Round Gut Belting M35.

Suitable for small Lathes, Polishing Heads, etc.
Size: 3/8", 1/2", 5/8", 3/4", 7/8", 1".


Set of Bit Stock Drills in Case M29.

9 Sizes: 1/16" to 1/2".




Order
by
Number
—
Do
Not
Cut
Catalogue

For
Grinding
Wheels,
etc.,
See
Page 152
this
Catalogue



Sets of Carbon Steel Twist Drills in Metal Stands M30.

This Set comprises all the sizes of straight shank drills, Stubs, steel wire gauge, from No. 1-80 inclusive. Each hole is numbered to correspond to size of drill. The even numbers are on one side, the odd on the other, thus making selection very convenient.



Sleeves or Shell Sockets M31.


No. 1 to fit 2 Socket. No. 2 to fit 3 Socket.
No. 1 to fit 3 Socket. No. 3 to fit 4 Socket.

HIGH SPEED

Jobbers' Length Straight Shank Drills.

Stocked in
Sizes from 1/16" to 1/2" in 64ths of an inch.

PLEASE WRITE TO US FOR ANY TOOLS NOT LISTED IN THIS SECTION



M36.

Plain Screw Vises


High Grade Semi-Steel Replaceable Nut. Width of Jaw, 2½", 2¾", 3", 3½", 4", 4½", 5", 6", 7".



M37.

Quick Action Vises

The simple quick action mechanism enables jaws to be instantly set to any required width. High Grade Semi-Steel Castings. Width of Jaw, 3½", 3¾", 4", 4½", 5", 5½", 6", 7".



M38.

Offset Vises (Semi-Steel)

With plain screw. The patented design of this vise readily holds long vertical work with the full width of jaws. In six sizes. Width of Jaw, 3", 3½", 4", 4½", 5", 6".




Forged Hand Vise M39.

ENGLISH
MAKE.

Length:
3"
3½"
4"
5"
6"

VICES

*Famous "Dawn" Brand and
World Famous Makes*




Swivel Base Vises

M40.

Plain Screw.

The swivel base enables worker to swing vise to any lateral position, where it can be securely locked with two holding down screws. Made in Seven Sizes. Width of Jaw, 2½", 3", 3½", 4", 4½", 5", 6".

**For Woodworkers' Vises and
Cramps, see Page 149.**




M41.

Machine Vises

Semi-Steel Plain Screw.

Accurately machined slide faces and hardened steel jaws. Available in three sizes: 3", 4", 5", width of Jaw.



Improved Parallel Vise

M42.

The body of this Vise is made from good quality Cast Iron. The detachable Jaw Plates are of steel, specially cut and hardened.


No.	Width of Jaw	Opens to
00	2½"	2"
0	2¾"	2½"
1	3"	3½"
2	3½"	4"
3	4"	4½"
4	4½"	5"
5	5"	6"



Mathieson's Pin Vise

M43.


Hollow Handle.



M44.

Steel Guide Vises


Sturdily and accurately constructed, with 2" width of jaw, and a maximum opening of 2".



M45.

"Dawnette"

Another famous "Dawn" product, with a 2" width of jaw, and a maximum opening of 2".




M46.

Steel "T" Bar Vise

Cast Steel Jaws, with hardened serrated faces, mounted on mild steel brass plate, and mild "T" section slide bar.

Width of Jaw: 4", 5", 6", 7", 8".

Jersey Clamp Base Vise



M47.

No.	Width of Jaw
40	1½"
42	1¾"
44	2"
46	2½"

Strong, Efficient,
Reliable.

WE ARE GLAD TO GIVE QUOTATIONS, WRITE OR PHONE

Grinding and Polishing Heads




M48. (left)

The "Dawn," No. 22. Double polishing spindle and one set of flanges for $\frac{3}{4}$ " grinding wheel.

M49. (right)

The "Dawn," No. 24. Single polisher. Other end two flanges and drill chuck. $\frac{3}{8}$ " to spindle; $\frac{1}{2}$ " spindle; $2\frac{1}{2}$ " pulley.




M50. (right)

The "Dawn," No. 26. Double end grinding spindle. Two sets of flanges for $\frac{3}{4}$ " grinding wheel.



M51. (left)

The "Dawn," No. 28. Double end grinding and polishing spindle. Two sets of flanges for $\frac{3}{4}$ " wheels.



LIFTING JACKS




M52.

Broad base, low lift. Lifts 4" from $9\frac{1}{2}$ "; 3 ton and 6 ton. Also narrow base. 1 ton, lift 4" from 9"; 3 ton, lift $2\frac{3}{4}$ " from $6\frac{1}{4}$ ".

M53.

Narrow base, high lift. 3 ton, lift 9" from 15"; 5 ton, 9" from 20"; 10 ton, 12" from 24".



PARALLEL HAND REAMERS Of Special Alloy Steel


M54.

These Reamers are made with Spiral Flutes of left-hand direction, which type of flute prevents any dragging of the tool into the hole, and the blades thereby possess the advantage of imparting a shearing cut. They have the advantage over straight-fluted reamers, inasmuch as they do not tend to form pockets or corners, as the cutting edges do not lie parallel with the direction of the hole, and therefore in conjunction with the fact of the cutting edges being unevenly spaced, all risk of "chatter" is eliminated.

PARALLEL TYPE have a small taper at the point for $\frac{1}{2}$ inch and $\frac{3}{4}$ inch up, to ensure an easy start.

TAPER type have a straight taper the full length of the flute. In sizes $\frac{1}{2}$ to 1 inch, in 64ths.

Taper Pin Reamers



M55.

Spiral fluted. Taper— $\frac{1}{4}$ inch to 1 inch.

No.	Dia. Small End	Length over all
0	.135in.	2 $\frac{1}{2}$ in.
1	.146in.	2 $\frac{3}{4}$ in.
2	.162in.	3in.
3	.183in.	3 $\frac{7}{16}$ in.
4	.208in.	3 $\frac{1}{2}$ in.
5	.240in.	4 $\frac{7}{16}$ in.

"G.T.D." Taper Reamers



M56.

Sizes: $\frac{1}{2}$ ", 5/16", $\frac{3}{8}$ ", 7/16", $\frac{1}{2}$ ", 9/16", $\frac{5}{8}$ ", $\frac{3}{4}$ ".

Order by Number
Do Not Cut Catalogue

Burring Reamers with Spiral Flutes



These Burring Reamers are made of finest steel and designed especially for removing burrs, caused by cutting pipe. They are also extensively used for countersinking.

Great care is used in grinding these tools to adapt them for use in a variety of materials.

	Style of Shank	Capacity Pipe
M57.	Bit Brace	$\frac{1}{4}$ " to $\frac{1}{2}$ "
M58.	Bit Brace	$\frac{1}{2}$ " to 1"
M59.	Bit Brace	$\frac{3}{4}$ " to 1 $\frac{1}{2}$ "
M60.	Bit Brace	$\frac{1}{2}$ " to 2"

QUALITY, ECONOMY, RELIABILITY

HACK SAWS


Millers-Falls Extension Hack Saw Frames
M61.

A very popular Hack Saw. Heavily nickelled. Takes 8" to 12" saws. Quickly adjusted. Light. Made of Tempered Steel. Handles of Cocobola Wood. Highly Finished


Goodell-Pratt Solid Steel Hack Saw Frames
M63.

Similar design to M71. These Frames are made of solid steel, natural finish. They have polished hardwood handles. Blade can be faced four ways. Depth of throat, 2 3/4". In four sizes, for 8", 9", 10" and 12" Blades.

HACK SAW BLADES FOR POWER MACHINES

M68.
Sterling

Length	Width	Thick	Teeth per inch
12"	3"	21	14
14"	3"	21	14
17"	1"	18	12

Ding Dong Hack Saw Blades
M69.

In either 14, 24, 32 teeth to inch. Sizes: 8", 9", 10", 12".

Ding Dong Hack Saw Blades
M70.

In either 14, 24, 32 teeth to inch. Sizes: 8", 9", 10", 12".

M71.
Goodell-Pratt Solid Steel Hack Saw Frames

These frames are similar to Fig. M63, as described above, excepting depth of blade to back, which is 5 1/4". Takes 12" Blade.


Millers-Falls Rigid Back Extension Hack Saw Frames
M62.

This frame is extra heavy, highly finished, and very rigid. Heavily Plated. Will take 8" to 12" saws.

Millers-Falls Hack Saw Frames

M65.

At left. Cast iron frame and hardwood handle. Blade faceable in 4 directions. 8", 9", 10" or 12".


M64.



At right. Adjustable from 8" to 12". Thumb nut to secure blade tension. Complete with 10" Blade.



Millers-Falls Coping Saw Frames



M66.

Below. 4 1/2" throat. Blade locks, facing any of 4 directions.



M67.

Above. 4" throat. Equipped with one Blade in frame and 1 doz. spares.

For CARPENTERS' SAWS, See Page 135.


M72.
Jewellers' Saw Frame

M73.
Jewellers' Saw Frame

Metal Cutting Blades for Jewellers' Saw Frame

M74.


MILLERS-FALLS KEYHOLE HACK SAW

M75.


FOR CUTTING METAL OR WOOD

Cuts nails, metal lath, plaster board, stucco, armoured cable, conduit, packing, bakelite, fibre, hard or soft wood, etc. Ideal for use in corners where an ordinary hack saw frame will not go. Light, flexible, strong.

WE STOCK TOOLS BY THE WORLD'S FOREMOST MAKERS


**Millers-Falls Patent File Handle
M76.**

While this handle holds perfectly files with tangs of all sizes and shapes, and is primarily a file handle, yet it also holds a variety of shanks of different shapes and sizes which do not exceed $\frac{3}{4}$ " square or flat.

Malleable iron handle, japanned black. Screw and yoke white nickel. Length: $5\frac{1}{4}$ ".




**Boxwood Bossing Mallets
M77.**



Sizes: 2", 2 $\frac{1}{4}$ ", 2 $\frac{1}{2}$ ", 2 $\frac{3}{4}$ ", 3".

**Tinsmiths' Boxwood Mallets
M78.**




Sizes: 2", 2 $\frac{1}{4}$ ", 2 $\frac{1}{2}$ ", 2 $\frac{3}{4}$ ", 3", 4".

**Boxwood Turnpins
M79.**



Sizes: $\frac{1}{4}$ ", 1", 1 $\frac{1}{2}$ ", 1 $\frac{3}{4}$ ", 1 $\frac{1}{2}$ ", 2", 2 $\frac{1}{4}$ ", 3".

**Boxwood Dressers
M80.**



Sizes: 2", 2 $\frac{1}{4}$ ", 2 $\frac{1}{2}$ ", 3".

**Boxwood Bossing Stick
M81.**



**Boxwood Bending Stick
M82.**



**Boxwood Bobbins and Followers
M83.**




Bobbins—
Sizes: $1\frac{1}{4}$ ", $1\frac{1}{2}$ ", 2", 2 $\frac{1}{2}$ ", 3", 4".
Followers—
 $1\frac{1}{16}$ ", $1\frac{1}{8}$ ", $1\frac{1}{4}$ ", $1\frac{3}{8}$ ", $1\frac{1}{2}$ ", $1\frac{5}{8}$ ", $1\frac{3}{4}$ ".

FILES

A Comprehensive Range of English and
Nicholson Files Always in Stock

NICHOLSON'S FILES



Bastard Files

M84.—Flat. M85.—Half Round. M86.—Round.

M87. Square

Sizes: 3", 4", 5", 6", 8", 10", 12", 14", 16".

Hand Bastard Files

M88.

Sizes: 3", 4", 5", 6", 8", 10", 12", 14", 16".

Hand Smooth Files

M89.

Sizes: 3", 4", 5", 6", 8", 10", 12", 14", 16".

Second Cut Files

M90.—Flat. M91.—Half Round

Sizes: 3", 4", 5", 6", 8", 10", 12", 14", 16".

Hand Second Cut Files


M92.

Sizes: 3", 4", 5", 6", 8", 10", 12", 14", 16".

Smooth Files

M93.—Flat. M94.—Half Round

Sizes: 3", 4", 5", 6", 8", 10", 12", 14", 16".




The "Dreadnought" Patent Milling Files

M95.—Tanged Pattern Taper Flat

M96.—Tanged Pattern Hand Parallel, with One Safe Edge.


Sizes: 10", 12", 14".

In Regular Out, Fine Out, and Combined Cuts (one side Regular, the other side Superfine). The Dreadnought Milling File cuts equally well Cast and Wrought Iron, Steel, Iron, Bronze, and all other Hard Metals, and owing to its self-clearing properties cuts lead, brass, aluminium and other soft metals without clogging. It is also invaluable for use on slate, marble, fibre, wood, vulcanite, rubber, etc., etc.



**Warding Files
M97.**

Sizes: 3", 4", 5", 6", 8".



**Horse Rasps
M98.**

Sizes: 14", 15", 16".

GOOD TOOLS ARE AN INVESTMENT

Pocket Screwdrivers M99.

This Tool is made from steel tubing, knurled and nickel-plated. The shank of the blade fits a solid lock in the tube, preventing it from turning, and is held from coming out by a slight turn in the chuck. To carry in pocket, reverse the blade, inserting it in the handle, giving a slight turn of the chuck to keep it there. It takes no more room in the pocket than a penknife.



Starrett's Screwdrivers for Eyeglasses and Other Small Screws M100.

Screws in eyeglasses have a provoking way of getting loose. This little tool is just the thing to have at hand in such cases. It is made in two pieces and screwed together, telescoping the driver blade when not in use. It is nickel-plated, neat to carry in the pocket, or key ring, or to attach to a watch chain.



Starrett's Jeweller's Screwdrivers M101.

Substantially made from steel tubing, knurled and nickel-plated. Five constitutes a set, with blades varying from .040 to .100 inch in width. The blades are held from turning in the handle by a solid lock, and from coming out by a slight turn of a neat chuck. The top is finished with a swivel knob concaved to fit the finger and hexagonal in shape to prevent rolling off the bench. To designate the size at a glance, the chuck end is marked with various grooves, four grooves indicating the finest size A, three grooves the next larger B, two grooves C, one groove D; the largest size, E, being plain.

Saw Punch (No. 200)

M106.



There is so much variation in the sizes of various styles of butchers' saw frames that most of the better class of butchers' saw blades are not punched when they leave the factory. All dealers in and users of these blades will find this inexpensive device very convenient for punching the necessary holes. The frame is made of nickel-plated, malleable iron. The screw and crossbar are polished steel. The punch and die are made from fine tool steel, carefully tempered. Length over all, 5 3/4". Size of punch 1/2". Net weight, 7 ounces.


Square Head Centre Punch M107.

Bright finish. Body, 5/16" diameter. Head, 1/2" square. Length over all, 4 inches.

Solid Punches (All Steel)


M108.

These Punches will be found very useful for punching holes in Thin Sheet Metal, driving out pins, etc. Sizes—



DANKS for TOOLS for all TRADES!

AMATEUR OR TRADESMAN, WE CAN SUPPLY YOUR REQUIREMENTS



Starrett's Magazine Screwdriver M102.

This is a Pocket Screwdriver with four blades of different widths, any of which may be quickly taken from the telescopic handle and inserted in the end, which is automatically locked and firmly held for use.

The smaller blades may be used to make holes in wood, to start screws as well as to drive them home. The widths of the blades are 3/32", 5/32", 3/4", and 1".

For other SCREWDRIVERS, see Page 141 this Catalogue

Three Square Scraper M103.

For scraping valves, babbitt metal, journals, bearings, etc. Made of fine English steel, perfect hollow ground, hardened and tempered; 3 1/2" blade, polished wood handle, brass ferrule.

M104. Curved Scrapers IN SETS

These scrapers have the flat or under side depression 1/2", the cutting edges being 1/16" wide. Can be sharpened on the oilstone, and need never be put on a grinding wheel. Best English File Steel.


Set of 3, one each 10", 12", 13".

Bell Centering Punches

Designed to quickly and accurately centre both round and square stock. Each tool has four case-hardened steel bearings. The punch runs through a guide, giving the punch an accurate bearing throughout its length. The punch is made of 5/16" tool steel, hardened and tempered. The entire tool is polished.

No. 523.—Centres up to 1 inch.

M105.



No. 534.—Centres up to 1 1/2 inches

Automatic Adjustable Stroke Centre Punch

M109.



The ordinary hammer and centre punch are not sufficiently accurate when laying out fine work. They require the use of both hands, and the accuracy of the blow depends upon the skill of the mechanic.

This Patented Centre Punch contains a mechanism which automatically strikes a blow of any required force when the punch is in the exact position desired by the operator. It is provided with a knurled adjustable screw cap, which, working in connection with a spring, regulates the stroke. For work requiring a heavy mark, turn cap down; for work requiring a light mark, turn it up. To use it, no hammer is needed. The punch being placed in an upright position over the working line, a downward pressure releases the striking block and makes the impression without danger of slipping, as is liable when a hammer is used. When adjusted for either light or heavy stroke, all indentations are of a uniform size for the starting of the drill, etc., and more accurate and quicker work may be done as required on delicate work in tool making. The working parts are hardened, durable and accessible for such repairs as may ever be needed. The adjustable cap fits the hand, with no stroke adjusting screw through and above it to bother. The point can be removed for regrinding and easily replaced. The AA size is 3 3/4" long when adjusted for medium stroke, 3/4" diameter, and weighs 1 ounce. The A size is 5" long when adjusted for a medium stroke, 3/4" in diameter, and weighs 3 ounces. The B size is 6 inches long when adjusted for a medium stroke, 5/8" in diameter, and weighs 4 ounces. It differs from the other sizes in being larger and capable of striking a much heavier blow.

Sizes: 18AA, 18A, 18B.

Starrett's Centre Punches M110.

Made of Fine Grade Steel. Both Ends Tempered, and Points Nicely Ground. Sizes: 5/64", 3/32", 9/64", 5/32", 3/4". Length of each size, 4 inches, except E, which is 5 inches. Moore & Wright's also stocked.



Countersink M111.

Superior Steel, and can be used in either hard or mild steel.



Precision Tools

Inside A M112. Outside B Starrett's Improved Firm Joint Callipers

The improvements in these Callipers prevent the stud from turning when loosening and tightening, and ensure a smooth and uniform friction of more or less tension to suit the user. Sizes: 3", 4", 5", 6", 8", 10", 12", 18"

Inside C M113. Outside D Starrett's Lock-Joint Transfer Callipers

These Callipers may be used inside of chambered cavities, over flanges, etc., removed and replaced without losing the size callipered. Sizes: 4", 5", 6", 8", 10", 12", 16", 18"

Inside E M114. Outside F Perfected Firm-Joint Screw Adjusting Callipers

Screw adjustment for fine measurements; improved joint, which may be set to any desired degree of uniform tension. Sizes: 4", 6", 8", 10", 12", 14", 16", 18"

Inside G M115. Outside H Starrett's Lock-Joint Callipers

A reliable Lock-Joint Calliper of wide scope for both inside and outside work. Sizes: 4", 5", 6", 8", 10", 12", 14", 16", 18", 20", 24"

Outside J M116. Inside I Yankee Callipers

Similar to the Fay pattern, but are lighter. They are very reliable. With either solid or spring nut. Sizes: 2½", 3", 4", 5", 6"

Outside K M117. Inside L Starrett's Toolmaker's Callipers

Made from round stock with legs drawn down. Finely finished. They are made with solid nut only. Sizes: 2", 3", 4", 5", 6"

Inside N M118. Outside M Thread Callipers

These Callipers are designed for measuring the diameter at bottom of inside or outside threads. Sizes: 4", 5", 6"



M119. (O) Yankee Spring Dividers

Sizes: 2½", 3", 4", 5", 6"

M120. (P) Toolmaker's Dividers

Sizes: 2½", 3", 4", 5", 6"


NOTE.—Callipers and Dividers are sent with Solid Nut unless otherwise ordered.



Starrett's Hermaphrodite Callipers M121.

With adjustable point, lock joint and sensitive adjustment. Reverse cut shows adjustable point; the front cut the lock-joint and sensitive adjustment. The adjustment is obtained by the knurled disc. Sizes: 4", 6", 8"

M122.
Adjustable points and improved firm joint. Sizes: 4", 6", 8"



Also stocked M123, Starrett's Spring Nut Callipers (Q and R), and M124, Starrett's Thread Callipers (S), Spring Nut.

DO NOT CUT
CATALOGUE,
ORDER BY
NUMBER.

Index Callipers M125.

May be used as either inside or outside, and registers in inches and metres. Sizes: 5", 7"



Pocket Scribes (No. 70)




M126.
This tool is made from steel tubing, knurled and nickel plated. The scriber is made from the best quality of steel, nicely tempered, and is held by a knurled chuck.
Size A: Handle ¾" diam., blade 2½" long.
Size B: Handle 1" diam., blade 2½" long.

HIGH GRADE TOOLS AT REASONABLE PRICES

GAUGES

SCREW PITCH
THICKNESS
CENTRE
FILLET AND
TAPER WIRE

Improved
Screw Pitch
Gauge
M130.



Starrett's Thickness
Gauge or "Feeler"
M133.



This Gauge has 22 leaves, varying in thickness by thousandths, running from .004 to .025. The thickness of each leaf is designated by the number upon it. Length when folded up, 2 1/2".



Thickness Gauge
M127.

A favourite Gauge with machinists and toolmakers in gauging narrow slots, as well as with the motor mechanic in adjusting the air gap for the valves on motors.

Size A has nine leaves, viz.: .0015, .002, .003, .004, .006, .008, .010, .012 and .015, with either straight leaves as shown, or with tapering leaves.


Sizes B and C have eight leaves the same as A with the omission of .0015.

Size A—Case 3 3/8" long by 1 1/2" wide; leaves 3 1/16" long by 3/8" wide.

Size B—Case 4 1/2" long by 1 1/2" wide; leaves 4 1/2" long by 3/8" wide.

Size C—Case 6 1/2" long by 1 1/2" wide; leaves 6" long by 1/2" wide.

Metric
Screw Pitch
Gauge
M128.



This Gauge is similar in design to 66972 with V thread. The base of this system is one millimetre. It is pitched from 1/2 millimetre up to 2 1/2 millimetres.

Whitworth
Screw Pitch
Gauge
M129.



26 pitches, 4 to 60
Has the following pitches:
4, 4 1/2, 5, 6, 7, 8, 9, 10,
11, 12, 13, 14, 16, 18, 19,
20, 22, 24, 25, 26, 28, 30,
32, 40, 48, 60
For Whitworth Standard
Thread only.

In this Gauge the free end of the leaf is made narrow, permitting it to be inserted in a small nut so that either outside or inside threads may be compared.

A late improvement in our screw pitch gauge is the stamping on each leaf of decimals showing the double depth of thread, which, of course, equals the depth of threads on the two sides of a tap having the same pitch. This enables the workman to determine what size of drill must be used to leave a full V-thread for a tap having the same pitch. To do this, calliper with a micrometer over the threads of the tap and from its size in thousandths shown, deduct those decimals given on the pitch gauge leaf which agree with the pitch of the tap. The result will show in thousandths the size of drill needed for a full thread. Allowance is to be made for the amount the thread is to be flattened.


The gauge has 22 pitches, viz.: 9, 10, 11, 11 1/2, 12, 13, 14, 15, 16, 18, 20, 22, 24, 26, 27, 28, 30, 32, 34, 36, 38, 40.

Thickness Gauge
M131.



Starrett's (No. 71) contains the following leaves: .0015, .002, .003, .004, .006 and .015. This combination of leaves permits the adjustment of tappets on motors and the gauging of slots from .0015 to .031. The leaves fold neatly in a metal case.

M132. Centre Gauges



For setting and grinding screw cutting tools.

Fillet or Radius Gauge
M135.

This Gauge affords means of obtaining the radii of fillets, corners, etc., as shown by the illustrations. Each blade is stamped with the radius in 64ths, the external being on one side and the internal on the other. It can be used in any position or at any angle, the formation allowing it to be used up to a shoulder, and for duplicating sample pieces. The studs holding blades in place are eccentric with the round end of case. This is of advantage, as when the gauge is opened the edge of case stands well away from the edge of the leaves.

Size A has 16 leaves, with radii from 1/32" to 17/64", inclusive, by 64ths.


Size B has 16 leaves, with radii from 5/32" to 33/64", inclusive, by 64ths.

Taper Wire and Thickness Gauge
M134.

This Gauge is especially designed for the use of marine engineers, machinists and others desiring a set of gauges in compact form.

The taper gauge shows the thickness in 64ths to 5/16" on one side, and on the reverse side is graduated as a rule 3" of its length, reading in 8ths and 16ths of an inch.

The wire gauge, English standard, shows on one side sizes numbered from 19 to 36, with two extra slots, one 1/16", the other 1/8" of an inch, and on the reverse side shows the decimal equivalents expressed in thousandths. This gauge has also nine thickness or feeler gauge leaves, approximately 4" long, of the following thicknesses: .002, .003, .004, .006, .008, .010, .012, .015 and 1/16", all folded within the case, which is 4 1/2" long, convenient to handle or to carry in the pocket.



AUSTRALIA'S LARGEST RANGE OF PRECISION TOOLS!

DANKS, ESTABLISHED IN 1859

**Starrett's Universal
Surface Gauge**


(No. 57)

M136.

Stock Spindle

Size A—3" 9".
Size B—3" 9" and 12".
Size C—3½" 12".
Size D—3½" 12" and 18".

This is an improved and most desirable gauge. The base is heavy and grooved for use on or against cylindrical work. The bracket being adjusted by a knurled screw in one end, against a stiff spring in the other, the spindle may be set upright or at any angle, or turned so as to work under the base and be sensitively adjusted to any position within its capacity.



Starrett's New Surface Gauge

(No. 257)

M137.


With Case-Hardened Steel Base

This Gauge has all the latest improvements. Its base is heavy and grooved through the bottom and end, adapting it for use on or against circular work as well as flat surfaces. The spindle may be set upright or at any angle, or turned so as to work under the base, and can be sensitively adjusted to any position. In the base are four gauge pins, frictionally held, which may be pushed to bear against the edge of a surface plate, or in the slot of a planer bed for lineal work.

For small work the spindle may be removed and the scriber inserted in a hole provided for it, where it can be sensitively adjusted and used to advantage on bench work. Special attention is called to the four gauge pins at the corners of the base, which adapt it to be used as a locomotive guide liner, and make it more convenient than other gauges for many uses.

An extra long spindle, which may be quickly substituted for the regular, will be sent with the gauge when ordered.

A—3" base, with 9" spindle.
B—3" base, with 9" and 12" spindles.
C—3½" base, with 12" spindle.
D—3½" base, with 12" and 18" spindles.




Depth Gauges

(No. 46)

M138.

Has in place of the round wire to slide in the groove, as shown with No. 45, a 4" or 6" scale, 8/16" wide, graduated in either 32nds and 64ths, or 64ths and 100ths, indicating exact measurements, and may be used separately from the gauge. This tool, like our No. 45, can be used with the scale clamped close to the end, allowing depth measurements to be taken in difficult places.

Size A with 3½" stock and 4" scale.
Size B with 3½" stock and 6" scale.
Size C with 6" stock and 4" scale.
Size D with 6" stock and 6" scale.



**Starrett's Registering Speed Indicator
M139.**



This instrument will automatically register hundreds as well as units and tens, thus relieving the mind from keeping tally. It will register up to 5000 revolutions and it is fitted with a hard rubber handle, making a safe insulator when used on electrical machinery. Nickel-plated.

**Starrett's High Speed Indicator
M140.**




The frictionless bearing against which inner end of spindle revolves prevents heating. The working parts are encased, and dial plate has two rows of figures, reading right and left as the shaft may run.

By moving the rotating disc to the starting point where the raised knobs coincide, the disc may be prevented from rotating by pressing the raised knob with the thumb. When the hand of your watch gets to the right position to take time, release the pressure, and thus liberate disc for counting revolutions. Every hundred may be noted by feeling the knob pass under the thumb lightly pressed against it, thus relieving the eye, which has only to look on the watch to note time.

**Universal Test Indicator
M141.**

This indicator may be used to test inside, outside or surface work. It can be instantly attached to the spindle or the scriber of any surface gauge, and used to show the slightest variation in thousandths. It may be clamped to a flat or round support, up to 8" flat or round.

A holder, as shown in cut, is designed to go in the tool-post of a lathe, adapting it for use to show the accuracy of all sorts of lathe work, turning, chucking, or locating and centering work on face plate. It is particularly adapted to truing up tool-makers' buttons, as it can be moved with the carriage of a lathe testing the button its full length. The head of the needle has three working points, equally distant from its fulcrum, so that the needle will vibrate, readings in thousandths, when work is in contact with either point—in front, above or below it. When in front, the spring operating the needle needs to be reversed to throw the point of the needle up instead of down, as when used above or below the work. This may be instantly done by a slight turn of the knurled disc to which the vibrating spring is attached. The working parts of the head are hardened. In setting the indicator, bring the contact point against the work so that the needle will point to 0, when any variation either way will show. The scale is graduated to read .015" on each side of 0.




As applied to surface gauge.

M142. No. 64A Indicator, with Tool-Post Holder and Arm complete.
M143. No. 64B Indicator only.


Do Not Cut Catalogue . . . Order by Number

M144. Universal Dial Test Indicator

Simple, reliable, easily read and very sensitive, it may be adjusted to any angle. The slightest pressure upon contact point produces a movement of the hand on the dial. Circumference of dial divided into 100 equal spaces, each representing a movement of the contact point of one-thousandth of an inch. One revolution of the hand, therefore, indicates one-tenth of an inch, the capacity of the instrument being two-tenths. With the contact points D and E any exterior surface may be tested as in cutters, racks, etc., whereas the contact point C with its smaller radius and diameter should be used only on plain surfaces. By bringing the contact point against the work with just enough pressure to give the hand one full turn, then setting it at 0, an opportunity is given for one full revolution of the hand to both right and left of 0, showing a rise or drop in the work and the amount of variation. A most valuable feature is the adjustable dial. By turning the knurled rim the dial may be instantly moved to bring the 0 mark to any point desired in relation to the hand. Each indicator is fitted with three hardened contact points for different classes of work. The special tool post holder and sleeve are useful in lathe work. For general work the indicator with sleeve K is adapted for use with our 9" or 12" surface gauges, No. 57 A and B, and No. 257 A and B.



The clamp G permits attaching the indicator to large lathe and planer tools, milling Arbors, etc.
The attachment F more than doubles the value of the indicator, adapting it for use inside of holes, to reach over blockings on face plates, etc.
No. 196A, Indicator with all attachments, as shown.



M150.
One-inch Micrometer Callipers

With Lock Nut and Ratchet Stop.
By thousandths to 1".

M151. **Two-inch Micrometer Callipers**
With a 1" Attachment.

M152. **Half-inch Micrometer Callipers**
With Lock Nut and Ratchet Stop. (No. 215).
To measure by thousandths up to $\frac{1}{2}$ ".

M153. (No. 219)
With Lock Nut and Ratchet Stop for measurements by ten thousandths up to $\frac{1}{2}$ ".

Micrometer Calliper Gauges

M154.

These Callipers meet the demand for accurate gauges at a low price. They are better adapted for general use than the Vernier or bar micrometer, as they can be set quickly for the different measurements and are more easily read.

Each Calliper is graduated to read by thousandths of an inch, is furnished with a lock nut, and is sent with or without ratchet stop as desired. The frames are drop forged from bar steel and are nicely finished. The 1" has the decimal equivalents stamped on the frame. The other sizes are marked to show their capacity.

Sizes: 1", 2", 3", 4", 5", 6".


Inside Micrometer Callipers

M155.


No. 124, like No. 120, is designed for internal and linear measurements, such as measuring cylinders, rings; also for setting callipers, comparing gauges, etc. It is also useful in measuring parallel surfaces. The micrometer screw in the head has $\frac{1}{2}$ " movement in Sets A and B, 1" in Set C, and, by means of the extension rods furnished, the sizes as given below for each set can be obtained. The extension rods are provided with a collar, against which the rods are conveniently and accurately set in the micrometer head. In setting these rods, see that the zero mark on the collar coincides with the zero mark on the micrometer head.

Set A has 6 rods and one $\frac{1}{2}$ " gauge, and measures from 2" to 8".
Set B has 10 rods and one $\frac{1}{2}$ " gauge, and measures from 2" to 12".
Set C has 4 rods and one 1" and two 2" gauges, and measures from 8" to 32".

The auxiliary handle, as shown in cut, can be used with Sets A, B, and D. The handle is used by removing the nut opposite the lock nut and screwing the handle in the place of same, thus fitting the tool for use in places too small for the hand.



MICROMETER CALLIPERS




M145.
Two-inch Micrometer Callipers
(No. 2)

For measurement by thousandths from 1" to 2", with lock nut, ratchet stop, and 1" test gauge.

Note—This Micrometer Calliper we also furnish with lock nut at end of frame.


M146. (No. 213)

For measurement by ten thousandths from one inch to two inches, with lock nut, ratchet stop, and one-inch test gauge.



M147.
Two-inch Micrometer Callipers
(No. 217)

For measurement by thousandths from 1" to 2". Has lock nut and 1" test gauge, but no ratchet stop.



M148.
Metric Micrometer Callipers

For measurements by hundredths of a millimeter up to twenty-five millimeters. May be furnished, when so desired with lock nut on end of frame.
Has lock nut and ratchet stop.

M149. (No. 214)

Similar to above, but for measurements by ten thousandths from 1" to 2".



Starrett's Vernier Callipers
M156. (No. 122)

These Callipers are graduated in either or both English and Metric divisions for outside and inside measure, and are warranted accurate. Points are placed on the beams and slides for setting dividers to transfer distances. Full directions for using the Vernier are sent with each calliper. The jaws are hardened, ground and lapped, parallel to each other, assuring accurate measurements at any contact points of the jaws. These callipers are sent with finely finished plush lined case. Sizes: 4", 6". Graduated on the front to read by means of the Vernier in 1000ths of an inch. Graduated in 64ths on the back.

M157. Metric and English

The same as No. 122 except that it has a Vernier on each side and is graduated to read by means of the Verniers, on the front in 50ths of a millimetre and on the back in 1000ths of an inch, with jaws ground to Metric widths as or Sizes: 150 mm. or 6", 200 mm. or 8".

M158. Metric and English

The same as No. 122 except that it has a Vernier on each side and is graduated to read by means of the Verniers on the front in 1000ths of an inch and on the back in 50ths of a millimetre, with jaws ground to English widths as or Sizes: 6" or 150 mm., 9" or 200 mm.

Sent with case unless otherwise ordered.

M159. Sliding Calliper Gauge



With a 5" scale accurately made and graduated for taking external or internal measurements. Slide extension for depth gauge. Has lock thumb screw. Nickel plated and leather pocket. Metric and English graduations with Vernier reading to 10 millimetres and 128th inch. English graduations with Vernier reading on one edge to 128ths. and on other 1000ths of an inch.

MAKE THIS CATALOGUE YOUR
GUIDE FOR ALL YOUR NEEDS!

"Time Saver" Tap and Drill Gauge M160.



This Gauge is approximately $\frac{5}{16}$ " thick, $2\frac{5}{16}$ " wide and 6 $\frac{1}{2}$ " long. It is hardened, ground and rubbed to a bright finish and is thoroughly tested after hardening.

By the use of this gauge one is enabled to select at once the right-sized drill to suit machine screw taps most commonly used, leaving just stock enough for the tap to cut as near a full thread as is practicable for one tap without breaking it, thus saving much time and uncertainty of result attending the former crude ways of making a selection.

SEE PAGE 170 ON HOW TO READ
A UNIVERSAL BEVEL PROTRACTOR
WITH VERNIER




M161.



Double Circular Wire Gauge

Imperial Standard Wire Gauge M162.

Sizes of the Numbers of Imperial Standard Wire Gauge. This Gauge has black finish, and the decimal equivalents of each number are stamped on the back. Each gauge tested carefully after hardening.




Standard Wire Gauge M163.



M164. Jobbers' Drill Gauge

This Gauge shows sizes from $\frac{1}{16}$ " to $\frac{1}{2}$ ", varying by 64ths. Each size is designated by both common and decimal fractions. Gauge is hardened and tempered, and the holes standard.




M165. Drill and Steel Wire Gauge

This Gauge gives the number of drill to fit each hole, and the size of the hole in thousandths of an inch.

TO OBTAIN RESULTS, THE BEST TOOLS ARE NOT TOO GOOD

COMBINATION SETS AND SQUARES




Bevel Protractors

M166.

With Hardened Blade and Reversible Head
(No. 490)

This tool has the special feature of having the head extend both sides of the blade. This greatly increases the usefulness of the tool, as the same angles may be transferred from either side of the frame without re-setting. Another improvement is that the turret is graduated to read both ways from 0 to 180 degrees. Mechanics will clearly appreciate the point, as direct readings may be had from the turret, indicating the supplement of the angle as well as the angle required. The fact that there is but one zero line on the frame eliminates all possible chance of confusion as to whether acute or obtuse angles are obtained. The head of the Protractor is 7" long and is supplied with an accurate level attached to one side as shown by cut. The blades are hardened and graduated with heavy figures reading both ways No. 4 graduation. 9", complete.



M167.

Starrett's Combination Sets

(No. 9)


With Hardened Blade

This cut shows Combination Set, with centre head and 7" bevel protractor head. Each head is interchangeable with the scale. Furnished with No. 4 and No. 7 graduation. No. 4 graduation sent unless otherwise ordered. Sizes: 9", 12", 18", 24".

M168.

Starrett's Universal Bevel Protractor


(No. 360)



Adapted for work in positions where others cannot be used, and renders the common universal bevel (for transferring angles) unnecessary.

The attachment shown in the smaller engraving will be found very convenient for grinding worm thread tools, tapers on lathe centres, and all long tapers.

Sizes A: 7". Size C: 12".
Size E: With both 7" and 12" blades.
Attachment extra.



M169.

Starrett's Combination Square

(No. 11)

With Hardened Blade

This useful, convenient tool combines Depth Gauge, Try, Mitre and Centering Squares. The blades are hardened and graduated in No. 4 and 7 graduation with heavy figures, reading both ways. 4", with centre head, no level. 6", with centre head, with level. 9", with centre head, with level. 12", with centre head, with level.


M170.

Combination Sets

(No. 434)

With Hardened Blade

The Set consists of Combination Square, with hardened, drop forged stock and centre head and Reversible Protractor Head. Furnished with No. 4 graduation. 9", set complete; 12", set complete.




How to Read Universal Bevel Protractor with Vernier

The disc of the Protractor is graduated in degrees from 0° to 90° each way. The Vernier plate is graduated so that 12 divisions on the Vernier occupy the same space as 23 divisions on the disc. The difference between the width of one of the 12 spaces on the Vernier and two of the 23 spaces on the disc is therefore 1/12 of a space on the disc. Each space on the Vernier is 1/12 of a degree or five minutes shorter than two spaces on the disc. If a line on the Vernier coincides with a line on the disc and the protractor is rotated until the next line on the Vernier coincides with the next line but one on the disc, the Vernier has been moved through an arc of 1/12 of a degree, or 5 minutes.

To read the protractor, note on the disc the number of whole degrees between 0 on the disc and 0 on the Vernier. Then count in the same direction the number of spaces from 0 on the Vernier to a line that coincides with a line on the disc. Multiply this number by 5 and the product will be the number of minutes to be added to the number of whole degrees.

In the above engraving the number of degrees between 0 on the disc and 0 on the Vernier is 52. The line marked 45 on the Vernier coincides with a line (70) on the disc, the number of spaces from 0 being 9. Multiplying this number by 5 gives 45. The number of minutes to be added to the number of degrees. The reading of the protractor is 52 degrees 45 minutes (52° 45').



Order by Number Only
Do Not Cut Catalogue

Universal Bevel Protractors with Vernier and Acute Angle Attachment

(No. 364)

M171.


This Protractor is made with Verniers reading five minutes or one-twelfth of a degree. The Verniers are so placed with relation to the graduated half circle as to make the protractor readable by Vernier in any position. The protractor stock is 4" long and has either a 7" or a 12" blade, 1/2" wide. With the 7" blade the tool weighs but six ounces. The disc is graduated in degrees from 0 to 90 each way and rotates the entire circle on a central stud inside the case. The blade, clamped by an eccentric stud against the edge of the disc, may be slipped back and forth its full length, or turned at any angle around the circle and firmly clamped at any point. Attention is called to the fact that the figures on the Vernier are placed close to the lines, thus making it easy to read the tool when taking measurements. Attention is also called to the central locking nut on this protractor. By a slight turn of this nut the protractor is firmly held in position. The acute angle attachment enables the user to obtain very small angles.

Size A: 7"; Size C: 12".

NO JOB IS DIFFICULT IF YOU HAVE THE CORRECT TOOLS


Starrett's Universal Bevel M172.

The set off in Blade increases its capacity and usefulness for Bevel Gear Work, etc., so that any angle, however slight, may be obtained.
Length, 3".



Starrett's Combination Bevel M173.

This bevel has a stud riveted in the straight edge stock or head, on which its split blade is hinged, so as to swing over the stock, and be clamped at any angle. The slotted auxiliary blade with clamp bolt may be slipped on to the split blade, and be clamped at any desired angle, and used, in combination with the stock of the other, for laying out work, measuring, or showing any angle desired, and, when so combined, will lie flat upon its work.
Length, 4".



Engineers' Steel Rules



M174.

No.	Length	Markings
1	12"	Tapping and Spanner sizes, inches, 1/16ths, 1/32nds, 1/64ths.
10	12"	Marked one side, inches, 1/8ths, 1/16ths.
11	12"	Marked one side, inches, 1/8ths, 1/16ths, 1/32nds, 1/64ths.
11c	12"	Narrow and very flexible, marked same as No. 11.
14	12"	Marked one side, 1/10ths, 1/20ths, 1/40ths, 1/50ths, 1/100ths, 1/16ths, 1/32nds, 1/64ths.
25	12"	Marked both sides, inches, 1/8ths, 1/16ths, 1/32nds, 1/64ths.
34	12"	Marked both sides, inches, 1/16ths, 1/32nds, 1/64ths, millimetres.
11	18"	Marked one side, inches, 1/8ths, 1/16ths, 1/32nds, 1/64ths.
11	24"	
11	36"	


Steel Rules, 2 ft., 2 fold M175.



(No. 1641) Marked 1/8ths, 1/16ths, 1/32nds, 1/64ths.
(No. 1644) Marked 1/8ths, 1/16ths, and Millimeters.

Also in Brass, 2 fold, 2 ft. long M176.

2 feet long, marked 8ths and 16ths. Machine made of hard brass, flexible.
(No. 1494), 2" wide, round stop joint. (No. 1495), 1" wide, round stop joint.
(No. 1498), 1 1/2" wide, stop joint.



Flexible Folding Steel Rules M177.


One Foot, Three Fold.
Marked 1/16ths, 1/32nds, 1/64ths.



Flexible Folding Steel Rules M178.

One Foot, Three Fold
Marked 1/16ths, 1/32nds, 1/64ths, and Millimeters on one edge.

RULES



Starrett's Spring Tempered Rules (No. 300.)

M179.

Graduations 1st corner in 64ths, 2nd corner in 32nds, 3rd corner in 16ths, 4th corner in 8ths. Thickness, 3/4ths. Approx.—Widths: 3", 8", 3", 1". Lengths: 2", 4", 6", 12".
(No. 303.)

M180.

Has same graduations as No. 300, except that it is graduated in 32nds on opposite sides at one end. Approx.—Widths: 3", 8", 3", 1". Lengths: 2", 4", 6", 12".
(No. 400.)

M181.

With one bevelled edge and end graduation. Has same graduations as No. 303, except that it has 64th graduations on the bevel edge. Approx.—Widths: 3", 8", 3", 1". Lengths: 2", 4", 6", 12".
(No. 603.)

M182.


Graduations similar to No. 400, except that the rule is figured so as to enable the user to quickly read the 64ths. Approx.—Widths: 3", 8", 3", 1". Lengths: 2", 4", 6", 12".



Patternmakers' Steel Contraction Rules, 24 inch (No. 19.)

M183.

Standard, Single and Double Contraction for Iron, Single Contraction for Brass.




Starrett's Steel Rules

M184.

These are very thin spring-tempered rules, nicely graduated on one side only. Those from 1" to 12" are 3/4" wide, and will easily conform to a 2" circle. Those from 18" to 48" are 1 1/4" wide, and are made from a trifle heavier stock.

Graduated in 32nds and 64ths.
Length: 2", 3", 4", 6", 9", 12".



Folding Steel Rules

M185.

Sizes: 12", 24".

LEVEL SIGHTS, LEVEL TUBES,
Etc., see Page 144



M186.

Starrett Cross Test Level

As the cut shows, two levels are united in one frame, extending at right angles 2 1/2" each way. The level weighs but four ounces. When placed on work to be levelled in both directions, it will not be necessary to move the tool.


Improved Levels for Testing
M187. Shafting, etc.

In addition to the regular parallel vial, the bases have a cross level which enables one to place or hold the base on a shaft level in its cross section, not canted sidewise; for the shape of a level glass is such that, though true as adjusted on a flat surface, it will not be reliable when canted sidewise. Hence the value of the cross level, not only to test the truth of shafting, but other surfaces which tend to throw the level base into a canting position.

The base of this level has an improved concaved groove running through the length of its base, leaving a flat margin each side, which improves its seat for flat work, while forming an absolutely true and reliable seat for shafting, etc., and is better than a V groove.



6" and 8" sizes.




12" size. The 18" is similar, but with double plumb.

Engineers' and Plumbers' Levels
M188.




This represents an adjustable, incline level, a fixed level, and a plumb. The hinged tube inside the working faces of the frame, carrying a level glass, is adjustable to the graduated scale, and shows any incline by 32nds (or less) to 2" to the foot without interfering in the least with the plumb. A longitudinal groove in seat of frame (not shown in cut) adapts it to rest on a cylindrical shaft or pipe as well as on flat surfaces. Sizes: 10", 15".



Stanley Nickel Plated Pocket Level
M189.

Made of hexagon brass tube, nickelled and polished. Sizes: 2 1/2", 3 1/2". In Preston's and Starrett's makes.




M190.

Brass Tube Levels

Sizes: 2 1/2", 4".

Double Steel Squares



M191.

With hardened Head and Blades. This cut represents a double steel square, with a 2 1/2" sliding blade, and is especially designed for tool makers. The rule being narrow and instantly adjusted to any length, however short, allows it to be used where it would be impossible to use any square with a fixed blade. The blade is graduated on one side only, in 32nds and 64ths.


Fitted to go with this stock there is not only a bevel blade 45° on one end and 30° on the other, but a very narrow straight one, about 1/4" wide, highly appreciated by die-makers for squaring small holes, both of which blades will be sent with the square unless otherwise ordered.

Patent Double Square
M192.

With Hardened Blade.

A very practical Square for Machinists and Fine Tool Makers. The sliding scale makes it more valuable than a full set of the common kind, while the extra bevel blade shown in left-hand cut provides both Hexagon and Octagon Angles.

Sizes: 4", with both Blades; 6", with both Blades and level; 9", with level and ordinary Blade only; 12", with level and ordinary Blade only.




Engineers' Steel Squares
M193.

Graduated as above. Sizes: 2", 3", 4", 5", 6". Or plain, sizes: 3", 4", 5", 6", 7", 8".




Starrett's Improved Bevel
M194.



The stock is slotted as well as the blade, permitting of adjustments not obtainable with a common bevel. Length, 9".

English Steel Straight Edges



M195.

Made from Bright Hardened Steel, one bevel edge.

Length. Width. Thickness

Size A	12"	1 1/2"	15 W.G.
Size B	18"	1 1/2"	15 W.G.
Size C	24"	1 1/2"	15 W.G.
Size D	36"	1 1/2"	14 W.G.
Size E	48"	2"	13 W.G.
Size F	60"	2 1/2"	13 W.G.
Size G	72"	2 1/2"	12 W.G.

WE STOCK ALL ENGINEERS' AND PLUMBERS' REQUIREMENTS

STEEL TAPES

Rabone's Steel Tapes

In Leather Cases.
Flush Handles.

M196.

Marked Feet and Inches on one side and Decimals on other.
 $\frac{3}{8}$ " wide 33 feet, 66 feet, 100 feet.
 $\frac{1}{2}$ " wide 33 feet, 66 feet, 100 feet.
 Also in Nickel Cases—12, 18, 33 feet.

For Other Makes and Sizes, see page 146

STANLEY'S IMPROVED LEVELLING STAND M197.




FIG. 1




FIG. 2




FIG. 3

A Levelling Stand used in connection with a wood or iron level and a pair of level sights will be found in many cases a very satisfactory and inexpensive substitute for the more expensive surveyors' instruments. By its use one can readily determine levels from a given point to one at a distance, such as locating or setting the profiles for foundation work, ascertaining the proper grades for drains, ditches, etc.

The Base is also provided with three wings (H-Fig. 1) so that it can be attached to the legs of a tripod.

No. 39 Levelling Stand is a combination of the No. 38 Stand, a No. 36 12" Stanley Metal Level and a pair of No. 2 Stanley Level Sights. (See Fig. 3).

See also Pages 144 and 145 for Levels and Transits

Improved Mercury Plumb Bobs

(Starrett)

M199.

The improvement consists in our patented device for fastening the string without a knot to tie or untie, simply by drawing it into the peculiarly slotted neck at the top, after unwinding the required length, when the bob will hang perfectly true. These plumb bobs are made from solid steel, bored and filed with mercury. Noteworthy features are their great weight in proportion to size, low centre of gravity, small diameter, hardened and ground points, knurling on the body, and the simple and effective device at top for fastening end of line after winding up.

Nickel plated. Each is provided with a braided silk line.

Size A—4" long, $\frac{3}{8}$ " diameter, 3½ ozs.
 Size B—5" long, $\frac{1}{2}$ " diameter, 6 ozs.
 Size C—5½" long, $\frac{3}{4}$ " diameter, 12 ozs.
 Size D—6" long, 1" diameter, 16 ozs.



DANKS
for all
TOOLS



Preston's Brass Plumb Bobs

M200.

Size	Weight
00	1½ ozs.
0	2½ ozs.
1	3½ ozs.
2	4½ ozs.
3	6 ozs.
4	8 ozs.
5	10 ozs.
6	13 ozs.

Surveyors' Bands

M198.

On Frame. $\frac{1}{4}$ " wide.
Etched feet (inches in eighths) and Links. Every Foot and Link numbered.



Drill Blocks and Clamp

TWO DRILL BLOCKS

M201.—Clamp only.

M202.—Clamp and Blocks Complete.

These drill blocks and clamps are of cast iron material, sufficiently strong to stand any work they may be subjected to. The blocks are $1\frac{1}{2}$ " square and 2" long, and are furnished in pairs.


The clamp will hold a round piece up to $1\frac{1}{2}$ " diameter firmly in the groove of the blocks, for prick punching, drilling or laying out a series of holes before and while being drilled.



Key-Seat Clamps

M203.

Designed to transform any common steel scale into a key-seat rule; and a valuable addition to any machinist's kit. They are made of steel, case hardened and accurately ground. A pair weighs but an ounce. They may be put on or taken off almost instantly, and are a complete substitute for a more costly tool. They may be used with our Combination Square Blades or with any straight rule with accurate results.



HAMMERS . . .

Engineers' Solid Cast Steel Hammers

M204.

Ball Pein. St. Pein. Cross Pein.
 $\frac{1}{2}$ lb. to 2½ lbs.



Napping Hammers

M205.

Australian Pattern. Best Cast Steel.
 Weight: 14, 16, 18, 20, 22




Sledge Hammers

Solid Cast Steel

M206.

Straight Pein. Cross Pein.
 Double Pein.
 6 lbs. to 28 lbs.



Masons' Spalling Hammers

M207.

Solid Cast Steel. Polished Faces
 Weight: 2½ to 28 lbs.



PLEASE WRITE TO US FOR ANYTHING NOT LISTED IN THIS SECTION



M208.
Adjustable T Tap Wrenches

Very convenient for holding small drills or taps. The jaws are hardened and tempered.
Size A—Capacity to 7/32".
Size B—Capacity to 5/16".

Russell's Adjustable Tap Wrench



M209.

A Superior Tap Wrench, easily and quickly adjusted, strong and durable.

- No. 1.—7 inches long, to suit taps to 1/4".
- No. 2.—11 inches long, to suit taps 3/16" to 1/2".
- No. 3.—16 inches long, to suit taps 1/2" to 3/4".
- No. 4.—21 inches long, to suit taps 3/4" to 1".

M210. Engineers' Taps

Taper, Plug or Bottoming.



Taper.



Plug.



Bottoming.

(Corresponding with English Taper, Second and Plug.)

Sizes: 1/8", 3/16", 1/4", 5/16", 3/8", 7/16", 1/2", 9/16", 5/8", 3/4", 1", 1 1/8", 1 1/4", 1 1/2".

Walworth Ratchet Stocks and Dies



M211.

For W.I. Pipe. Capacity: 1/4", 3/8", 1/2", 3/4", 1".
Also Without Ratchet.

M212. Walworth Stocks and Dies

For W.I. Pipe

Very popular with Gas and Water Fitters on account of its genuine quality and moderate price.

No. 0—1/4" to 1", No. 1—1/4" to 1", No. 1 1/2—1/2" to 1 1/2", No. 2—1 1/2" to 2".

Stocks and Dies for Brass and Copper Tube

M213.

Without Tap.



Size A.—1/4", 3/8", 1/2". Size B.—1/4", 3/8", 1/2", 3/4". Size C.—1/4", 3/8", 1/2", 3/4", 1".

Full Mounted Lightning Screw Plates for Bolts

One Stock to each Die.

Will cut a full thread at one cut. Adjustable to size. Each Stock fitted with collet and die.



M214.

Sizes: 1/4", 5/16", 3/8", 7/16", 1/2", 9/16", 5/8", 3/4", 1".



M215.
Gas Fitters' Burner Tools



M216.
Folding 3-Way Square

Taps for Gas
M217.


Sizes: 1/8", 1/4", 3/8", 1/2", 3/4", 1", 1 1/8", 1 1/4", 1 1/2", 2".



M218.

Rimer Tap and Drill
Combined, for Gas

Sizes: 1/8", 1/4", 1", 1 1/4", 1 1/2" and 2".




M219. Adjustable Dies

Whitworth Thread

The cut represents a section of the Die and Guide, and shows the method of adjusting.

The flister-head screw on the left is cupped under the head and serves as a hinge, holding the die firmly together at this point. The screw on the right has a taper head, and, by means of this taper, when the screw is turned to the right the die is gradually forced open. On the other hand, when the screw is turned upwards, or to the left, the die is allowed to close. This form of adjustment, though extremely simple, is by far the best, for when the die is clamped in the elastic stock it is in reality a solid die.

All Dies 2 3/16" diameter, except 1 1/4" and 1 1/2", which are 2 1/8" diameter.



Section of Die and Guide.

Elastic Stocks

For Round Adjustable Dies

M220.



To suit Dies 13/16" 1" 1 15/32" and 1 1/2" 2 3/16" 2 3/16" 2 3/16"
Length 6 3/4" 9" 15" 18" 22" 29"

Oster Stocks and Dies

M221.


These celebrated Stocks and Dies are now well known and have practically superseded all others of the adjustable class. Briefly their advantages are: (1) Dies and Guides are self centering and quick opening, and are operated by cams each independent of the other. (2) Dies can be instantly released without running back over the work. (3) All sizes are easily worked, even up to 4". (4) Each set of Dies cuts two distinct sizes, Nos 0 to 4 have two handles, 5 and 6 four handles, 7 and 8 are fitted with Ratchet Gear.



Extra Dies stocked for all sizes.
Wrought Iron Pipe Thread.

No.	Screws Pipe	No.	Screws Pipe
101	1/4" to 1/2"	102R	1/4" to 1 1/4"
102	1/4" to 1 1/4"	103R	1" to 2"
103	1" to 2"	104R	1 1/4" to 2"
104	1 1/4" to 2"	104 1/2 R	1 1/4" to 2"
104 1/2	1 1/4" to 2"	105	1 1/2" to 3"
105	1 1/2" to 3"	105 1/2 R	1 1/2" to 3"
105 1/2	1 1/2" to 3"	107R	2 1/4" to 4"
107	2 1/4" to 4"	107 1/2 R	1 1/2" to 4"
107 1/2	1 1/2" to 4"	108	2 1/2" to 4"
108	2 1/2" to 4"		

WE STOCK ALL PLUMBERS' AND ELECTRICIANS' REQUIREMENTS



Screw Plates

With round adjustable dies. Whitworth Thread, 2", 2/16" diameter. Guides, Plug Taps, and Bascom adjustable Tap Wrench.

M222.—1/2" to 3/4", five sizes, stock 18" long, cuts 1/4", 5/16", 3/8", 7/16", 1/2", complete in case.

M223.—1/2" to 3/4", five sizes, stock 22" long, cuts 1/4", 5/16", 3/8", 7/16", 1/2", complete in case.

M224.—1/2" to 3/4", similar to above Set, but with the addition of 5/16" and 7/16".
M225.—1/2" to 1", nine sizes, stock 29" long, cuts 1/4", 5/16", 3/8", 7/16", 1/2", 5/8", 3/4", 7/8", 1". complete in case.

"Green River" Button Die Screw Plates

Whitworth Thread

Dies 13/16" diameter, adjustable, with one tap to each size, stocks and tap wrench, complete in case.

M226.—Five sizes: 1/4", 5/32", 3/16", 7/32", 1/2".
M227.—Six sizes: 1/4", 5/32", 3/16", 7/32", 1/2", 9/32".

M228.—Seven sizes: 7/64", 1/4", 9/64", 5/32", 3/16", 7/16", 1/2".



M229. Russell's Screw Plates

Noted for their fast cutting, easy adjustment, accuracy and durability. Taps and Dies made from best quality tool steel. The entire product is fully warranted, and any defective parts will be replaced free of charge. Dies interchangeable with G.T.D. Co. Sets.

M230. "Duo" Die Stocks (No. 220A). For Pipe.



The dies are adjustable and can be reversed in the collet to cut a close thread. The bushings are removable to pass couplings, etc. The dies rest on machined bearings. These bearings support the dies and insure accurate alignment.

The handles and stocks are threaded with Briggs' standard pipe thread, thus permitting their easy repair if threads should become stripped.

Regularly furnished with one Stock, two "Little Giant" Pipe Dies and two bushings.


British (Whitworth) standard right-hand taper threads at regular prices.

ORDER BY NUMBER

DO NOT CUT CATALOGUE

Tapping Sizes of Drills required for Engineers' Taps

Size of Engineers' Taps	1/16	3/32	1/8	5/32	3/16	7/32	1/2	5/16	3/8	7/16	1 1/8	9/16	5/8
Size of Drill required	3/64	1/16	3/32	1/8	9/64	11/64	13/64	1/4	5/16	23/64	13/32	15/32	17/32
Size of Engineers' Taps	11/16	3/4	13/16	1 1/16	15/16	1 1/8	1 1/4	1 1/2	1 3/4	1 7/8	1 11/8	1 13/8	1 15/8
Size of Drill required	19/32	41/64	45/64	1/2	13/16	55/64	31/32	1 1/32	1 3/16	1 5/16	1 11/32	1 17/32	1 19/32



Whitworth's Standard Thread

	Dia.	No. threads per in.	Dia.	No. threads per in.	Dia.	No. threads per in.	Dia.	No. threads per in.	Dia.	No. threads per in.
	1/2	20	3/4	12	1	10	1 1/4	7	1 1/2	5
	5/16	18	9/16	12	1 1/8	9	1 1/8	6	1 3/8	4 1/2
	3/8	16	5/8	11	1 1/4	8	1 1/4	6	2	4 1/2
	7/16	14	11/16	11	1 1/2	7	1 1/2	5	2 1/4	4

$p = \text{pitch} = \frac{1}{\text{No. threads per inch}}$
 $d = \text{depth} = p \times .64033$
 $r = \text{radius} = p \times .1373$


PLIERS
Wrenches
Spanners
etc.



Flat Nose Pliers

Best English Make.

M231.—Sizes: 4", 4 1/2", 5", 6", 7".



Glaziers' Pliers


M232.—Size: 8".



Combination Pliers with Side Cutter and Burner Hole

M233. Sizes: 5", 6", 7", 8".

M234.



Toggle Jointed End Cutting Nippers


Sizes: 6", 7", 8".



Round Nose Pliers

Best English Make. Bright.

M235.—Sizes: 4", 4 1/2", 5", 6", 7".



M236.


Long Chain or Snipe Nose Pliers

With or Without Side Cutters.
661131.—Sizes: 6", 7".


PLIERS - WRENCHES - SPANNERS

Solid Cast Steel Cutting Pliers

M237.—With Joint Cutter. Sizes: 5", 5½", 6", 7", 8"


Wrought Steel Gas Pliers

M238.—English make, with wire cutter, pipe opener and turnscrew. Sizes: 6", 7", 8", 9", 10".


Cone Pliers

M239.—Useful for Bicycle and Motor Work; 8-inch.

"Bernard" End Cutting Nippers


M240.—Nickel Plated. A very powerful Cutter. Sizes: 4", 5", 6", 7".

"Bernard" End Cutting Pliers

M241.—Nickel Plated. Sizes: 4½", 5½", 6½", 7½".

"Bernard" Flat Nose Pliers

M242.—Parallel Jaws, Open Throat. Sizes: 4", 4½", 5".


M243.
Starrett's End Cutting Nippers
 Adjustable Jaws, Cuts Hard Steel Wire. Size 5½".

Electricians' Pliers

M247.—Insulated Handles. Sizes: 6", 7", 8".


Diagonal Cutting Pliers

M248.—Box Joint. Sizes: 4½", 5", 5½", 6".

Huntsman's Nippers
M249.

Will cut No. 6 Gauge Wire. Sizes: 6", 7".

"Bernard" Round Nose Pliers

(Below on right)


M250.

Parallel Action, Nickel-plated. Sizes: 4", 4½", 5".


M251.

"Clyburn" Spanners

Made of Steel. Jaws Hardened.

 Length, 8"; opens, ¾".
 Length, 12"; opens, 1½".
 Length, 16"; opens, 1¾".
 Length, 20"; opens, 2".
 Length, 10"; opens, 1".
 Length, 14"; opens, 1½".
 Length, 18"; opens, 1¾".

Tower Cutting Nippers

M244.—Sizes: 6", 8", 10".


Wire Cutters

M245.—Very powerful; 7½" long.


Manchester Cutting Nippers

M246.—Sizes: 6", 8", 10".

FOR OTHER CUTTERS AND NIPPERS, SEE PAGES 183 AND 184



"Regular" Wood Handle Screw Wrenches
M252.
Lengths: 8", 10", 12".



Machinists' Knife Handle Screw Wrenches
M253.
A very strong wrench, with bar running right through handle.
Lengths: 6", 8", 10", 12", 15".




"King Dick" Bicycle Spanners
M254.



"Westcott" Adjustable Wrenches
M255.
A very convenient wrench for general use.
Length Opens Length Opens
8" 1" 12" 1 1/2"
10" 1 1/2" 14" 2"



Telescopic Box Spanners
M256.
In sets of three to take nuts from 1/2" to 1 1/2".



M258. Malleable Pipe Vise


No.	Takes Pipe
1	3/8" to 1"
2	1" to 1 1/4"
3	1 1/4" to 1 3/4"
4	1 3/4" to 2"
5	2" to 3"
6	3" to 4"

For bench and general shopwork.

"Erie" Pipe Vise
M257.

No.	Size
0	to 2"
1	to 2 1/2"
2	to 3 1/2"
3	to 4 1/2"
4	to 6"

This Vise is made of malleable iron, with steel jaws. It is very easily and quickly manipulated, and is in great demand amongst Plumbers and Engineers.




"STILLSON" PIPE WRENCHES
M259.


All Steel.			
Length	Takes Pipe	Length	Takes Pipe
18"	1/2" to 2"	36"	1/2" to 3 1/2"
24"	3/4" to 2 1/2"	48"	1" to 5"



M260. With Wood Handles.
Length Takes Pipe Length Takes Pipe
6" 1/2" to 1" 10" 1/2" to 1 1/2"
8" 3/4" to 1 1/4" 14" 1" to 1 1/2"




M262. Drop Forged Wrenches
Double End. 22 1/2" Angle.
No. Opening No. Opening
500 1/2" and 3/4" 503 1/2" and 7/16"
501 3/4" and 5/16" 504 7/16" and 1/2"
502 5/16" and 1/2"



M263. Engineers' Combination Wrench
Length: 10", 12", 15".
Takes Pipe: 1/2" to 1", 1" to 1 1/2", 1 1/2" to 2 1/4".




M264. "Footprint" Pipe Wrenches
Length To open Length To open
5 1/2" 1/16" to 1 1/2" 14" 1/2" to 3"
7" 1/8" to 1 1/2" 16" 3/4" to 3 1/2"
9" 1/4" to 2 1/2" 21" 1" to 4 1/2"
12" 1/2" to 3"



M265. "Footprint" Wrenches
All Steel.
Lengths: 4 1/2", 6", 12".



M266. Auto. Screw Wrenches
Hardened. Largely used by Motorists and Cyclists.
No. Size
1 5"
2 6 1/2"
3 8"



M267. "Vulcan" Bijaw Chain Pipe Wrenches
With Reversible Jaws.

No.	Length	Takes Pipe	No.	Length	Takes Pipe
31	20"	1/2" to 1 1/2"	33	37"	3/4" to 4"
32	27"	1" to 2 1/2"	33 1/2	44 1/2"	1" to 6"

M268.

"Vulcan" Chain Vise

The "Vulcan" Drop-forged Chain Pipe Vise is adapted alike for Bench and Post.

The "Vulcan" is strong, compact, quick in operation, and sure in its gripping qualities. Its compact form enables ready carriage in bag or hand to jobs away from the workshop.

A quick pitch screw on one side and chain pockets on the other enable a rapid adjustment.

All parts are made from wrought steel, and jaws are tempered for file-sharpening. The hand-made chains are same as used in the well-known "Vulcan" Pipe Wrench, which we stock

- No. 1 holds pipe 1/2" to 2".
- No. 2 holds pipe 1/2" to 4".
- No. 4 holds pipe 1/2" to 8".

A Most Efficient Vise for Holding Fittings.



OTHER VISES — PAGE 160

PLUMBERS' TOOLS, ONE OF OUR SPECIALITIES

BLACKSMITHS' AND FARRIERS' TOOLS



"No
Better
Made!"

The
Improved
"Bufco" Forge
M269.

This Fire Pan is stamped from a heavy steel plate on enormous presses, and is the strongest and best-looking hearth made for an inexpensive forge.

The blower supplied on this forge is the "Bufco," which is favourably known to the entire trade. Gear ratio of 36 to 1, pressed steel fan, dust tight gear case, and cut steel gears.

(O61) With 18" hearth.
(O62) With 20" hearth.



M272. Water Tye Irons


Sizes: 12", 13", 14", 15".



M273. Anvil Cutters

Blacksmiths' Bellows



M274.



Sizes: 20", 22", 24", 26", 28", 30", 32", 34", 36", 38", 40", 42".

M275. Blacksmiths' Anvils


In weights from 28 lbs.



M276. Blacksmiths' Leg Vise

Special Steel Jaws.

Size of Jaw: 4", 4½", 5", 5½", 6".
Approx weight: 50, 55, 75, 90, 112 lbs.




M270. Farriers' Knives



M277. Farriers' Pincers

Sizes: 10", 11", 12".



M271. Farriers' Buffers



M278. Blacksmiths' Tongs


All Patterns.

TINSMITHS' TOOLS



M279. Mathieson's Tinsmiths' Snips

Sizes: 8", 9", 10", 11", 12", 14".



M280. Cousins' Tinsmiths' Snips

Sizes: 8", 9", 10", 11", 12", 14".




M281. Mathieson's Tinsmiths' Snips

Sizes: 8", 9", 10", 11", 12", 14".




M282. Soldering Irons

Weight: 2, 1, 1½, 1¾, 2, 2½, 2¾, 3, 4, 5, lbs.



M283. Bent Snips

Sizes: 8", 9", 10", 11", 12".



M284. Cert Bow Shears

Sizes: 10", 12".

Tinsmiths' Hand Groovers

M285.


1", 3/16", ¼", 5/16", ¾", 1".



M286.

Tinsmiths' Hollow Punches

For punching holes in thin Sheet Metals.
Sizes: 1", 1½", 2", 2½", 3", 3½", 4", 4½", 5", 5½", 6", 6½", 7", 7½", 8", 8½", 9", 9½", 10", 10½", 11", 11½", 12", 12½", 13", 13½", 14", 14½", 15", 15½", 16", 16½", 17", 17½", 18", 18½", 19", 19½", 20", 20½", 21", 21½", 22", 22½", 23", 23½", 24", 24½", 25", 25½", 26", 26½", 27", 27½", 28", 28½", 29", 29½", 30", 30½", 31", 31½", 32", 32½", 33", 33½", 34", 34½", 35", 35½", 36", 36½", 37", 37½", 38", 38½", 39", 39½", 40", 40½", 41", 41½", 42", 42½", 43", 43½", 44", 44½", 45", 45½", 46", 46½", 47", 47½", 48", 48½", 49", 49½", 50", 50½", 51", 51½", 52", 52½", 53", 53½", 54", 54½", 55", 55½", 56", 56½", 57", 57½", 58", 58½", 59", 59½", 60", 60½", 61", 61½", 62", 62½", 63", 63½", 64", 64½", 65", 65½", 66", 66½", 67", 67½", 68", 68½", 69", 69½", 70", 70½", 71", 71½", 72", 72½", 73", 73½", 74", 74½", 75", 75½", 76", 76½", 77", 77½", 78", 78½", 79", 79½", 80", 80½", 81", 81½", 82", 82½", 83", 83½", 84", 84½", 85", 85½", 86", 86½", 87", 87½", 88", 88½", 89", 89½", 90", 90½", 91", 91½", 92", 92½", 93", 93½", 94", 94½", 95", 95½", 96", 96½", 97", 97½", 98", 98½", 99", 99½, 100".



M287.

Lead Ladles

Sizes: 3", 3½", 4", 4½", 5", 5½", 6", 6½", 7", 7½", 8", 8½", 9", 9½", 10", 10½", 11", 11½", 12", 12½", 13", 13½", 14", 14½", 15", 15½", 16", 16½", 17", 17½", 18", 18½", 19", 19½", 20", 20½", 21", 21½", 22", 22½", 23", 23½", 24", 24½", 25", 25½", 26", 26½", 27", 27½", 28", 28½", 29", 29½", 30", 30½", 31", 31½", 32", 32½", 33", 33½", 34", 34½", 35", 35½", 36", 36½", 37", 37½", 38", 38½", 39", 39½", 40", 40½", 41", 41½", 42", 42½", 43", 43½", 44", 44½", 45", 45½", 46", 46½", 47", 47½", 48", 48½", 49", 49½", 50", 50½", 51", 51½", 52", 52½", 53", 53½", 54", 54½", 55", 55½", 56", 56½", 57", 57½", 58", 58½", 59", 59½", 60", 60½", 61", 61½", 62", 62½", 63", 63½", 64", 64½", 65", 65½", 66", 66½", 67", 67½", 68", 68½", 69", 69½", 70", 70½", 71", 71½", 72", 72½", 73", 73½", 74", 74½", 75", 75½", 76", 76½", 77", 77½", 78", 78½", 79", 79½", 80", 80½", 81", 81½", 82", 82½", 83", 83½", 84", 84½", 85", 85½", 86", 86½", 87", 87½", 88", 88½", 89", 89½", 90", 90½", 91", 91½", 92", 92½", 93", 93½", 94", 94½", 95", 95½", 96", 96½", 97", 97½", 98", 98½", 99", 99½, 100".



CAST IRON METAL POTS


M288.

Sizes and Approximate Weights:
6", 7 lbs.; 7", 8 lbs.; 8", 18 lbs.;
9", 23 lbs.; 10", 25 lbs.; 12",
42 lbs.; 14", 65 lbs.

You can
depend on
DANKS!

ALWAYS BUY TOOLS BY REPUTABLE MAKERS

TINSMITHS' TOOLS (continued)



Shave Hooks
M289.
Heart Shape or Three Cornered.



Rivet Set
M290.
Sizes: 1/16", 1/8", 3/16", 1/4".

BLOW LAMPS, Etc.

"Aetna" Plumbers' Kerosene Blow Lamps

M291.

(As shown)

Made of Brass. Length of flame, 10". Burns about 1/2 pint kerosene per hour.
No. 2, 1 pint.
No. 7, 1/2 pint.



M292.

"Vesuvius" Painters' Kerosene Blow Lamps


Similar to the "Aetna", but with wider nozzle.
No. 2, capacity, 1 pint.



M293.

Benzine Blow Lamps

(Wickless). Made of Brass. For soldering or paint removing, 4" Flame, burns 3 1/2 to 4 hours.
May be used in any position. Thoroughly safe and reliable.



Plumbers' Spirit Blow Pipes
M294.

For making joints in lead and composition piping. Handier, cleaner, and more efficient than the ordinary candle.




Brass Blow Pipes
M295.

Sizes: 8-inch, 10-inch, 12-inch.

The Original "Primus" Brazing Lamps

M296.



This Lamp is the newest construction of Paraffin Brazing Lamps, and embodies all the good points of similar lamps and several new improvements in the burner, which is of a type that will last longer than any other. The Regulating Valve is of an improved type, so that the flame can immediately and completely be extinguished without releasing the air pressure in the tank.

No. 608 has the same Oil Tank as No. 607, but is provided with an extra large and strong Burner.

N.B.—An important feature is the whole-drawn Flame Cylinder, the thickness of which is increased 50 per cent. at points where exposed to the greatest heat.

TABLE No. 7507

Number	601	603	605	607
Capacity of Oil Tank, about pints	1	1 1/2	2 1/2	5 1/2
Diameter of Oil Tank, about ins.	3 1/4	3 3/4	4 1/4	5 1/2
Full Height ins.	7 1/4	8 3/4	10 1/4	14 1/4
Has Burner No.	R161	R162	R163	R164
Melts Copper Rods 2" long, and				
1/2" thick, by a pressure of 60 lbs., in min. . .	2.20	—	—	—
3/4" thick, by a pressure of 60 lbs., in min. . .	3.40	2 50	—	—
1" thick, by a pressure of 60-67 lbs., in min. . .	—	4 30	3 50	—
1 1/4" thick, by a pressure of 67-82-90 lbs., in min. . .	—	—	4.10	3 45
1 3/8" thick, by a pressure of 82-90 lbs., in min. . .	—	—	—	5.45
2" thick, by a pressure of 90 lbs., in min. . .	—	—	—	—
Length of flame, by ordinary pressure ins.	9	11	14	20
Consumption of Oil—				
Per hour, by a pressure of 60 lbs. pints	1 1/2	2	—	—
Per hour, by a pressure of 67 lbs. pints	—	—	3 1/2	—
Per hour, by a pressure of 90 lbs. pints	—	—	—	5 1/4
Weight, about lbs.	1 1/2	2 1/2	3 1/2	7 1/4

The Original "Primus" Blow Lamps

M297.




TABLE No. 7509

Number	631	632	633	634	635	636	637
Full Height ins.	6 1/4	8 1/2	8 1/2	10 1/4	10 1/4	7 1/4	7 1/4
Diameter of Oil Tank ins.	3 1/4	3 3/4	4 1/4	3 3/4	4 1/4	3 3/4	4 1/4
Capacity of Oil Tank, about pints	1/2	1	1 1/4	1	1 1/4	1	1 1/4
Has Burner No.	R152	R149	R148	R159	R158	R151	R150
Melts Copper Rods 2" long and 5/16" thick, by a pressure of 45 lbs. in min. . .	1.40	1.25	1.25	1.25	1.25	1.25	1.25
Length of flame, by ordinary pressure ins. . .	7	10	10	10	10	10	10
Consumption of oil per hour.							
by 30-lbs. pressure pints	3/8	3/4	3/4	3/4	3/4	3/4	3/4
Weight, about lbs.	1 1/2	2 1/4	2 1/4	2 1/2	3	2 1/2	2 1/4


WE OFFER A LARGE SELECTION OF TOOLS AT COMPETITIVE PRICES

ENGINEERS' CHISELS ...



Engineers' Chisels
M298.

Diamond Point. Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $1\frac{1}{2}$ ", $2\frac{1}{2}$ ".



Engineers' Chisels
M299.

Oval Pattern. Baker's celebrated make.
Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $1\frac{1}{2}$ ", $2\frac{1}{2}$ ", $3\frac{1}{2}$ ", $4\frac{1}{2}$ ".



Engineers' Chisels
M300.

Half-round. Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $1\frac{1}{2}$ ", $2\frac{1}{2}$ ".



Engineers' Cross Cut Chisels
M301.

Sizes: $\frac{1}{2}$ ", $1\frac{1}{2}$ ".

TUBE WHEELS



Barnes' Wheels
M302.

Sizes: 1, 2, 3, 4.

Chatwin's Tube Wheels
M303.

Sizes: 1, 2, 3, 4.




Barnes' 3-Wheel Tube Cutters
M305.

No. 1 cuts $\frac{1}{2}$ "-1"; No. 2 cuts $\frac{1}{2}$ "-2"; No. 3 cuts $1\frac{1}{2}$ "-3".

Jones' Patent Cutters
M304.

For Cast Iron Mains
(Chatwin's Make)

Extra Links and Pins Stocked.
Sizes: 2" to 4", 2" to 6".




MONKS' IRONMOULDERS' TOOLS




M306. Cleaners

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $1\frac{1}{2}$ ", $2\frac{1}{2}$ ".




Boss Tools
M307.

Sizes: $\frac{3}{4}$ " x 1", 1" x $1\frac{1}{2}$ ", $1\frac{1}{2}$ " x $1\frac{1}{2}$ ".




Upsets or Girder Tools
M308.

Sizes: $\frac{1}{2}$ " x $\frac{1}{2}$ ", $\frac{3}{4}$ " x $\frac{3}{4}$ ", $1\frac{1}{2}$ " x $1\frac{1}{2}$ ", $2\frac{1}{2}$ " x $2\frac{1}{2}$ ".



Flange Bead Upsets
M309.

Sizes: $\frac{1}{2}$ ", $1\frac{1}{2}$ ", $2\frac{1}{2}$ ".



Flange Cleaners
M310.

Sizes: $\frac{1}{2}$ ", $\frac{3}{4}$ ", $1\frac{1}{2}$ ", $2\frac{1}{2}$ ".



**Flange
Corner Smoother**
M311.

1" x $1\frac{1}{2}$ ", $1\frac{1}{2}$ " x $1\frac{1}{2}$ ", 2" x 2".




Heart and Square
M312.

Sizes: 2" x $1\frac{1}{2}$ ", $2\frac{1}{2}$ " x $1\frac{1}{2}$ ",
 $3\frac{1}{2}$ " x 2".


**Main
Layers'
Tools**
M313.

No. Name
7 Yarning Tool.
6 Caulking Tool.
5 Caulking Tool.
4 Colt's Foot
Chisel.
3 Cutting Chisel.
2 Diamond Point
Chisel.
1 Cold Chisel.




Fillet Smoothers
M314.

Sizes: $\frac{1}{2}$ " x $\frac{1}{2}$ ", $\frac{3}{4}$ " x 1, 1" x $1\frac{1}{2}$ ".



Moulders' Trowels
M315.

Sizes: 5" x 1", 6" x $1\frac{1}{2}$ ", 6" x $1\frac{1}{2}$ ".



Boss Cleaners
M316.

Sizes: $\frac{3}{4}$ ", $1\frac{1}{2}$ ", 1".



METALS

Lead in Ingots, Sheet, Pipe and Wire.

Copper in Ingots, Sheet, Tube, Rods and Wire.

Brass in Ingots, Sheet and Tubes.

Tin in Ingots and Pipe.

Babbitts, Velocite and other Bearing Metals.

Phosphor Bronze, Phosphor Tin, Regulus Metal.


Yellow Metal, Rod and Sheet, "Delta" Metal Rod.

Tobin's Bronze in Rods.

Brazing Metals, Spelter, Strip and Wire.

GIVE US AN OPPORTUNITY TO QUOTE FOR YOUR REQUIREMENTS

FOUNDRY BRUSHES




M317.

No. 61.—7½" x 2½". Hollow sides, round ends. Flat, hardened and tempered steel wire, medium strength. 2" Bristles. No straps.

M318.

No. 2.—8" x 2½" oblong. Flat, hardened steel wire Bristles, medium strength, 3" long. Leather straps.




M319.

No. 62.—7½" x 2½". Round ends. Flat, hardened and tempered steel wire. Medium strength. 3" Bristles. Fitted with slides to enable any degree of stiffness to be obtained. Leather straps.

M320.

No. 64.—7½" x 2½", straight sides, round ends. Flat, hardened and tempered steel wire, medium strength. 3" Bristles. Leather straps.

BRAZING BRUSHES



Specially tempered fine round steel wire.

M321.

No. 16.—4 row Brush, 6" x 1½", length overall 12", bent handles, metal backs, wire bristles 1½" long.

M322.

No. 112.—4 row brush, 6" x 1½", length overall 12", bent handles, extra stiff wire bristles 1½" long.

M323.

No. 44.—8" x 2½" oblong. Same as No. 2, but made with heavier and stiffer wire.

M324.

No. 33.—8" x 2½". Round ends, hollow sides with extra strong round steel wire 1½" long.

M325.

EMERY CLOTH.


M326.

EMERY POWDER.

M327.


Best English Silver Tool Steel, 13" lengths.

WASHER CUTTERS, ETC.



Double Washer Cutter
M328.

Cuts up to 10" diameter.



Double Washer Cutter
M329.

Cuts up to 5½" diameter.



M330.

Wad Punches

Sizes: 1", 9/16", 5/8", 11/16", 3/4", 13/16", 7/8", 1", 1 1/16", 1 1/8", 1 3/16", 1 1/4", 1 1/2", 1 3/4", 2".



Double Washer Cutter
M331.

Cuts up to 6" diameter.



Saddlers' Punches (Hand Forged)

M332.

NUMBERS AND SIZES:


Nos. 6, 3/16"; 7, 7/32"; 8, 1/4"; 9, 9/32"; 10, 5/16"; 11, 11/32"; 12, 3/8"; 13, 7/16"; 14, 1/2"; 15, 9/16"; 16, 5/8".

M333.

Bernard Nickelled Ticket Punches (Round).

M334.

Paragon Revolving Belt Punches (4 hole or 6 hole).



Belt and Strap Punch and Belt Marker.

M335.

A very small article that can be carried in the vest pocket, always ready. Lift the small stud, and push the cutter to whatever size required, from 1/16" hole to 13/32". In operation, push the blade right through the leather to size required, then one or two turns and the operation is completed.

"Stubs" Wire Gauge

M336.

Nos. 1-15, 16-30, 31-38, 39-46, 47-50, 51-54, 55-57, 58-60.

Fractional Sizes

M337.

1/16", 5/64", 3/32", 7/64", 1/4", 9/64", 5/32", 11/64", 3/16", 13/64", 7/32", 15/64", 1/2", 17/64", 9/32", 19/64", 5/16", 21/64", 11/32", 23/64", 3/8", 13/32", 7/16", 15/32", 1/2".

M338. MUSIC SPRING STEEL WIRE

Music Wire Gauge	5	6	7	8	9	10	11	12	13	14	15	16	17
Equivalent on Standard Gauge	28	28	27	25	24	23	22	21	21	21	20	20	20
Breaking Strain	—	—	—	—	—	160	182	223	250	280	310	351	382
Music Wire Gauge	18	19	20	21	22	23	24	25	26	27	28	29	30
Equivalent on Standard Wire Gauge	19	19	19	18	18	18	17	17	16	16	15	15	14
Breaking Strain	420	465	510	550	587	640	750	850	970	1000	1240	1240	1430



Engineers' Leather Tool Bags

Made from Strong Harness Leather. Stock Size.
Length, 16"; Width, 6"; Depth, 8".

M339.—As illustrated.

M340.—The same, with Lock and Key.

Engineers' Leather Tool Bags

Made from Strong Harness Leather. Stock Size.
Length, 16"; Width, 6"; Depth, 8".

M341.—As illustrated.

M342.—The same, with Lock and Key.

Other Sizes in either style made to order.

Wire Strainers - -
See next page for
Cutters, Pliers, etc.

Order by Number

Do Not Cut Catalogue

THE KILBURN WIRE STRAINER

M346.




Adapted for new or old fencing, and when applied to the latter the necessity of unloosening or cutting and splicing the wire is done away with. Barbed wire may be strained as readily as plain wire—cutting and splicing being unnecessary. The strainer is made of one solid piece, is self catching (the retaining finger prevents wire from unwinding), and by means of a small key, is turned like an auger.


REID'S "Titan" Wire Strainer

M347.

Can be used at or
between the Posts.




**OIL
CANS**



M343.

With Strong Folded Bottom, made of best charcoal tin plates. Copper spouts.


Sizes: ½ pint, 1-pint, 1-pint.



Braime's Fixed Spout Oil Cans

M344.

Similar to 661253, but with fixed spout.
Sizes: ½-pint, 1-pint, 1-pint.




Braime's Seamless Steel Oil Cans

M345.

Detachable Spouts.


Body made out of one sheet of steel without seam or joint, consequently they cannot leak. Fitted with patent double-slide grit excluder feed-hole. In ½, 1, 1 1/3, 2, 3, 1, pint.



**WALKER'S
WIRE
STRAINERS**

M348.

FOR LEAVING
ON THE
POSTS.




**"TARGET"
WIRE
STRAINER**

M349.

Light and Strong.
Certain in Action.

The "TARGET" is equally
effective for Plain or Barb
Wire.


QUOTES GLADLY GIVEN FOR LINES NOT LISTED



PAGE'S PATENT WIRE STRAINER
M350.


Will strain any wire, and enable the operator to tie any knot desired. Weight, 5 lbs. Fitted with Grips that will not damage the wire.

Full instructions with each Strainer.
Strong and durable—made of Forged Steel.




TELEGRAPH WIRE STRAINER AND VICE
M351.

Used extensively by Victorian Government for straining Telegraph Wires.



DONALD'S WIRE STRAINER
M352.

Full instructions sent with each Strainer.



"LOCK-GRIP" WIRE STRAINERS
M353.


The "Lock-Grip" is a most effective tool for straining all classes of wire under all conditions. One that will do its work. It gets a grip that will not slip nor damage the softest wire.

- The advantages of this Strainer are obvious, and may be summarised:—
1. It is strong, compact, solid and self-contained.
 2. No trouble with slipping wire.
 3. The wire being strained in a straight line, there is no loss of tension when Strainer is removed. An important point with steel wire.
 4. It is well and accurately made of best materials, necessary parts deeply case-hardened. No castings are used. Drop forgings and stampings throughout.
 5. It makes a very handy tool to carry in a car, and, with a length of good steel wire and small single pulley block, will extricate a car from almost any difficulty.


WIRE CUTTERS AND PLIERS



M354.
WIRE FENCING PLIERS—Sizes: 8 and 10 inch.



M355.
Huntsman's Nippers
Will cut
No. 6 Gauge
Wire.




Ironsides Patent Wire Cutter
M356.

For fencing and other thick wires. Being by far the most powerful single-hand wire cutter made. Will easily cut 5 and 6 gauge wire.

The "Elm City" Fence Pliers
M357.



All steel. Combines splicer, staple puller, wire cutter and hammer in one tool. The cutter will cut No. 7 wire.




Gripping
the Staple

Pulling
the Staple

Gripping the
wire before
Splicing

Splicing
Wire

SEE ALSO PAGES 175, 176 and 184



Single Handed
M358.

Two Handed
M359.

Compound Lever Bolt and Wire Cutters

High Quality, moderately priced cutters, designed especially to do a large variety of work which does not justify the buying of a larger and more expensive tool.

"Red Devil" Wire Fence Tool M360.




A good, inexpensive wire fence tool. Two single checked hammer heads. Two wire cutters, pipe grip and wire stretcher. Oval face, has two round holes to grip staples. Handles smooth, "No Pinch" scientific shape, low gun metal finish. Face of tool polished.

The Improved "RED DEVIL" WIRE FENCE TOOL M361.



EIGHT USEFUL TOOLS IN ONE!



661279 (1919).

8 TOOLS IN 1

Staple Puller
Hammer
Wrench
Wire Stretcher

Wire Cutter
Pincers
Wire Tier
Pipe Grip

This powerful tool ensures a better job, besides saving wire, staples and time. It drives, pulls or straightens staples and cuts, stretches and ties wire. In stringing barbed wire it protects the hands from barb stabs.

Forged from the highest grade tool steel. Giant strength and leverage. Two hammer heads, one single checked, the other double checked. Two effective cutters, pipe grip, pincers and wire stretcher. The tool has an oval face with heart-shaped openings to engage wire fence staples.

"No Pinch" Dentyne Knurled Handles, scientific shape. Gun metal finish. Polished head.

One size only, 10".

FENCING WIRE, ETC.

To meet your Fencing Requirements, the following Comprehensive Range of Plain and Barb Wires and Wire Nettings, etc., is stocked by our Hardware Department:—

Fencing Wire—Galvanised and Black in 4 to 8, 9 and 10 Gauges.

Special High Tensile Wires in 12½ and 14 Gauge with breaking strains of 850, 1140 and 1250 lbs.

Barb Wires—Galvanised in Iowa pattern, 12, 13 and 14 Gauges; Waukegan in 12½ and 14 Gauges.

Single Strand Barb Wire in 11 and 12 Gauge; particularly suitable for electric fences or any position where a light wire is necessary.

Fence Posts—"Star" in 5 ft., 5 ft. 6 in. and 6 ft. Lengths.

Wire Netting may be had in ½ in., ¾ in., 1 in., 1½ in., 1½ in., 1½ in., 2 in., 3 in. and 4 in. Mesh; widths from 12 ins. to 72 ins., covering all uses from chickens to sheep fencing.

Black and Galvanised Baling Wire in 4 to 16 Gauge is also stocked.

A full range of requisite fittings can be had, viz., Staples, Wire Netting Clips, Wool Bale Fasteners, Driving Caps.


Full Particulars in Hardware Section.

YOUR ENQUIRIES WILL BE WELCOMED.

WE SPECIALIZE IN COUNTRY ORDERS

"PENNSYLVANIA" LAWN MOWERS

Highest Quality.
Self Sharpening.



G1.

These Mowers are made of the best quality materials throughout. The Blades are made of specially and carefully tempered Crucible Tool Steel—the kind that is used for Chisels, Hatchets, or other tools requiring a keen edge.


The "Pennsylvania" Junior

G2.

Is of superior quality, fitted with a train of gears, which makes the whole machine last longer, and allows of the five cutting blades being placed so far back that they do not dig into the turf or make a rough cut if the wheels should run into an uneven spot on the lawn. This Mower is noted for its strength, service, and light running features. Low wheel: 8", 12", 14", 16"; High Wheel: 10", 15", 17".

QUALCAST MOTOR MOWER

G3.




With six 16" cuttings blades. Powered with 1½ h.p. 2-stroke engine with air cleaner and choke. Cuts cleanly and evenly at a rate of 3750 cuts per minute at quiet walking pace. Utterly dependable and amazingly economical. Write for fuller details.

"Pennsylvania" Lawn Trimmers


G4.

Made to meet the demand for a serviceable tool of the Mower type to take the place of grass shears and other devices for cutting the grass left at the edges of lawns after mowing. Will cut to within ½" from walls to tree trunks, and will mow any border which is wide enough to accommodate one wheel. Fitted with 5½" four-blade Cylinder, giving a 6" cut. Ball bearings.



**GARDEN
Tools & Needs**


G5.



"Philadelphia" Lawn Mowers

Genuine "Philadelphia" Lawn Mowers are strong and durable. The knives are made from the best Vanadium Crucible Tool Steel, possess fine cutting qualities, and are correctly fitted. The Roller bearings wear straight and evenly along their entire surface. The wear can be easily taken up, and the journals kept perfectly true. The Handles are made from well-seasoned, straight-grained Maple.

**QUALCAST
MOWERS**




G6.


Easy running, smooth cutting. Simple blade adjustment and bronze bearings. Five cutting blades suitable for all grasses. 10", 12", 14".

G7.

As above with Ball Bearings. 10, 12, 14, 16 inches.



DO NOT CUT CATALOGUE, QUOTE NUMBER AND PARTICULARS



SIRDAR

LAWN MOWERS

G8.

A highgrade lightweight Mower made from specially selected materials and designed to give long service under all conditions. Specially suited for Buffalo and Couch. Plain or Ball Bearing models. 10, 12 or 14 inches.

GRASS CATCHERS

G9.—"Pennsylvania."


G10.—"Philadelphia."

G11.—"Champion."

These Cutters are fitted with strong canvas sides, a galvanized bottom that will not sag, and strong supporting rods, which are so rigid that no other support is necessary. Can be instantly placed on or removed from the Mower. Sizes: 12", 14", 15", 16", 17".


NOTE

THESE THREE MOWERS STOCKED ONLY BY OUR SYDNEY HOUSE

NOTE


G12.—THE "BURNLEY"

A high grade Mower of medium weight. With six ball bearings, light running, and designed for heavy service. 12, 14, 16 and 18 inches.



G13.—THE "PREMIER"

Specially suited for buffalo and couch, and ideal for spongy lawns. 10 inch wheel. Ball bearings. 12, 14 and 16 inches.



G14.—THE "SENIOR"

This machine has a chain of gears on each side, ensuring a positive drive under all conditions. Ball bearing. 12, 14 and 16 inches.

SPARE PARTS FOR ALL MOWERS LISTED HERE ARE ALWAYS AVAILABLE

WHEELBARROWS - - - Sydney House Only



G15.


QUICK TIP CONCRETE BARROW

Roller Bearing Axle, Pneumatic Tyres, and Patent tipping action.

G16.

THORNSETT PATENT BARROW

Self Loading, Easy Tipping Tray. 29" x 20". Flat Steel Frame. Rubber Grip Handles. I.R. Tyred Disc Wheels. Weight, 40 lbs.



G17. (below).


GARDEN BARROW

Three-quarter inch Tubular Frame Tray. 27" x 23" with heavy side straps. Wrought Steel Wheel. Weight, 52 lbs.

G18.

LADIES' GARDEN BARROW

Half-inch Tubular Steel Frame, Steel Tray. 23" x 20". I.R. Tyred or Wrought Steel Wheel. Weight, 23 lbs.



Melbourne House - - - Barrows - - - Page 188

WE APPRECIATE YOUR ORDER WHETHER LARGE OR SMALL

Rollers and Wheelbarrows

DO NOT CUT
CATALOGUE


ORDER BY
NUMBER

ALL CONCRETE SOLID ROLLERS

G19. (at right)


Durable and serviceable. 24 ins. x 19 ins.
Weighs $4\frac{1}{2}$ cwt.

Also G20, Domestic size, 18 ins. Face x
12 ins. Diam. $1\frac{1}{2}$ cwt.



G21.—CONCRETE BARROW

One inch Tubular
Steel or Wood Frame.
Tray specially strap-
ped for concrete work.
Continuation of frame
round wheel serves as
pivot for tipping. 5
cub. ft. Weight,
80 lbs.



STEEL FACE, WATER BALLAST CONCRETE INTERNAL (above)

- G22.—24 in. Face, 24 in. Diam. $4\frac{1}{2}$ -6 cwt.
G23.—24 in. Face, 18 in. Diam. $3\frac{3}{4}$ - $4\frac{1}{2}$ cwt.
G24.—18 in. Face, 24 in. Diam. $4\frac{1}{2}$ -5 cwt.
G25.—18 in. Face, 18 in. Diam. 3 - $3\frac{1}{2}$ cwt.

STEEL FACE, SOLID

- G26.—18 in. Face, 14 in. Diam. $2\frac{1}{2}$ cwt.
G27.—18 in. Face, 12 in. Diam. $1\frac{3}{4}$ cwt.
G28.—16 $\frac{1}{2}$ in. Face, 11 $\frac{1}{2}$ in. Diam. $1\frac{1}{4}$ cwt.



G29.—Three-quarter inch Tubular Steel
Frame. Tray, 26 x 23 inch. Solid
Wrought Steel Wheel. Weight, 32 lbs.

G30. (at right) NAVY BARROW

G30.—One inch Tubular Steel
Frame, Seamless Tray with
strong Steel Wire edges.
Wheel, Flat Mild Steel with
Cast Iron Box. Heavy Bolt
Axle. 3 cub. ft. Weight,
56 lbs.

G31. — 4 cub. ft. Weight,
60 lbs.

G32.—3 cub. ft., Painted Tray,
with Pneumatic Tyre Wheels.
G33.—4 cub. ft., Painted Tray,
with Pneumatic Tyre Wheels.




Painted or Galv. Trays

G34. (at right)

DOUBLE CYLINDER ROLLER

Best make, 20 in. Diameter, weighing
 $3\frac{1}{4}$ cwt.

Also G35, larger size, 22 in. Diameter,
weighing 4 cwt.



NOTE.—The Barrows illustrated on this page are obtainable
ONLY from our SYDNEY HOUSE.

See Next Page for Barrows stocked by
MELBOURNE HOUSE

LET US QUOTE YOU FOR YOUR GARDEN REQUIREMENTS

Wheel Barrows

**G36.
GARDEN
WHEELBARROW**

Made of 24 gauge
Galvanized Iron.
Capacity, 3 cub. ft.



G37.

**CONCRETE
BARROW**



Made of 18 gauge
Galvanized Iron.
Rubber Tyred Wheel.
Capacity,
approx. 5 cub. ft.
(dry).

G38.

**LIGHT
CONCRETE
BARROW**

Made of Painted
Galvanized Iron.


Capacity,
2½ cub. ft. (wet).
3 cub. ft. (dry).



G39.

HEAVY NAVVY BARROW

Made of 18 gauge Galvanized Iron.
Capacity, 3 cub. ft. (dry).



G40.

WOODEN GARDEN BARROW


Made with Kauri Top & Hardwood Frame.
Iron Wheel with Chilled Hub.

Well constructed to stand hard wear.

Size No. 2: Large.

Size No. 3: Small.

Size No. 4: Youth's Special.



G41.

WOODEN NAVVY BARROW

Made with Kauri Top & Hardwood Frame.
Iron Wheel with Chilled Hub.

Well constructed to stand hard wear.

Size No. 1: Heavy.

SEE ALSO NEXT PAGE



G42.

**WHEELS FOR
BARROWS**

Sizes: 10" x 1".
12" x 1½".
14" x 1½".
16" x 1½".
18" x 1½".
18" x 2".




G43.

CONCRETE BARROW

Made of 18 gauge Galvanized Iron.
Steel Wheel. Capacity, 5 cub. ft. (dry).

THE LOWEST PRICE IS NOT ALWAYS ECONOMICAL

SPADES and SHOVELS



G44. Brade's Improved Shovels
Hammered Steel, Rivetless. Blades, Black Finish.
Sizes: 0, 1, 2, 3.
In D Handle and Long Handle Types.



G45. Parke's Open Socket Steel Shovels
Stamped out of Sheet Steel. Light and Strong. Wheel Brand.
Round Mouth. Sizes: 3 and 4. In D and Long Handle Types.



G46. Corn Scoop
Riveted Black. Sizes: 3, 4, 5, 6, 7, 8.



G47. Locomotive Shovel
Crutch Handle.



G48. Long Handled Round Mouth Shovel
Sizes: 2 to 5.



G49. Long Handled Square Mouth Shovel
Sizes: 2 to 5.


ALSO STOCKED (SYDNEY):
Parke's Forks, Spades, Shovels



G50. Post-hole Spade Strapped Bright.



G51. Skelton's Solid Steel Garden Spades
No. 1—11½" x 7". No. 2—12" x 7½".




G52. Brade's Socket Garden Spades
All Steel. Hollow Back. Turnover Tread.



G53. Stamped Steel Spade
Turnover Treads. Sizes: 0, 1, 2, 3.




G54. Border Spade
Strapped, 5½" x 9".



G55. Ladies' Light Border Spade



G56. Post-hole Tool
Treaded, 6½" x 5" x 14".




No. 2 Parke's Long Handled Garden Spades
G57.

DANKS SUPPLY ALL GARDENERS REQUIREMENTS AT REASONABLE PRICES

FORKS




G58. Garden Forks
Solid Steel, Strapped, Square Prongs. 4-Prong. 5-Prong.



G59. Spading Forks
4-Prong. 5-Prong.



G60. Border Fork, Light, T and D Handle



G61. Long Handle, Hollow Tanged




G62. Short Handle, Hollow Tanged



G63. Long Handle, Socket



G64. Short Handle, Socket



G65. Combined Rake and Hoe. Also Head only



G66. Long Handle, Socket



G70. Short Handle, Socket
G71. Short Handle, Riveted



G67. Skelton's Solid Steel Garden Tools in Sets



G68. Tasmanian Pattern Brade's Potato Fork
5-Prong.



G69. Ladies' Garden Hoes
All Steel. Ash Handled. Sizes: 5", 6".


Also Stocked (Sydney)
PARKE'S FORKS, SPADES, SHOVELS

TOOLS FOR THE HOME GARDENER


HOES—Continued:



Garden Hoes
G72.
6", 6½" 7" 7½".



Light Vine Hoes
G73.



Planters' Hoes
G74.

No. 00—6" x 7"
No. 0—6½" x 7½"
No. 1—6¾" x 7¾"
No. 2—6¾" x 8"



Burr Hoes
G75.
6" and 4½".



Vine Hoes
G76.
3 and 4 Prong.



Garden Hoes
G77.
5", 6", 7", 8".




Portarlington Hoes
G78.
Sizes:
5", 5½", 6", 6½", 7".



Dutch Hoes
G79.
Sizes: 4", 5", 6", 7",
8", 10".



All Steel Potato Drags
G80.
Ash handles; 4 prongs.



"Norcross" Cultivator Hoes
G83.
3-prong (as illustrated).
Does similar work to the 5-prong pattern.

G84. "Midget."
Fitted with 9 in. handle, and intended for
cultivating small vegetation, where a long
handle would be unsuitable. Excellent for
strawberry beds, etc.

G85. 5-prong.
By removing centre prong,
rows of small plants can be
closely weeded and cultivated.
With centre prong removed
and other four reversed, it
forms a potato digger. 4 ft.
handle.

DO NOT CUT
CATALOG—ORDER BY
NUMBER



Thistle Hoes
G86.
3".




Rabbiters' Hoes
G87.



Pick-eye Grubbing Hoes
G88.
3½ and 4 lbs.



English Mattocks
G89.
Long or Short
Cutter
4, 4½, 5 lbs.



Dock Lifters or Daisy Grubbers
G81.
10" and 24".


Turf Edgers (All Steel)
G82.
Ash Handle. With Tempered Blade.

GARDEN RAKES



Garden Rakes
G91.

10, 12, 14, 16 Flat Teeth.
In Steel or Malleable.



Steel Garden Rakes
G92.
10, 11, 12, 14 16 Bow Teeth.



Unhandled Garden Rakes
G90.
12, 14, 16 Teeth.

QUALITY IS OUR WATCHWORD



G93. BRADES' DOUBLE-ENDED ROAD PICKS
5 lbs., 6 lbs., 7 lbs.




G94. BRADES' DOUBLE-ENDED PICKS
Sizes: 4 lbs., 5 lbs., 6 lbs., 7 lbs.




G95. BRADES' MINERS' PICKS
Sizes: 3½ lbs., 4 lbs., 4½ lbs.

Pruning Needs

G96.
Disston's "Little
Giant" Pruner
Supplied with or without
Saw.



G97.
Duplex Pruning Saws
Sizes: 14" and 16".



G98.
Adelaide Pruning Saws
Sizes: 12" and 14".



G99.
Lopping Shears
English Make.

G100. Seccateurs

No. 10, 6", Rose Shears.
No. 100, 9" Medium Quality
No. 30, 9" Heavy Quality
No. 130, 9" Checkspring, black finish.
No. 140, 9" Checkspring, nickel finish.
No. 240, 9" Check Brass Spring, nickel finish.
Reiser's Celebrated Make.



Shears




G101. Best English Garden Shears (Notched)
Sizes: 8", 9", 10", 12"



G102.
Ladies'
Garden
Shears

G103.
Grass
Shears

Bent Handles.



G104.
Best English Border Shears
With Wheel, or without; 8" and 9".



SPADE OR FORK HANDLES

G105.
"D" Shovel Handles
Bent. Straight.


G106.
Rake Handles
Sizes: 5 ft., 5½ ft., 6 ft.

G107.
Plantation Hoe
Handles
4 feet.
Dia.: 1½", 1¾", 2", 2¼".



G108.
Spade or Shovel
"D" Handles
Malleable Iron.
Wood Grip.


G109. Pick
Handles



DO NOT
CUT
CATALOG.
ORDER BY
NUMBER

WE STOCK ALL ORCHARDISTS' AND GARDENERS' REQUIREMENTS

SCYTHES



TYZACK'S SCYTHE BLADES
G110.

Riveted Back, 34", 36", 38" 40".

G111.
**TYZACK'S
BRAMBLE
SCYTHE
BLADES**




26 inch.



SCYTHE HANDLES

G112.


American Patent Fastening.



**REAPING
HOOKS—**

G113.

No. 2
No. 3



SICKLES

G114.

Best Quality,
with Serrated Edge

No. 3
No. 4



G115.


Light Fern Hook



G116.


Bagging Hook

Sizes: Nos. 4, 5, 6.




G117.

Gippslander Hook



G118.

**Specially Shaped
Heavy Fern Hook**



G119.

**Medium "Whipper"
Type Hook**


SCYTHE STONES



Carborundum Scythe Stones
G120.



Waterloo Scythe Stones
G121.



SEE ALSO TOOL SECTION,
Pages 151 and 152.

**GRINDSTONES
ON STAND**

G123.

COMPLETE WITH TREADLE AND
HANDLE.

Sizes: 14", 16", 18", 20", 22", 24".

FOR STANDS ONLY, See Page 151.



G122.

Indian Pond Scythe Stone

Electric Hay Knife

G124.



SEE ALSO TOOL SECTION — PAGE 151

TOOLS FOR THE MAN ON THE LAND

Item	Page	Item	Page	Item	Page	Item	Page
Electric Lamps, Table & Standard	66	Gauges, Screw and Pitch	166	Jacks, Bumper Bar Type	131	Matching Pieces	6, 27
" Lighting Units	67, 68, 70	" Surface	167	" Hydraulic Quick Lift	130	Mattocks	191
" Radiators	63, 65	" Thickness	166	" Lifting	161	Mauls, Handled	142
" Radios, "Breville"	72	Gauge Drill and Steel Wire	169	" Motor, Plain and Ball-Bearing	130	Maul Rings	142
" Ranges, "McClary"	58, 59, 60	" Expansion Tank	19	" J.D." Garage Assortment	130	Metals	30, 180
" "Moffat"	61	" Glass Protector	19	" J.D." Quality Motor Products	128	" Weights of	28
" Refrigerators, "Electro"	71	" Jobber's Drill	169	Jet, Concussion	22	Metal Pots, C.I.	178
" Vacuum Cleaners	74	" Marking, Mortice and Cutting	146	Jets and Cones	22	Meters, Water	26, 27
Enamels	99, 100	" Mountings	19	Jointers, Bed	154	Methylated Spirits	101
Enamel Tint Card, VIII., Paint Section		" Sliding Calliper	169	" Cross	154	"Midget" Steam Trap	19
Enamelled House Numbers	116	" Tap and Drill	169	Joints, Expansion	18	Mill White	102
" Signs	116	" Water	19	Junctions, Brass	8	Mirrors	53
Engineers' Chisels	180	" Wire Standard	169	" C.I. Sewer	14	Mirror Arms	116
Everette Compression Coupling	8	" Wire, "Stubs"	181	" Mall. Iron	24	" and Glass Clip	116
Expanded Metal	123	Gimlets	148	Kalsomine	100	" Movements	116
Expansion Joint	18	Glacie Cord	123	" See Coloured Page, Paint Section		Mitra Boxes	150
" Plugs	12	Glass Plates	116	Kerosene	100	" Templates	150
Extension, C.I. Sewer	15	Globe Valves	17	" "Wesco."		Molasses, Gate	2
" Ladders	101	Glue Pots, Cast Iron	146	Keys, Cutting	109	Motor Accessories, Alphabetical List	127 to 130
" Pieces	6, 7, 10	Glues, Liquid, Powdered & Sheet	103	" Fireman's	27	Motor Horns	133
F.		Glycerine	100	" Sluice Valve	21	" Oil	133
"Fabrex" Cloth	96	Gauges, Woodworkers'	134	Key Seat Clamps	173	" Products, "J.D." Quality	128
Fanlight Openers	115	Graphite	24	Knobs, Shutter	117	" Pumps, "Rega"	133
Fanlight Buffers	178	Grates	16	Lacquers	100	Muffler, Steam	20
" Knives	178	" Coke	92, 93	Ladles	178	Music, Spring Steel Wire	182
" Pincers	178	" Furnace, Copper or Stove	93	Ladders	101	N.	
Faucet, Sanitary Drinking	55	" Interior	90	Lagging, Asbestos	25	Nails, Roofing	120, 121
Fence Charger, "Big Six"	79	Gratings	10	Lamps, "NOX" Electric	74	" Wire	121
Fencing Requirements	124	Grinders	152	" "Tilley" Kerosene	94	Nail Puller	141
" Posts, Iron	124	Grinding Heads	161	Latches, Door	109, 111	" Sets	146
Ferrules, Brass	10	Grindstones	151, 193	" Gate	114	Name Plates	116
Ferrule Unions	5	Grindstone Stand and Mounting	151	Lathes, Bench	156	Needle Valves	17
Filter Cocks	4	Ground Vent, C.I. Sewer	15	Lavatory Door Fittings	112	Nipples, Brass	9
Filters, "Coo-ee" Pressure	55	Gullies, Brass	10	Lawn Mowers	185, 186	" Brazing Metal	7
" "Rapid" Pressure	55	" C.I. Sewer	15	Lead, Bends	11	" Malleable Iron	23
Filter, Pressure Candles	55	" "Palazzi"	10	" Caps	11	" Rathbone	23
Files, Saw	153	Gun Metal Bosses	8	" Cones	11	" Wrought Iron	23, 24
" Various	163	" Unions	8	" Damncourse	29	Nuts	120
Fire Brigade "Y" Pieces	27	H.		" Ladles	178	" Hexagon Bright Steel	131
Fire Hose	27	Hack Saws	162	" Main Connections	23	" Castellated Bright Steel	131
" Cocks	27	Hair Felt	26	" Pipe	29	O.	
" Directors	27	Hammers	142	" Seals	11	Offsets, C.I. Sewer	15
" Unions	27	" Brick, Slaters'	155	" Sheet	29	Oil Cans	149, 182
Fire Hydrants	27	" Engineers', Masons'	173	" Sockets	11	Oil Fittings: Tees, Elbows, Unions, etc.	126, 127, 128
Fire Plugs	22	" Napping, Sledge	173	" Tacks	11	Oil Castor	102
" Covers	22	Handles, Box	117	" Tennis Court Lines	29	" Linseed	102
" Flanges	22	" for Axes, Hammers, Sledges	142	" Traps	11	" Neatsfoot	102
Fireman's Keys	27	" for Files	163	" Wire	29	" "Salamander" Motor	133
Flanges, Brass	9	" for Forks and Spades	192	" Wnol	29	" Stones	151
" C.I. for Fire Plugs	22	" Picks	192	Lead, White and Red	101	" Stove	94
" Mall. Iron	24	Hasps and Staples	113	Leather Belting	24	" Syphon	20
" Wrought Iron	24	Hatch Boxes, C.I.	22	Letter Plates	111	Outlets	3
Flap Vents	15	Hay Knife	193	Levelling Instruments	144	Oven for Kerosene Stove	93
Flaring Tool	16	Hemp Packing	25	" Stands	144, 173	P.	
Flexible Metal Tubing	133	Hessian	96	Levels	144, 172	Packings	25, 26
Float Valve	5	Hinges	111, 112	Level, Pocket, Canvas	153	Pad Bolts	113
Floor Coverings	107	Hoes, Garden	190, 191	Lifting Jacks	161	Padlocks	113
Floor Wastes	10	Holdfasts	121	Lift Pumps	13	Paints and Painters' Requisites	97 to 106
Fluming, Galv. Steel	46	Hooks, Cabin	118	Lightning Conductor Tridents	8	Paint, Aluminium	97
Flushers, "Hush"	13, 57	" Cleat	119	Lime and Limb	100	" "Asbeskote"	107
Flush Pipes, S.I.	11	" Cup	118	Lines, Bricklayers'	155	" Ormonoid Black	107
" Clips	11	" and Eyes	118	Line, Pins Steel	154	" Ormonoid Red	107
Flush Rings	117	" and Eyes for Leather Belting	118	Locks, Cupboard, Door and Drawer	109, 110	" Paving	103
Fly Doors	123	" Fern	193	" Carriage Door	114	" Ready Mixed	102
" Wire	123	" Hat and Coat	116	Locknuts, Brass	9	" Roof	103
Fluxite Solder Paste	25	" Reaping	193	" Mall. Iron	24	" Tint Card	Pages I. & V.
Followers	163	" Screw	121	" Wrought Iron	24	Painters' Brushware	97, 98
Force Cups	13	" Wardrobe	116	Locksets, Mortice	110	"Palazzi" Brass Gullies	10
" Pumps	13	Horns, Motor	133	"Lomoto" Packing	26	Pans, Pedestal	56
Forge, Blacksmith's	178	Hose Clamps	133	Lubricators	20	" Slop Hopper	56
Forks, Garden	190	" Connections	32	M.		Pasta, "Stix" Cold Water	96
Fountain Cocks	4	" Bracket, Fire	27	Main Clips	22	Pencils, Carpenters'	134
" Hot Water	94	" Garden	33	Main Layers' Tools	180	Penetrene	24
" Sanitary, Drinking	55	Hospital Cocks	5	Malleable Iron Bushes	23	Pet Cocks	18
Furniture Polish	100	Hot Water Fittings	4, 7	" Caps	22	Petrol Fittings: Elbows, Tees, Unions, etc.	126, 127, 128
G.		"Hush" Flushers	13, 57	" Crosses	23, 24	Petrol Taps	128
Galvanised Iron Products	121, 122	Hydrants	22, 27	" Elbows	23, 24	Phenyle	104
Garage Assortment, "J.D."	130	" Caps	27	" Locknuts	24	Picks	192
Garage Door Fittings	119	" 1" Stand. Pipe	16	" Nipples	23	Picture Hangers	118
" Swivel	8	I.		" Plugs	24	" Hooks	118
Garden Forks	190	Indicator, Speed	167	" Sockets	24	" Wire	118
" Hoes	190, 191	" Test	167	" Tees	23, 24	Pincers	178
" Rakes	190, 191	" Dial Test	168	" Unions	23	" Carpenters'	141
" Rollers	187	Information for Builders and Carpenters	153	" "Y" Pieces	24	Pipe Cutters	180
" Spades	189	" Home Decorators	96	Mallets, Bossing	163	" Wheels	180
Gas Electric Stoves	62	" Pumps	37	" Carpenter's	141	Pipe Joint Compound	25
" Fitters' Tools	174	" Useful	28, 30, 31	" Tinsmith's	163	Pipes, Compo., Lead and Tin	29
" Fittings, Brass	25	" White Rose Boilers	80	Manhole Steps	12	" Soil	15, 29
" Rings	93	Injectors	19	Marking Gauges	146	" Water, Sizes of	31
" Stoves	91	" Bi-Sulphide	28			" W. Iron, Weights of	37
" Valves	17	Inlets, C.I. Sewer	15				
Gate Valves	17	Iron Cement	26				
Gauges	20	Iron Fire Places	122				
" Centre	166	Iron, Galvanised Products	121, 122				
" Depth	167	Ironmoulders' Tools	180				
" Feeler	166						
" Fillet and Radius	166						

